



This is a digital copy of a book that was preserved for generations on library shelves before it was carefully scanned by Google as part of a project to make the world's books discoverable online.

It has survived long enough for the copyright to expire and the book to enter the public domain. A public domain book is one that was never subject to copyright or whose legal copyright term has expired. Whether a book is in the public domain may vary country to country. Public domain books are our gateways to the past, representing a wealth of history, culture and knowledge that's often difficult to discover.

Marks, notations and other marginalia present in the original volume will appear in this file - a reminder of this book's long journey from the publisher to a library and finally to you.

Usage guidelines

Google is proud to partner with libraries to digitize public domain materials and make them widely accessible. Public domain books belong to the public and we are merely their custodians. Nevertheless, this work is expensive, so in order to keep providing this resource, we have taken steps to prevent abuse by commercial parties, including placing technical restrictions on automated querying.

We also ask that you:

- + *Make non-commercial use of the files* We designed Google Book Search for use by individuals, and we request that you use these files for personal, non-commercial purposes.
- + *Refrain from automated querying* Do not send automated queries of any sort to Google's system: If you are conducting research on machine translation, optical character recognition or other areas where access to a large amount of text is helpful, please contact us. We encourage the use of public domain materials for these purposes and may be able to help.
- + *Maintain attribution* The Google "watermark" you see on each file is essential for informing people about this project and helping them find additional materials through Google Book Search. Please do not remove it.
- + *Keep it legal* Whatever your use, remember that you are responsible for ensuring that what you are doing is legal. Do not assume that just because we believe a book is in the public domain for users in the United States, that the work is also in the public domain for users in other countries. Whether a book is still in copyright varies from country to country, and we can't offer guidance on whether any specific use of any specific book is allowed. Please do not assume that a book's appearance in Google Book Search means it can be used in any manner anywhere in the world. Copyright infringement liability can be quite severe.

About Google Book Search

Google's mission is to organize the world's information and to make it universally accessible and useful. Google Book Search helps readers discover the world's books while helping authors and publishers reach new audiences. You can search through the full text of this book on the web at <http://books.google.com/>

THE ANTIQUARY'S
BOOKS

14 DAYS
BOOK

Acc 618.6

A

Harvard College
Library



FROM THE BEQUEST OF

Lucy Osgood

OF MEDFORD, MASSACHUSETTS

THE ANTIQUARY'S BOOKS
GENERAL EDITOR: J. CHARLES COX, LL.D., F.S.A.

CELTIC ART IN PAGAN
AND CHRISTIAN TIMES

©

CELTIC ART IN PAGAN AND CHRISTIAN TIMES


BY

J. ROMILLY ALLEN, F.S.A.

WITH NUMEROUS ILLUSTRATIONS

METHUEN & CO.
36 ESSEX STREET W.C.
LONDON
1904

Enc. 618.6
A



Lucy S. ...

First Published in 1904

CONTENTS

	PAGE
PREFACE	XV
CHAPTER I	
THE CONTINENTAL CELTS AND HOW THEY CAME TO BRITAIN	I
CHAPTER II	
PAGAN CELTIC ART IN THE BRONZE AGE	22
CHAPTER III	
PAGAN CELTIC ART IN THE EARLY IRON AGE	61
CHAPTER IV	
PAGAN CELTIC ART IN THE EARLY IRON AGE	90
CHAPTER V	
PAGAN CELTIC ART IN THE EARLY IRON AGE	129
CHAPTER VI	
CELTIC ART OF THE CHRISTIAN PERIOD	162
CHAPTER VII	
CELTIC ART OF THE CHRISTIAN PERIOD	232
CHAPTER VIII	
CELTIC ART OF THE CHRISTIAN PERIOD	254
INDEX	305

LIST OF ILLUSTRATIONS IN THE TEXT

	PAGE
The Hallstatt Sword	8
Ornament on bronze sword-sheath from La Tène	11
Gaulish helmet of bronze from Gorge-Meillet	12
Chevron patterns of the Bronze Age	27-36
Bronze spear-heads ornamented with rows of dots	39
Gold lunula from Killarney	40
Longitudinal section of chamber and passage of Tumulus at Newgrange, Co. Meath	45
Plan of chamber and passage of Tumulus at Newgrange, Co. Meath	47
Spiral ornament at Newgrange, Co. Meath	48
Slab with spiral ornament outside entrance to passage of Tumulus at Newgrange, Co. Meath	49
Spiral ornament on bronze axe-head from Denmark	51
Bronze axe-head with spiral ornament from Sweden	52
Winding band (curved swastika), sculptured on rock near Ilkley, Yorkshire	58
Cup-and-ring sculptures on rock at Ilkley, Yorkshire	59
Bronze sword-sheaths from Hunsbury	97
Silver-gilt fibulæ found in Northumberland	104
Bronze beaded torque from Lochar Moss, Dumfriesshire	112
Late-Celtic bronze spoon from Brickhill Lane, London	119
Late-Celtic bronze spoon from Crosby Ravensworth, Westmoreland	119
Late-Celtic spoon, one of a pair, from Weston, near Bath	120
Late-Celtic urns from Shoebury, Essex	123
Late-Celtic bronze mirror from Trehan Bahow, Cornwall	131
Bronze sword-sheath from Hunsbury	132
Late-Celtic pottery from the Glastonbury Lake Village	142
Late-Celtic wooden tub found at the Glastonbury Lake Village	147

viii LIST OF ILLUSTRATIONS

	PAGE
Handles of pair of Late-Celtic spoons from Weston, near Bath	147
Engraved bone object from Slieve-na-Caillighe, Co. Meath	150
Fibula of bronze-gilt from Æsica	152
Collar from Broighter, Limavady, Co. Londonderry	153
Spiral ornament in illuminated MS. copied from repoussé metalwork	154
Shading of parallel lines	156
Cross-hatching placed diagonally	156
Cross-hatching placed diagonally, with dots	157
Cross-hatching of double lines placed diagonally	157
Chequerwork grass-matting shading	157
Engine-turned shading	158
Dotted shading	158
Swastika design on shield from the Thames	159
Engraved ornament found at the Glastonbury Lake village	161
Handles of bronze bowl found at Barlaston, Staffordshire	166
Handle of bronze bowl from Chesterton-on-Fossway, Warwickshire	167
Handle of bronze bowl from Chesterton-on-Fossway, Warwickshire	168
Spiral ornament from the Book of Durrow	169
Cross-slab from Pen-Arthur, Pembrokeshire	181
Erect cross-slab at St. Madoes, Perthshire	183
Cross at Penmon, Anglesey	185
Great wheel-cross of Conbelin at Margam Abbey, Glamorganshire	187
Cross at Neuadd Siarman, near Builth, Brecknockshire	189
Cross at Nevern, Pembrokeshire	191
Pin-brooch from Clonmacnois, King's Co.	221
Pierced marble screen at Ravenna	245
Regular plaitwork without any break	259
Method of making breaks in plaitwork	259
Regular plaitwork, with one vertical break and one horizontal break	260
Six-cord plait, with horizontal breaks at regular intervals	260
Cross-shaft at Golden Grove, Carmarthenshire	261
Cross-shaft at Llantwit Major, Glamorganshire	261
Eight-cord plaits, with cruciform breaks	262, 263
Six-cord plait, with cruciform breaks	264
Ten-cord plait, with cruciform breaks	264

LIST OF ILLUSTRATIONS ix

	PAGE
Knots derived from a three-cord plait	264
Diagrams of knotwork	265, 266
Method of deriving knots Nos. 3 and 6 from a four-cord plait	267
Knots Nos. 4, 5, 7, and 8 derived from a four-cord plait	268
Knot No. 1, derived from either a three-cord or a six-cord plait	268
Knots 3 and 4, derived from a six-cord plait	269
Evolution of knot No. 1 from a six-cord plait	269
Evolution of knot No. 7 from an eight-cord plait	271, 272
Diagrams of knotwork	273
Knotwork from Ramsbury, Wilts, and Nigg, Ross-shire	274
Circular knotwork from Tarbet, Ross-shire	276
Circular knotwork from Monasterboice, Co. Louth	276
Triangular knotwork from Ulbster, Caithness	277
Triangular knotwork from Dunfallandy, Perthshire	278
Key-patterns	280, 282
Shaft of cross of Eiudon at Golden Grove, Carmarthenshire	283
Erect cross-slab at Rosemarkie, Ross-shire	284
Methods of connecting spirals	285
Tree key-pattern, Meigle, Perthshire	286
Key-pattern border from the Book of Kells	287
Method of connecting spirals	288

LIST OF PLATES

v I.	{	Grave of a Gaulish warrior at Sesto Calende, Italy	} <i>To face page 8</i>
		Bronze fibulæ of La Tène type from the ceme- teries of the Marne	
v II.	{	Bronze armlet of the La Tène period from Germany	} " 10
		Bronze armlet of the La Tène period from Longi- rod (Vaud)	
		Bronze armlet of the La Tène period from the cemeteries of the Marne	
v III.		Gaulish helmet of bronze from Berru (Marne) .	} " 12
v IV.		Cinerary urn of Bronze Age from Lake, Wilts, now in the British Museum. Height 1 ft. 3¼ ins.	} " 22
v V.	{	Bronze Age urn of "Incense Cup" type from Aldbourne, Wilts, now in the British Museum. Height 3¼ ins.	} " 24
		Bronze Age urn of "Food Vessel" type from Alwinton, Northumberland, now in the British Museum. Height 5 ins.	
v VI.		Bronze Age urn of "Drinking Cup" type from Lakenheath, Suffolk, now in the British Museum. Height 7½ ins.	} " 26
v VII.	{	Spiral ornament on stone ball from Towie, Aberdeenshire, now in the Edinburgh Museum. Scale ½ linear	} " 58
		Winding band curved swastika on sword-hilt from Denmark	
		Bronze sword-hilt with winding band pattern from Denmark	
		Bronze sword-hilt with spiral ornament from Denmark	
v VIII.		Bronze mirror from Birdlip, Gloucestershire, now in the Gloucester Museum. R. W. Dugdale, photo	} " 68

✓ IX.	Iron dagger with bronze hilt and sheath from the River Witham	<i>To face page 92</i>		
✓ X.	Bronze harness rings from Polden Hill, Somersetshire, now in the British Museum. Scale $\frac{3}{4}$ linear	” 94		
✓ XI.	{ Late-Celtic bronze fibula from Walmer, Kent, now in the British Museum. Scale $\frac{3}{4}$ linear . Late-Celtic fibula from Ireland, now in the Museum of the Royal Irish Academy, Dublin Enamelled bronze fibula from Risingham, Northumberland, now in the Newcastle Museum . Bronze fibula from Water Eaton, Oxon, now in the British Museum. Scale $\frac{1}{4}$ linear . . .	” 98		
		{ Bronze fibula from Clogher, Co. Tyrone, now in the British Museum. Scale $\frac{1}{2}$ linear . . Late-Celtic bronze fibula (locality unknown), now in the British Museum. Scale $\frac{1}{2}$ linear . S-shaped enamel bronze fibula (locality unknown), now in the British Museum. Scale $\frac{1}{2}$ linear . S-shaped fibula of enamelled bronze from Norton, E. Riding of Yorkshire, now in the British Museum. Scale $\frac{1}{2}$ linear	” 100	
			{ Bronze fibula from Polden Hill, Somersetshire, now in the British Museum, side view. Scale $\frac{3}{4}$ linear Bronze fibula from Polden Hill, Somersetshire, now in the British Museum, front view. Scale $\frac{3}{4}$ linear	” 102
				{ Bronze fibula from River Churn, now in the British Museum, front view. Scale $\frac{1}{2}$ linear . Bronze fibula from River Churn, now in the British Museum, side view. Scale $\frac{1}{2}$ linear . .
✓ XIV.	{ Bronze hook and disc ornament from Ireland, now in the Dublin Museum Bronze pin enamelled from Danes' Graves near Driffield, Yorkshire Bronze disc fibula with Late-Celtic ornament from Silchester, now at Strathfieldsaye House. S. Victor White, of Reading, photo.	” 108		

✓ XV.	{ Bronze beaded torque from Mowroad, near Rochdale. Scale $\frac{3}{4}$ linear Bronze collar from Wraxhall, now in the Bristol Museum }	To face page 110
✓ XVI.		Bronze armlets from the Culbin Sands, now at Altyre, near Forres, N.B.
✓ XVII.	Late-Celtic bronze mirror in the Mayer Museum, Liverpool (locality unknown)	„ 114
✓ XVIII.	Late-Celtic pottery from Hunsbury, now in the Northampton Museum	„ 122
✓ XIX.	{ Late-Celtic pottery from Yarnton, Oxford- shire, now in the British Museum. Scale $\frac{3}{4}$ linear Late-Celtic pottery from Kent's Cavern near Torquay, Devonshire, now in the British Museum. Scale $\frac{3}{4}$ linear }	„ 124
✓ XX.		Granite monolith with Late-Celtic sculpture at Turoe, Co. Galway. Height of stone 4 ft. Reproduced from a photograph by Mr. A. McGoogan illustrating Mr. George Coffey's paper in the <i>Proceedings of the Royal Irish Academy</i>
✓ XXI.	{ Cruciform harness mounting of bronze ena- melled (locality unknown), now in the British Museum. Scale $\frac{1}{2}$ linear Bronze enamelled harness mounting from Polden Hill, Somersetshire, now in the British Museum. Scale $\frac{3}{4}$ linear }	„ 136
✓ XXII.		{ Upper part of bronze sword-sheath from Lisnacrogghera Co., now in the British Museum Lower part of bronze sword-sheath from Lisnacrogghera Co., now in the British Museum }
✓ XXIII.	{ Handle of Late-Celtic bronze tankard, Trawsfynydd, Merionethshire, now in the Mayer Museum, Liverpool Bridle bit of bronze enamelled, from Rise near Hull, now in the British Museum. Scale $\frac{1}{4}$ linear }	

- . XXIV. Detail of ornament on Late-Celtic bronze shield from the Thames at Battersea, now in the British Museum . . . *To face page 152*
- ✓ XXV. { Circular disc of bronze with repoussé ornament from Ireland, now in the British Museum } " 154
 { Bronze enamelled harness-ring from West-hall, Suffolk, now in the British Museum. Scale $\frac{3}{4}$ linear }
- ✓ XXVI. { Cast of metal object (locality unknown) from the Albert Way Collection, now in the Museum of the Society of Antiquaries, Burlington House } " 170
 { Cover of the Stowe Missal, in the Museum of the Royal Irish Academy, Dublin (A.D. 1023 to 1052) }
- ✓ XXVII. Erect cross slab in Aberlemno Churchyard, Forfarshire. John Patrick, of Edinburgh, photo. " 184
- . XXVIII. Bronze bell with engraved ornament from Lough Lene Castle, Co. Westmeath, in the Museum of the Royal Irish Academy " 202
- ✓ XXIX. The shrine of the bell of St. Patrick's Will, in the Museum of the Royal Irish Academy, Dublin (A.D. 1091 to 1105) . " 204
- . XXX. Head of the Lismore crozier at Lismore Castle, Co. Waterford (A.D. 1090 to 1113) " 206
- ✓ XXXI. { Celtic quadrangular bell of bronze with zoomorphic handles from Llangwynodl Church, Carnarvonshire, now in the possession of Corbet Yale-Jones Parry, Esq., of Madryn Castle, Pwllheli. Mr. Morgan Evans, of Pwllheli, photo. } " 210
 { Bronze reliquary from Lower Lough Erne, now in the possession of T. Plunkett, Esq., of Enniskillen. 7 ins. long by $5\frac{1}{4}$ ins. high by $3\frac{1}{2}$ ins. wide. R. Welch, of Belfast, photo. }

	{ Bronze fibula with plaitwork and Late-Celtic ornament from the Ardakillen Crannog, near Strokestown, Co. Roscommon, now in the Museum of the Royal Irish Academy, Dublin . . .	} <i>To face page 216</i>
✓ XXXII.		
✓ XXXIII.	Silver penannular brooch from Ireland, now in the British Museum. Scale $\frac{1}{4}$ linear	„ 222
✓ XXXIV.	Biskra woman wearing a pair of penannular brooches, the ends of the pins pointing upwards	„ 224
✓ XXXV.	Details of ornaments on the Tara brooch	„ 226
✓ XXXVI.	Details of ornaments on the Tara brooch	„ 228
✓ XXXVII.	Details of ornament on the Tara brooch, in the Museum of the Royal Irish Academy, Dublin	„ 230
	{ Circular knotwork on slab in church of Sta. Sabina, Rome	} „ 244
✓ XXXVIII.		
✓ XXXIX.	{ Key pattern, S. Apollinare Nuovo, Ravenna } { Vine scrolls, S. Apollinare Nuovo, Ravenna }	„ 246
	{ Plaitwork of Romano-British pavement at Lydney Park, Gloucestershire . . .	} „ 258
✓ XL.		
✓ XLI.	Erect cross slab from Collieburn, Sutherland, now in the Dunrobin Museum	„ 274
✓ XLII.	Detail of ornament on erect cross slab at Nigg, Ross-shire	„ 276
	{ Four men placed swastika fashion on recumbent pavement at Meigle, Perthshire. Scale $\frac{1}{4}$ linear	} „ 288
✓ XLIII.		
✓ XLIV.	{ Detail of ornament on erect cross slab at Nigg, Ross-shire }	„ 292

PREFACE

THIS work is an attempt—whether successful or not the critic must decide—to give a concise summary of the facts at present available for forming a theory as to the origin and development of Celtic art in Great Britain and Ireland. By Celtic art is meant the art of the peoples in Europe who spoke the Celtic language, but it must always be borne in mind that although linguistically they were Celts, yet racially they were of mixed Celtic and Iberian blood, so that their art was possibly quite as much Iberian as Celtic. It is only since the epoch-making discoveries of Schliemann in Greece, of Flinders Petrie in Egypt, and of Arthur Evans in Crete that it has been possible in a satisfactory manner to connect the culture of Britain in the Bronze Age with the corresponding culture on the Continent. It is now quite clear that certain characteristic decorative motives, such as the divergent spiral, are of foreign origin instead of having been invented in Ireland, as was at one time believed. Other discoveries made in England, more especially those at Aylesford, Glastonbury, Mount Caburn, and

Hunsbury, have thrown an entirely new light on the archæology of this country by showing that the Early Iron Age began here two or three centuries at least before the Roman occupation. Lastly, the explorations made by Continental antiquaries at Hallstatt in Austria, La Tène in Switzerland, and in the Gaulish cemeteries of the Marne district in France, point to the sources of the culture to which the late Sir Wollaston Franks gave the name "Late-Celtic."

Celtic art naturally divides itself into two distinct periods, the Pagan and the Christian. With regard to the latter, the remains have been so fully investigated that it is hardly probable any new facts will be brought to light which will seriously alter the conclusions now arrived at. With regard to the Pagan period the case is altogether different, as most of the finds hitherto made have been due to accident, and until the large number of inhabited and fortified sites belonging to this period are systematically excavated our knowledge must necessarily remain incomplete.

I have endeavoured to give in the footnotes all the sources whence my information has been obtained, but I should like more especially to acknowledge my indebtedness to A. Bertrand and S. Reinach's *Les Celtes dans les Vallées du Pô et du Danube*; J. Anderson's *Scotland in Pagan Times* and *Scotland in Christian Times*; Arthur Evans' papers on the Aylesford, Æsica, and Limavady finds in the *Archæologia*; and George'

Coffey's papers on the ornament of the Bronze Age, Newgrange, etc., in the *Journal of the Royal Society of Antiquaries of Ireland*, and in the *Transactions and Proceedings of the Royal Irish Academy*.

The theory of the evolution of Celtic knotwork out of plaitwork (as explained on pages 257 to 278) is entirely original, and, simple as it appears when explained, took me quite twenty years to think out whilst classifying the patterns that occur on the early Christian monuments of Scotland, England, Wales, and Ireland, nearly all of which I have examined personally.

No illustrations are given of the pages of the Celtic illuminated MSS. on account of the difficulty of making satisfactory reproductions of them on a small scale. I have thought it better to refer the reader either to the MSS. themselves or to the *Publications of the Palæographical Society* and Professor J. O. Westwood's *Miniatures of the Anglo-Saxon and Irish Manuscripts*.

A large number of photographs of Late-Celtic metalwork in the British Museum have been specially taken for this work by Mr. H. Oldland, with the kind permission of Mr. C. H. Read, F.S.A. I am indebted to the Rev. Canon W. Bazeley for obtaining a photograph of the Birdlip mirror in the Gloucester Museum, and to Mr. George for the loan of Sir H. Dryden's drawings of the Hunsbury sword-sheath in the Northampton Museum. Mr. George Coffey, M.R.I.A., of the Museum

of the Royal Irish Academy, has also from time to time been good enough to assist me in various ways. The photographs of the cast of the Nigg cross were taken by Messrs. M. and T. Scott, of Edinburgh, for Mr. D. J. Vallance, the curator of the Museum of Science and Art at Edinburgh.

For the use of electrotypes of blocks I have to give my best thanks to the Society of Antiquaries of London,¹ the Society of Antiquaries of Scotland,² the Royal Society of Antiquaries of Ireland,³ the Royal Irish Academy,⁴ the Royal Archæological Institute,⁵ the Cambrian Archæological Association,⁶ the Somersetshire Archæological Society,⁷ and the publishers of the *Antiquary*,⁸ the *Reliquary*,⁹ and the *Illustrated Archæologist*.¹⁰ Plates XXVI., XXIX., XXXV., XXXVI., and XXXVII. are from the series of photographs taken by Mr. W. G. Moore, of Upper Sackville Street, Dublin, for the Royal Irish Academy.

¹ Blocks on pp. 112, 123, 152, 153, 166, 167, 168.

² " " 154, 169, 183, 276 to 278, 274 to 288.

³ " " 150, 221.

⁴ " " 39, 40, 45, 47.

⁵ " " 119, 120, 131, 147.

⁶ " " 27 to 36, 181, 185, 187, 189, 191, 259 to 269, 271 to 273, 283.

⁷ " " 142.

⁸ " " 147, 161.

⁹ " " 104.

¹⁰ Plate XXXIV.

CELTIC ART IN PAGAN AND CHRISTIAN TIMES

CHAPTER I

THE CONTINENTAL CELTS AND HOW THEY CAME TO BRITAIN

THE CELTS A BRANCH OF THE ARYAN FAMILY OF NATIONS

ALL the nations at present inhabiting Europe, with the exception of the Turks, the Finns, the Magyars, and the Basques, speak Aryan languages, and are to a large extent of Aryan descent,¹ although their blood has been mixed from time to time with that of the Neolithic non-Aryan aborigines. The Celts, therefore, belong to the Aryan group of nations, and came from the same cradle of the race in Central Asia as did the ancestors of the Greeks, Italians, Teutons, Slavs, Armenians, Persians, and the chief peoples of Hindustan.

It has been the fashion amongst persons holding what they suppose to be advanced views to dispute the fact that the cradle of the Aryans was in Central Asia, but this is neither the time nor the place to discuss

¹ The fallacy that identity of language or of culture necessarily implies identity of race must be carefully guarded against.

the question. It is sufficient for our purpose to note that the successive waves of Aryan conquest entered Europe from the east, and that their general direction was towards the west.

THE CELT AS DESCRIBED BY GREEK
AND ROMAN AUTHORS

The Celts make their first appearance in history at the end of the sixth century B.C., when, however, they are referred to not by their name as a people but by the name of the country they occupied. Thus, Hecataeus of Miletus, writing about 509 B.C., mentions Marseilles as being a Ligurian city near the Celtic region.¹

Herodotus, writing half a century later, is the first historian who uses the word *κελτός* (Celt) as distinguished from *κελτική* (the Celtic region). In the two passages² in which the Celts are mentioned, Herodotus says that they inhabited the part of Europe where the Danube has its source, and that the only other people to the westward were the Cynetes or Dog-Men. Both Herodotus and Aristotle erroneously supposed that the source of the Danube was situated in the Pyrenees.

Aristotle³ describes the country of the Celts as being so cold that the ass is unable to reproduce his species there.

Plato, who lived sixty years after the time of Herodotus, classes the Celts with the Scythians, Persians, Carthaginians, Iberians, and Thracians, as being warlike nations who like wine, and drink it to excess.⁴

¹ *Μασσαλία πόλις τῆς Δαγμοτικῆς κατὰ τὴν κελτικὴν* (C. and T. Muellerus, *Fragmenta Historicorum Græcorum*, Paris, 1841, vol. i., p. 2, fragm. 22).

² Bk. ii., chap. xxxiii.; and Bk. iv., chap. xlix

³ *De Generatione Animalium*.

⁴ *De Legibus*.

Pytheas (*circa* B.C. 300) is the first author who includes the part of Europe which was afterwards the Gaul of Cæsar within the Celtic territory.¹

According to the earlier historians, the parts of Europe occupied by the Celts at the end of the fourth century B.C. were the coast of the Adriatic from Rimini to Venice, Istria and the neighbourhood of the Ionian Gulf, and the left bank of the Rhone from the Lake of Geneva to the source of the Danube.²

Polybius (B.C. 205-123) gives more definite and satisfactory information about the Celts than the somewhat vague references made to them by previous writers. From him we learn³

(1) That the Celts of upper Italy did not come from the Gaul of Cæsar, but from the valley of the Danube, and more particularly from the countries which border upon the northern slopes of the Julian Alps of Noricum.

(2) That these peoples were primarily divided into Cisalpine Celts and Transalpine Celts, that is to say, into the Celts of the Alps and of the north of the Alps. In the third century B.C. these latter were already called, more particularly by Polybius, by the name of Galati.

(3) That the Cisalpine Celts, who from a remote period long before the fourth century B.C. inhabited the wide plains of Lombardy from the Alps to the river Pò, were, for the most part, an agricultural and sedentary race living in luxury and in a state of civilisation without any doubt greatly superior to that which could have existed in Gaul at that time.

(4) That the Galati, on the contrary, the Transalpine Celts, although kinsmen to the former mountaineers, still half nomads, shepherds and warriors chiefly, always ready to run the risk of a raid, armed from the fourth century with

¹ C. Elton's *Origins of English History*, p. 25.

² A. Bertrand and S. Reinach's *Les Celtes*, p. 19.

³ *Ibid.*, p. 27.

an iron sword, an iron-headed spear and a shield, lived under the régime of a sort of military aristocracy, as proud as they were poor, such as the inhabitants of the Caucasus were, not half a century ago.

The people who were called *Celtæ* by the earlier historians, and *Galatæ* by the more recent writers, were also known to the Romans as *Galli*; but these three separate appellations do not seem to indicate any difference of race, and indeed they all have the same meaning, viz. a warrior. The Gauls of Cæsar's time preferred to call themselves by the name which he wrote, *Celtæ*.¹

All the Classical authorities are agreed as to the physical characteristics of the Celts with whom they were acquainted. The Celts are invariably described as being tall, muscular men, with a fair skin, blue eyes, and blonde hair tending towards red.² Such were the Gauls who conquered the Etruscans of northern Italy in B.C. 396, took Rome under Brennus six years later, sacked Delphi in B.C. 279, and gave their name to Galatia in Asia Minor.

It may well be asked what has become of the tall, fair-haired Celts who in the fourth century B.C. were the terror of Europe? The answer seems to be that being numerically inferior to the races which they conquered, but did not exterminate, they after a time became absorbed by the small, dark Iberians, who were the aborigines of France and Spain in the later Stone Age. In Great Britain the once warlike Celt at last became so effete that he fell an easy prey to the Picts, the Scots, the Angles, and the Saxons.

¹ Prof. J. Rhys' *Celtic Britain*, p. 2.

² C. Elton's *Origins of English History*, p. 113.

THE CELTS AS REPRESENTED IN GREEK AND ROMAN ART

The physical type of the Celt in Classical Sculpture was fixed by the artists of Pergamos, who were commissioned to perpetuate the victories of Attalus I. (B.C. 241-197) and Eumenes II. (B.C. 197-159) over the Galatians of Asia Minor.¹ The originals of the statues executed at this period to decorate the acropolis at Pergamon and at Athens have since been popularised by means of numerous copies. The statue most familiar to everyone is that wrongly called the Dying Gladiator,² but which is really a Gaulish warrior mortally wounded, as may be seen by the twisted torque round his neck, and the shape of his shield and trumpet. The other statues of the same class are the group formerly known as Arria and Paetus³ (representing a Gaul committing suicide after having killed his wife) and the figures of an old man with a young man dead⁴ and a young man wounded⁵ from the defeat of the Gauls by Attalus.

In all these works of art the Gaulish type is the same, the men being tall and muscular, with abundant unkempt locks, and an energetic, almost brutal, physiognomy, the very opposite of the intellectual beauty of the ideal Greek. The type thus fixed by eminent artists was handed down from generation to generation, until the last years of the Roman empire. It may be recognised on the Triumphal Arch at Orange⁶

¹ *Les Celtes*, p. 37; H. B. Walters' *Greek Art*, p. 91; and Dr. A. S. Murray's *History of Greek Sculpture*, vol. ii., p. 376.

² In the Museum of the Capitol at Rome; cast in the South Kensington Museum.

³ Prof. Ernest Gardner's *Handbook of Greek Sculpture*, pt. ii., p. 456; and A. Baumeister's *Denkmäler*, p. 1237.

⁴ At Venice.

⁵ In the Louvre.

⁶ A. de Caumont's *Abécédaire d'Archéologie* (Ère Gallo-Romaine), Second edition, p. 194.

(Vaucluse), in the south of France, and at the sarcophagus of Ammendola¹ in the museum of the Capitol at Rome, both of which have derived their inspiration from the works of art of the time of the kings of Pergamon. Latterly the Gaulish type became that of barbarians generally.²

THE CELT AS REVEALED BY ARCHÆOLOGICAL RESEARCH

From an archæological point of view the Celtic civilisation which existed in Central Europe, certainly as far back as 400 B.C., and very probably three or four centuries earlier, was that of the Iron Age. The Continental antiquaries divide the Iron Age in this part of Europe into two periods marked by differences in culture. The culture of the Early Iron Age is pre-historic, and is called that of "Hallstatt," after the great Alpine cemetery near Salzburg in Austria.

The culture of the Later Iron Age comes after the time when the Celts first make their appearance in history, and is known to Swiss and German archæologists as that of "La Tène," from the Gaulish Oppidum at the north end of the Lake of Neuchâtel in Switzerland. The La Tène culture in the form it occurs in France is called "Marnian," and corresponds with the "Late-Celtic" culture of Great Britain.

Hallstatt, from which the Celtic civilisation of the earlier Iron Age takes its name, is situated thirty miles S.E. of Salzburg in Austria, amongst the mountains forming the southern boundary of the valley of the Danube. It was a place of great commercial importance in ancient times, in consequence of the salt mines in the neighbourhood, and because it lay on the great

¹ S. Reinach's *Les Gaulois dans l'art antique*.

² S. Reinach's *Les Celtes*, p. 38.

trade route by which amber was brought from the mouth of the Elbe to Hatria, at the head of the Adriatic.¹

The pre-Roman necropolis of Hallstatt was discovered in 1846, and excavations have been going on there at intervals ever since. In 1864 M. de Sacken, curator of the collection of antiquities in the Vienna Museum, published a monograph on the subject, which still remains the best book of reference. M. de Sacken did not superintend the excavations personally, that task having fallen to the lot of George Ramsauer. Copies in MS. of Ramsauer's notes on the contents of the tombs, and sketches of the antiquities discovered in them exist in the Ashmolean Museum at Oxford, and in the national museums at Saint-Germain and at Vienna.

The Hallstatt finds show very clearly the transition from the Bronze to the Iron Age in Central Europe.

M. Salomon Reinach thus summarises, in his *Les Celtes dans les Vallées du Pô et du Danube* (p. 129), the conclusions arrived at by M. de Sacken :—

(1) Two distinct races have been buried at Hallstatt ; one of which cremated the bodies and the other which practised inhumation ; the former showing themselves to have been much richer than the latter.

(2) The people, as represented by their grave-goods, must have supported themselves, besides working the salt mines (their chief industry), by breeding cattle. The number of bones and teeth of animals found in the tombs show that they possessed herds. Their agricultural pursuits are proved by the presence of numerous scythes and sickles in the graves. Slag and moulds from founderies indicate that they were metallurgists.

¹ C. Elton's *Origins of English History*, pp. 46 and 62, and Prof. W. Boyd Dawkins' *Early Man in Britain*, pp. 417, 466, and 473.

(3) Amongst the individuals who had been burnt the greater part of the men and women displayed a relative luxuriousness of toilet appliances, a luxuriousness which was ministered to by foreign commerce supplying amber from the Baltic, Phœnician glass, ivory, embroidery in gold thread and stamped gold-leaf of oriental workmanship, used in the decoration of the sword-hilts and scabbards.

(4) On the bronze vessels, side by side with the old geometrical ornament, common to them and to the Cisalpine vases, are to be seen new combinations of symbolical designs which recur on the Celtic coinage of Gaul.

Amongst the objects most characteristic of the Hallstatt culture are :—

(1) Daggers, or short swords, with a pointed blade of iron and a bronze handle having two little projections at the top terminating in round knobs and resembling the antennæ of an insect.

(2) Long double-edged swords with an iron blade made in imitation of the leaf-shaped swords of the Bronze Age, having the edges slightly curved outwards in the middle, but not having so sharp a point as the Bronze Age sword, and being much longer. The hilts have a massive pommel encrusted with ivory and amber, and ornamented with gold-leaf.


(3) Pails, or situlæ, of thin bronze plates ornamented with figure subjects executed in repoussé work, and exhibiting a peculiar style of art which Dr. Arthur Evans thinks the Celts borrowed from the Veneti, the ancient Illyrian inhabitants of the north of the Adriatic, who, in their turn, had come under Hellenic influence whilst the amber trade route between Greece and the Baltic passed through Hatria.




The Hallstatt
Sword



GRAVE OF A GAULISH WARRIOR AT SESTO CALENDE, ITALY



BRONZE FIBULA OF LA TÈNE TYPE,
FROM THE CEMETERIES OF
THE MARNE



BRONZE FIBULA OF LA TÈNE TYPE,
FROM THE CEMETERIES OF
THE MARNE

Dr. Arthur Evans¹ divides the Hallstatt remains into an earlier and a later group, the former dating from about 750 to 550 B.C. During the later period, from 550 B.C., he thinks there was a tendency for the typically Gaulish or Late-Celtic culture to overlap that of the Early Iron Age. The Gallo-Italian tomb of a Celtic chieftain, found in 1867 at Sesto-Calende,² at the south end of Lago Maggiore, illustrates the transition from the Hallstatt to the La Tène culture. Amongst the grave-goods were a situla with figure subjects in repoussé metalwork and a short pointed iron sword having a handle furnished with antennæ, like those from Hallstatt.

In addition, there were the remains of a chariot, horse-trappings, a bronze war-trumpet, helmet and greaves, and iron lancehead, such as we should expect to find buried with a Celtic warrior in the Iron Age in Gaul or Britain.

La Tène (which gives its name to the modified and later form of Hallstatt culture as it existed in Central Europe from about 400 B.C., when the name of the Gaul superseded that of the Celt, to the time of Cæsar's conquest) is a military stronghold, or oppidum, situated at the N.E. end of the Lake of Neuchâtel, commanding an important pass between the upper Rhone and the Rhine. The remains at La Tène were first explored by Colonel Schwab in 1858, and subsequently by E. Vouga in 1880. The objects derived from this remarkable site are to be seen in the public museums at Bienne, Neuchâtel, and Berne; and in the private collections of Colonel Schwab,

¹ Rhind Lectures on the "Origins of Celtic Art," Lecture II., as reported in the *Scotsman* for December 12th, 1895.

² S. Reinach's *Les Celtes*, p. 49.

Professor Desor, E. Vouga, Dardel Thorens, and Dr. Gross.¹

According to Dr. Arthur Evans, the date of the culminating epoch of Gaulish civilisation, as represented by the antiquities from La Tène, is probably the third century B.C. It was at this period that the earlier foreign elements derived from Hallstatt, and even from countries further afield, became thoroughly assimilated, and the style of art called Late-Celtic began to take definite shape.

The typical arms found at La Tène are :—

(1) A long sword with a double-edged iron blade having a blunt point. The length and flexibility of the blade made it useless for thrusting in the way which was possible with the shorter and more rigid leaf-shaped sword of the Bronze Age, so the pointed end was abandoned.

(2) Lances with an iron point often of a peculiar curved form.²

(3) An oval shield of thin bronze plates ornamented with bosses.

(4) A horned helmet of bronze.

The characteristic La Tène ornament is found chiefly on the sword-sheaths, the helmets, and the shields. The La Tène fibulæ are derivatives of the “safety-pin,” and usually have the tail-end bent backwards, as in the Marnian fibulæ in France and the Late-Celtic fibulæ in England.


The Gaulish culture in France corresponding with that of La Tène in Switzerland has been called

¹ The remains are fully described in Dr. F. Keller's *Lake Dwellings*; Dr. R. Munro's *Lake Dwellings of Europe*; E. Vouga's *Les Helvètes à la Tène*; and Dr. Gross' *La Tène un Oppidum Helvète*.


² With flame-like undulating edges “so as to break the flesh all in pieces” (C. Elton's *Origins of English History*, p. 116).



BRONZE ARMLET OF THE LA TÈNE PERIOD FROM GERMANY



BRONZE ARMLET OF THE LA TÈNE PERIOD
FROM LONGIROD (VAUD)



BRONZE ARMLET OF THE LA TÈNE PERIOD
FROM THE CEMETERIES OF THE MARNE

“Marnian” by the French archæologists because the principal remains of this period have been found in the cemeteries of the Department of the Marne. A list of seventy-two such Marnian cemeteries (some of which contained as many as 450 graves) is given by A. Bertrand in his *Archéologie Celtique et Gauloise*, p. 358. The objects obtained from these cemeteries are fully illustrated in the *Dictionnaire Archéologique de la Gaule*, and in Leon Morel's *La Champagne*



Ornament on Bronze Sword-sheath from La Tène


souterraine (*Album*). The best collections are those in the Museum of Saint-Germain and the British Museum. M. Bertrand fixes the date of the Marnian cemeteries at from 350 to 200 B.C., the period between the time when bronze weapons ceased to be used, and the introduction of a national coinage into Gaul.

From the point of view of art, two of the most interesting burials discovered in the Département du Marne are those at Berru¹ and Gorge-Meillet² of ✓

¹ A. Bertrand's *Archéologie Celtique et Gauloise*, p. 356.

² E. Fourdriguiet's *Double Sépulture Gauloise de la Gorge-Meillet*.

warriors interred with their chariots, horses, and complete military equipment, including two bronze helmets, which show the kind of decoration prevalent at the period, and afford a link between the Marnian style in Gaul and the Late-Celtic style in Britain. The



Gaulish Helmet of Bronze from Gorge-Meillet

burials at Berru and Gorge-Meillet correspond very nearly with those at Arras, Danes' Graves, and elsewhere, in the portion of Yorkshire occupied by the Celtic tribe of the Parisi.

The Marnian cemeteries belong to the second Iron Age of Central Europe after 400 B.C., but in the commune of Magny Lambert (Côte-d'or), near the source



CASQUE DE BERRU (MARNE) - BRONZE - 4th CENTURY B.C.

GAULISH HELMET OF BRONZE FROM BERRU (MARNE)

of the river Seine, tumuli have been opened containing long iron swords and bronze *situlæ* of distinctly Hallstatt type.

Dr. Arthur Evans thinks that the older, or Hallstatt, culture of Central Europe was gradually modified and transformed into the La Tène, Marnian, and Late-Celtic stages of culture, in consequence of the foreign influence exercised by the continual flow of Greek commerce into eastern Gaul from the sixth century B.C. onwards. Ample evidence of this commercial intercourse is afforded by the discovery of tripods, hydrias, œnochoës, and painted vases of Greek workmanship associated with Gaulish burials,¹ as at Grækwyl, near Berne in Switzerland, at Somme-Bionne (Marne), at Rodenbach in Bavaria, and at Courcelles-et-Montagne (Haute-Marne).

The great difficulty in understanding the evolution of Celtic art lies in the fact that although the Celts never seem to have invented any new ideas, they professed an extraordinary aptitude for picking up ideas from the different peoples with whom war or commerce brought them into contact. And once the Celt had borrowed an idea from his neighbour, he was able to give it such a strong Celtic tinge that it soon became something so different from what it was originally as to be almost unrecognisable.

Polybius gives the following picture of the Cisalpine Gauls :—

“These people camp out in villages without walls, and are absolutely ignorant of the thousand things that make life worth living. Knowing no other bed than straw, only eating flesh, they live in a half-wild state. Strangers to

¹ A. Bertrand's *Archéologie Celtique et Gauloise*, pp. 328 to 347; see also L. Lindenschmit's *Die Alterthümer unserer heidnischen Vorzeit*, Mainz, 1858, etc.

everything which is not connected with war or agricultural labour, they possess neither art nor science of any description."

The tendency of the Celt to copy rather than invent is brought out most clearly in their coinage. M. A. Bertrand¹ says:—

"Were they settled in Macedonia they imitated with more or less success the tetradrachms of Philip and of Audoleon, king of Paeonia; did they advance towards Thrace, they copied the tetradrachms of Thasos. The Senones of Rimini took for their model the Roman and Italian *aes grave*; in the north of Italy, finding themselves in contact with nations who used the monetary system of the drachm and its multiples and divisions, the Gauls copied them until the time they were driven back on the Danube. In Liguria they copied the drachms of Massalia. Were they encamped on the banks of the Danube in Noricum, or in Rhaetia, they again copied the monetary systems of their neighbours. The tetradrachms of the Boii on which are inscribed the name of 'BIATEC,' one of their chiefs, reproduced the type of the last Roman of the family of Fufia struck between the years 62 and 59 B.C. In a word, the same habit of imitation is found everywhere in the cradle of Gaulish numismatics properly so-called; on the left bank of the Rhine, it was the gold staters of Philip which served as the model for gold pieces and sometimes for silver; in Aquitaine, it was the coins of Emporia, Rhoda, and Massalia. Armorica and the frontier countries were the first who adopted for their coinage types which can be called national, although still reflecting those imitated from the Macedonian staters. Let it be noticed that we are in one of the most Celtic parts of Gaul: it is therefore natural that the difference in genius between the two races of Celts and Gauls should manifest itself most clearly."

¹ *Archéologie Celtique et Gauloise*, p. 387.

INVASION OF BRITAIN BY GOIDELIC CELTS IN
THE BRONZE AGE

The aborigines of Europe, who were driven westward by the successive waves of Aryan conquest, appear to have been in the Neolithic stage of culture, and they are identified by Prof. W. Boyd Dawkins with the Iberians mentioned by Strabo. Prof. W. Boyd Dawkins gives a map in his *Early Man in Britain* (p. 318) showing the relative distribution of the Iberic, Celtic, and Belgic races in the historic period. In this map the Iberians occupy the north of Africa, the west of Spain and France, the country round Marseilles, the whole of Wales, and the south-west of Ireland. The Celts follow behind to the eastward, pressing the Iberians towards the Atlantic.

In the opening address of the Antiquarian Section at the meeting of the Royal Archæological Institute at Scarborough in 1895, Prof. Dawkins said:—¹

“The theory that the Neolithic inhabitants of the British Isles are represented by the Basques and small, dark Iberic population of Europe generally, has stood the test of twenty-five years’ criticism, and still holds the field. From the side of philology it is supported by the fact pointed out by Inchauspé that the Basque word *aits* for stone is the root from which the present names of pick, knife, and scissors made of iron are derived. This of itself shows that the ancestors of the Basques were in the Neolithic stage of culture. The name of Ireland, according to Rhys,² is derived from Iber-land (Hibernia), the land of the Iberians, or sons of Iber. The evidence seems to be clear: 1. That the Iberians were the original inhabitants of France and Spain in the Neolithic age, and the only inhabitants of the British Isles; 2. That

¹ *Archæological Journal*, vol. lii., p. 342.

² *Celtic Britain*, p. 262.

they were driven out of the south-eastern parts of France and Spain in the Neolithic age; (3) That they are now amply represented by the small dark peoples in the Iberian Peninsula, and in the island which bears their name, and in various other places in Western Europe, where they constitute, as Broca happily phrases it, 'ethnological islands.' The small, dark, long-headed Yorkshiremen form one of these islands."

Let us pause for a moment to consider the stage of culture attained by the Neolithic aborigines of Britain whom the Celts found here on their first arrival. The houses in which Neolithic man lived are of two kinds: (1) pit dwellings dug to a depth of from seven to ten feet deep in the chalk, like those at Highfield,¹ near Salisbury, explored by Mr. Adlam in 1866; and (2) hut circles like those at Carn Brê near Camborne,² in Cornwall, excavated by Mr. Thurstan C. Peter, and on Dartmoor,³ excavated by the Rev. S. Baring-Gould and Mr. R. Burnard. In many cases the villages are fortified by a wall of rubble stone, as at Grimspound, on Dartmoor. Neolithic dwellings have also been explored by Mr. George Clinch, at Keston, in Kent.⁴

Neolithic man supported himself by the chase and by fishing, and also was a farmer in a small way, growing wheat and cultivating flax. He had domesticated the sheep, goat, ox, hog, and dog. He could spin, weave, mine flint, chip and polish stone implements and make rude pottery.

¹ W. Boyd Dawkins' *Early Man in Britain*, p. 267; and E. T. Stevens' *Flint Chips*, p. 57.

² R. Burnard in *Trans. of Plymouth Inst.*, 1895-6; and T. C. Peter in *Jour. R. Inst. of Cornwall*, No. 42.

³ Reports of Dartmoor Exploration Committee in the *Trans. of Devonshire Assoc. for Advancement of Science*.

⁴ *Proc. Soc. Ant. Lond.*, ser 2, vol. xii., p. 258, and vol. xvii., p. 216.

He buried his dead in long barrows, chambered cairns, and dolmens. Cremation was not practised, and it was usual to inter a large number of bodies in a chamber constructed of huge stones.

Such was the aboriginal inhabitant with whom the first Celtic invader had to contend. I say *first* Celtic invader advisedly, for there was a second Celtic invasion at a later period. The vanguard of the Celtic conquerors are called by Prof. J. Rhys, in his *Celtic Britain* (p. 3), "Goidels," to distinguish them from the "Brythons," who constituted the second set of invaders. The modern representatives of the Goidels are the Gaelic-speaking population of the Highlands of Scotland, Ireland, and the Isle of Man; whilst the descendants of the Brythons now inhabit Wales, Cornwall, and Brittany. At the time of the Roman occupation the Brythonic tribes inhabited the whole of England with the exception of the districts now occupied by Cumberland, Westmoreland, Devon, and Cornwall. The most important of these Brythonic tribes were the Brigantes and Parisi of Yorkshire, the Catuvelauni of the Midland Counties, the Eцени of the eastern counties, the Atrebatas of the Thames Valley, and the Belgæ, Regni, and Cantion in the south. The south of Scotland was in possession of the Dumnoni and Otadini, who were Brythons, as were also the Ordovices of Central Wales. The Ivernians still held their own in the north of Scotland. The remainder of Great Britain was inhabited either by pure Goidels or by Goidels who had mixed their blood with the Ivernian aborigines.

As Prof. J. Rhys has pointed out in his *Celtic Britain* (p. 211), the soundest distinction between the Goidels and the Brythons rests on a peculiarity of

pronunciation in their respective languages. In the corresponding words in each language where the Brythons use the letter P, the Goidels use Qv. Hence they have been termed the "P and Q Celts." The most familiar instance of this is where the Welsh use the word *ap* to mean *son of*, and the Gaels use *mac*. The older form of *mac* found on the Ogam-inscribed monuments of Ireland, Scotland, Wales, and the West of England is *maqvi*, as in the bi-literal and bi-lingual inscribed stone at St. Dogmael's, in Pembrokeshire, where the Latin "SAGRANI FILI CVNOTAMI" has as an equivalent in Ogams "SAGRAMNI MAQVI CYNATAMI." In modern Welsh *map*, or *mab*, has been shortened by dropping the *m*, and in Gaelic the *v* of *maqvi* has been dropped, and the *q* made into *c*.

So much for the philological differences between the Goidel and the Brython. They can also be distinguished archæologically, the former as being in the Bronze Age stage of culture, and the latter in the Early Iron Age when he arrived in Britain. In a subsequent chapter we shall have to deal with the Brythonic Celt, but at present we are concerned exclusively with the Goidel.

The Neolithic inhabitants of this country, whom the Goidelic Celts found here on their arrival, were ethnologically a small dark-haired, black-eyed race, with long skulls of a type which is still to be seen amongst the Silurians of South Wales.¹ The ethnological characteristics of the Goidels were entirely different: they were tall, fair-haired, round-headed, with high cheek-bones, a large mouth, and aquiline nose. In studying the past much must necessarily be more or less conjectural, and we can never hope to see otherwise than "as in a glass darkly." As far, however, as it is

¹ Boyd Dawkins' *Early Man in Britain*, chapter ix.

possible to ascertain the facts, it appears probable that the advancing wave of Goidelic Celts did not entirely overwhelm the aborigines or drive them before it. Most likely the big Goidels made the small Iberians "hewers of wood and drawers of water," and in time either absorbed them or themselves became absorbed.

THE CHRONOLOGY OF THE BRONZE AGE IN EUROPE

Actual dates in years can only be ascertained by means of historical documents, and therefore no chronology of the ages of Stone, Bronze, and Iron is possible except where contact can be established between the prehistoric (or non-historic) races living in those stages of culture in Northern and Central Europe, and the more advanced civilisations on the shores of the Mediterranean and in Asia. Long before direct contact took place between the northern barbarians and the Egyptians, Assyrians, Phœnicians, Greeks, Romans, and other great nations of antiquity, through invasions or immigrations, a more indirect contact must have existed for centuries, owing to the trade in such things as amber, gold, bronze, and tin. Dates have been fixed approximately by the finding of imported objects in different countries, and by studying their geographical distribution. Other almost untouched fields of investigation which would help to solve many of the problems of prehistoric chronology, are the migration of symbols and patterns and comparative ornament.

The attempts that have been made to fix the duration of the Ages of Stone and Bronze in actual years are at the best mere guesses, but it may be worth while stating the conclusions arrived at by some of the leading European archæologists, so as to give a rough idea of

the time at which bronze was in use for the manufacture of implements and weapons in different countries.

Egypt during the greater part of its existence as a civilised nation was in the Bronze Age. The copper mines of the Sinaitic peninsula were worked as early as the Fourth Dynasty, as is proved by the rock inscriptions of Sneferu (B.C. 3998–3969) at Wady Maghera.¹ Bronze was certainly used by the ancient Egyptians in the fourteenth century B.C., and in the tomb of Queen Aah Hotep, although bronze weapons were found, iron was conspicuous by its absence, indicating that the latter metal had not come into general use in the fifteenth century B.C.

The Mycenæan civilisation in the Ægean was of the Bronze Age, and Prof. Flinders Petrie places its flourishing period at about 1400 B.C.² Bronze continued in use in Greece until the time of the Dorian invasion, B.C. 800.

In dealing with the local centres of the bronze industry, Prof. Boyd Dawkins³ recognises three distinct local centres in Europe.

- (1) The Uralian, or Eastern—Russia.
- (2) The Danubian, or Northern and Central—Scandinavia, Hungary.
- (3) The Mediterranean, or Southern—Greece, Italy, France, Switzerland.

Dr. Oscar Montelius⁴ gives the following tentative dates for the duration of the Bronze Age in these areas:—

¹ Petrie's *Hist. of Egypt*, vol. i., p. 31. Article on "The Age of Bronze in Egypt," in *L'Anthropologie* for January, 1890, translated in the *Smithsonian Report* for 1890, p. 499.

² *Jour. of Hellenic Studies*, vol. xii., p. 203.

³ *Early Man in Britain*, p. 414.

⁴ *Matériaux pour l'histoire primitive de l'homme*, pp. 108–113.

The Caucasus.—The Massagete were, according to Herodotus, still using bronze in the sixth century B.C.

Greece.—Bronze Age civilisation of Mycenæ, 1400 to 1000 B.C.

Italy.—Terramare of Bronze Age, twelfth century B.C. Iron introduced in ninth or eighth century B.C.

Scandinavia and Germany.—Bronze Age begun in fifteenth century B.C., and ended in fifth century B.C.

Worsaae¹ places the beginning of the Bronze Age in Scandinavia five centuries later than Montelius, *i.e.* 1000 B.C.

Dr. Naue² dates the Bronze Age in Upper Bavaria from 1400 B.C. to 900 B.C.

As regards Great Britain, there is no reason for supposing that the Brythonic Celts of the Early Iron Age arrived in this country much before B.C. 300, which date would terminate the Bronze Age, at all events in southern England. The date of the beginning of the Bronze Age in Britain can only be surmised. If, as we hope to be able to prove, much of the art of that period here can be traced to a Mycenæan origin there is no reason why the Bronze Age in Britain should not have commenced shortly after the spiral-motive patterns were transferred from ancient Egypt to the Ægean, say, about 1400 B.C., and thence to Hungary, Scandinavia, and other parts of Europe. It is not impossible, nay, it is even probable, that the Bronze Age may have lasted a thousand years in Britain, beginning B.C. 1300, and ending B.C. 300.

¹ *The Industrial Arts of Denmark*, p. 41.

² Dr. Arthur Evans' review of Dr. Julius Naue's *Die Bronzeseit in Obayern* in the *Academy* for April 27th, 1895.

CHAPTER II

PAGAN CELTIC ART IN THE BRONZE AGE

GENERAL NATURE OF THE MATERIALS AVAILABLE FOR THE STUDY OF THE ART OF THE BRONZE AGE IN BRITAIN, AND THE DECORATIVE MOTIVES EMPLOYED

AS we have already observed, the Goidelic Celts were in the Bronze Age stage of culture when they landed in Britain. Let us now inquire into the nature of the materials available for the study of the Pagan Celtic art in the Bronze Age.

The remains of this period may be classified, according to the nature of the finds, as follows :—

- (1) Sepulchral remains.
- (2) Remains on inhabited and fortified sites.
- (3) Merchants' and founders' hoards.
- (4) Personal hoards, that is to say, finds of objects purposely concealed, either in times of danger, or buried as *ex voto* deposits.
- (5) Finds of objects accidentally lost.
- (6) Sculptured rocks and stones.

The art of the Bronze Age in Europe is both of a symbolical and decorative character. The principal symbols employed are :—

The Swastika.		The Ship.
The Triskele.		The Axe.
The Cup and Ring.	↓	The Wheel.



**CINERARY URN OF BRONZE AGE FROM LAKE, WILTS;
NOW IN THE BRITISH MUSEUM
HEIGHT 1 FT. 3 $\frac{1}{4}$ INS.**

It is probable that most of these were connected with sun-worship.¹

The chief decorative art motives which were prevalent during the Bronze Age are as follows:—

- The Chevron.
- The Concentric Circle.
- The Spiral.
- The Winding Band.

With the introduction of bronze into Britain an entire change took place in the burial customs of the people. The long barrows with their megalithic chambers and entrance passages gave place to round barrows containing cists constructed of comparatively small slabs of stone, and having no approach from the exterior.

Although burial by inhumation still continued to be practised, cremation was adopted for the first time. The proportions of unburnt to burnt bodies found in opening barrows in different parts of England vary according to Thurnam² thus:—

	Unburnt.		Burnt.
Wilts . . .	82	...	272
Dorset . . .	21	...	91
Derbyshire . . .	} 150	...	121
Staffordshire . . .			
Yorkshire . . .			
Yorkshire . . .	58	...	53

The survival of the practice of inhumation to so large an extent would seem to indicate that the bronze-using Goidels amalgamated with the Neolithic aborigines rather than exterminated them.

The unburnt bodies were usually buried in a doubled-

¹ See J. J. A. Worsaae's *Danish Arts*, p. 68.

² *Archæologia*, vol. xliii., p. 310.

up position, and sometimes an urn was placed near the deceased. When the body was cremated the ashes were placed in a cinerary urn, and the grave-goods most commonly consisted of smaller pottery vessels, a bronze dagger or razor, and a stone wrist-guard. Occasionally flint implements and polished stone axe-hammers have been found with burials of this type, but it does not necessarily follow, in consequence, that bronze was unknown at the time.

The sepulchral pottery derived from the round barrows of the Bronze Age supplies us with ample material for studying the art of the period.

The principal collections are to be seen in the British Museum and the museums at Devizes, Sheffield, Edinburgh, and Dublin. These have been derived from the barrows opened by Sir R. Colt Hoare in Wiltshire, T. Bateman in Derbyshire and Staffordshire, Rev. Canon Greenwell and the Rev. J. C. Atkinson in Yorkshire, C. Warne in Dorsetshire, and W. C. Borlase in Cornwall.

The pottery from the round barrows exhibits an endless variety of form, but as regards their suggested use, they may be divided into four classes, namely :—

- (1) Cinerary urns.
- (2) Food-vessels.
- (3) Drinking-cups.
- (4) Incense-cups.

There is no doubt as to the use for which the cinerary urns¹ were intended, because they are found filled with burnt human bones, sometimes placed in an inverted position upon a flat stone, and sometimes mouth upwards. The cinerary urns vary in height from 6 inches to 3 feet, and the most common shape resembles that

¹ Greenwell's *British Barrows*, p. 66.



BRONZE AGE URN OF "INCENSE-CUP" TYPE
FROM ALDBOURNE, WILTS; NOW IN
THE BRITISH MUSEUM
HEIGHT $3\frac{1}{2}$ INS.



BRONZE AGE URN OF "FOOD-VESSEL," TYPE FROM
ALWINTON, NORTHUMBERLAND; NOW IN
THE BRITISH MUSEUM
HEIGHT 5 INS.

of an ordinary garden flower-pot, with a deep rim round the top, probably to give the vessel greater strength.

The so-called food-vessels¹ have received this name because they are believed to have contained food for the deceased in the next world. In support of this theory it may be mentioned that remains of substances resembling decayed food have been found in some of the vessels in question. Urns of the food-vessel type are shaped like a shallow bowl, and they vary in height from 3 to 8 inches. They are usually found placed beside the deceased.

The use of the so-called drinking-cups² is suggested more by the form, which resembles that of a mug, or beaker, slightly contracted in the middle, than by any actual facts connected with their discovery. They are generally placed near the deceased. The height of the drinking-cups varies from 5 to 9 inches. The Hon. J. Abercromby, F.S.A. (Scot.), has recently published an elaborate monograph on the drinking-cups of the Bronze Age entitled "The Oldest Bronze Age Ceramic Type in Britain; its close Analogies on the Rhine; its Probable Origin in Central Europe."³

Incense-cups were conjectured by Sir R. Colt Hoare and the earlier archæologists to have been used for burning some aromatic substance during the funeral rites. The view taken by the late Mr. Albert Way, and supported by Canon Greenwell,⁴ is that they were for carrying burning wood to light the funeral pile. The incense-cups are the smallest of the sepulchral vessels of the Bronze Age, being only from 1 to 3 inches high. The shape is like that of a little cup. The sides

¹ *British Barrows*, p. 84.

² *Ibid.*, p. 94.

³ *Jour. Anthropolog. Inst.*, vol. xxxii., p. 373.

⁴ *British Barrows*, p. 81.

are sometimes perforated. The incense-cups are often found inside the cinerary urns.

Canon Greenwell states that the urns of the four different types were found associated with unburnt and burnt bodies in the barrows opened by him on the Yorkshire wolds in the following proportions:—

	Unburnt.	...	Burnt.
Cinerary urns	12	...	9
	(of cinerary urn type, but without ashes)		(containing burnt bones)
Food-vessels	57	...	16
Drinking-cups	22	...	2
Incense-cups	none	...	6

The geographical distribution of the different types of sepulchral urns, as far as at present ascertained, is as follows: Food-vessels are most common in Yorkshire, and most rare in Wiltshire and the south of England generally. Drinking-cups are found all over Great Britain,¹ and it is the type of urn which varies least. Incense-cups are found with greater frequency in the south of England than in the north.

Now as to the decorative features of the sepulchral pottery of the Bronze Age in Great Britain.

The sepulchral urns are made of coarse clay moulded by hand—not turned on a lathe—and imperfectly baked by means of fire. The decoration was executed whilst the clay was moist, either by

- (1) The finger-nail.
- (2) An impressed cord.
- (3) A pointed implement.
- (4) Stamps of wood or bone.

Besides incised patterns produced by these methods, the ornament was sometimes moulded in relief and

¹ See map given by the Hon. J. Abercromby in the *Jour. Anthropolog. Inst.*, vol. xxxii., pl. 24.



**BRONZE AGE URN OF "DRINKING-CUP" TYPE FROM LAKEN.
HEATH, SUFFOLK ; NOW IN THE BRITISH MUSEUM
HEIGHT 7½ INS.**

sometimes sunk, and the incense-cups often have ornamental perforations.

With the exception of the circles found on the bottoms of some of the incense-cups the decoration consists entirely of straight lines running more often diagonally than either horizontally or vertically. The same preference for diagonal lines will be observed in the key patterns in the Irish MSS. of the Christian




Fig. 1.

period, and led, as we shall see in a subsequent chapter, to those modifications of the Greek fret which are characteristically Celtic.

Of the hundreds and hundreds of sepulchral urns of the Bronze Age that have been found in Great Britain no two are exactly the same either in size, form, or decoration. The fertility of imagination exhibited in the production of so many beautiful patterns by combining diagonal straight lines in every conceivable way is really amazing. On examination it will be found

that, complicated as the patterns appear to be, the chevron or zigzag is at the base of the whole of them. We use the heraldic terms for the sake of convenience; their meaning will be understood by a reference to Fig. 1.

It will be seen that the chevron consists of two straight lines or narrow bars inclined towards each other so as to meet in a point, the form thus produced being that of the letter **V**. Now the chevron, or **V**, is capable of being combined in the following ways:—

- W**.—Two chevrons, with the points facing in the same direction, placed side by side.
- ◊.—Two chevrons, with the points facing in opposite directions, placed with the open sides meeting.
- X**.—Two chevrons, with the points facing in opposite directions, placed with the points meeting.

By repeating the **W**, ◊, and **X**, each in a horizontal row, the patterns shown on Fig. 2 are obtained.



(a) The Triangle, or Chevron Border.

(b) The Lozenge Border.

(c) The Saltire Border.


(d) The Hexagon Border.

Fig. 2.

It will be noticed that the same pattern results from repeating a series of ◊'s in a horizontal line as from repeating a series of **X**'s, so that in order to distinguish the lozenge border from the saltire border, it is necessary

to introduce a vertical line between each pair of **X**s. The hexagon border is derived from the lozenge by omitting every other **X**.

It is a principle in geometrical ornament that for each pattern composed of lines there is a corresponding pattern in which bars of uniform width are substituted for lines. Another way of stating the same proposition is, that for each pattern composed of geometrical



(a) Line Chevron Border.
 (b) Bar Chevron Border.
 (c) Surface Pattern, produced by repeating either of the preceding.

Fig. 3.

figures (squares or hexagons, for instance) there is a corresponding pattern produced by moving the figures apart in a symmetrical manner so as to leave an equal interspace between them. This principle is illustrated by Fig. 3, where a zigzag bar is substituted for the zigzag line of the triangle or chevron border.

Then, again, another set of patterns may be derived from those composed of lines or plain bars, by shading alternate portions of the design as in chequer-work. Thus on Fig. 4 are shown three different ways of shading the chevron border, and on Fig. 5 the method of shading the patterns on Fig. 3.




Fig. 4.




Fig. 5.

Fig. 4.—(a) Line Chevron Border.
(b, c, and d) Different Methods of Shading (a).

Fig. 5.—(a) Bar Chevron Border.
(b) The same as (a), but shaded.
(c) Surface Pattern, produced by repeating (b).

A few new patterns (see Fig. 6) may be produced by placing the chevron with the point of the V facing to the right or left, thus, < or >, instead of upwards or downwards, thus, \wedge or \vee .




Fig. 6.

(a) Chevron Border, with V's placed thus, > >.
(b) The same as (a), but with a horizontal line through the points of the V's.
(c) The same as (a), but shaded.
(d) The same as (b), but shaded.

Figs. 7 to 10 give the triangular patterns, plain and shaded, produced by repeating the chevron border (see Fig. 2, a).




Fig. 7.




Fig. 8.

- Fig. 7.—(a) Single Border, composed of Triangles.
 (b) Double Border, composed of Triangles, with the points of all the Triangles meeting.
 (c) Surface Pattern, composed of Triangles, with the points of all the Triangles meeting.

Fig. 8.—(a, b, and c) The Patterns shown on Fig. 7, shaded.




Fig. 9.




Fig. 10.

- Fig. 9.—(a) Double Border, composed of Triangles, with the points of the Triangles in one row falling in the centres of the bases of Triangles in the row above.
 (b) Surface Pattern, composed of Triangles, arranged in the same way as in the preceding.

Fig. 10.—(a and b) The Patterns shown on Fig. 9, shaded.

The patterns derived from the lozenge are shown on Figs. 11 to 18.




Fig. 11.




Fig. 12.

Fig. 11.—(a) Lozenge Border, composed of two sets of Chevrons, with their points facing in opposite directions.

(b) The same as (a), but with the Chevrons set apart.

(c) The same as (a), but with bars substituted for lines.

(d) The same as (b), but with bars substituted for lines.

Fig. 12.—(a) Lozenge Border, with Triangles or Chevrons, shaded.

(b) Lozenge Border, with Lozenges shaded.

(c) The same as Fig. 11 (c), but shaded.

(d) The same as Fig. 11 (d), but shaded.




Fig. 13.

Fig. 13.—(a) Surface Pattern, produced by repeating the Bar-Chevron Border, so that the points of all the Chevrons meet.
 (b) The same as (a), but with the Chevrons set apart.




Fig. 14.

Fig. 14.—(a) The same as Fig. 13 (a), but shaded.
 (b) The same as Fig. 13 (a), but shaded.

D







Fig. 15.

Fig. 16.

Fig. 15.—(a) Line Lattice-work Surface Pattern, produced by the repetition of either the Chevron Border, Fig. 2 (a), or the Lozenge Border, Fig. 2 (b).

(b) The same as (a), but shaded.

Fig. 16.—(a) The same as Fig. 15 (b), but with shaded Lozenges of two different sizes.

(b) Lattice-work Surface Pattern; the same as Fig. 15 (b), but with diagonal white bars instead of lines.




Fig. 17.




Fig. 18.

Fig. 17.—(a) Bar Lattice-work-Surface Pattern; the same as Fig. 15 (a), but with diagonal bars instead of lines.

(b) The same as (a), but shaded.

Fig. 18.—(a) Surface Pattern, produced by repeating Fig. 11 (c).

(b) The same as (a), but shaded.

The patterns derived from the saltire are shown on Fig. 19.




Fig. 19.

(a) Saltire Border Pattern.

(b, c, d) Saltire Border Pattern, shaded in different ways.

(e) The same as (a), but with bars instead of lines.

The patterns derived from the hexagon are shown on Figs. 20 and 21.




Fig. 20.




Fig. 21.

Fig. 20.—(a) Hexagon Border Pattern, derived from the Lozenge Border, Fig. 2 (b), by leaving out every other X.

(b) The same as (a), but with the Triangles shaded.

(c) The same as (a), but with the Hexagons shaded.

(d) Surface Pattern, composed of Hexagons and Triangles; produced by repeating (c), so that the Hexagons in one horizontal row adjoin the Triangles in the next.

Fig. 21.—(a) Hexagon Surface Pattern, probably derived from Fig. 11 (b), by drawing straight lines between the points of each of the Chevrons.

(b) The same as (a), but with bars instead of lines, and having the Hexagons shaded.

The variations in the practical application of the chevron patterns, which have been described above,

to the decoration of the sepulchral pottery of the Bronze Age, are produced in the following ways:—

- (1) By placing the chevrons (*a*) horizontally, or (*b*) vertically.
- (2) By making the chevrons of different sizes.
- (3) By altering the angle of the chevrons, *i.e.* making the points more acute or more obtuse.
- (4) By shading some parts of the pattern whilst other parts are left plain.
- (5) By using different methods of shading, such as plain hatching, cross-hatching, dotting, etc.
- (6) By combining the chevrons with horizontal and vertical lines.
- (7) By arranging the patterns in horizontal bands of different widths.

In a few cases¹ hexagonal figures occur in the decoration of the urns, but the patterns do not belong to the true hexagonal system of ornament. The hexagons were arrived at by leaving a space between the triangles of the chevrons, as on a drinking-cup found at Rhos-heirio,² Anglesey.

The decoration of the urns is generally confined to the exterior, the only exceptions being the interiors of the lips of some of the examples and the crosses in relief found on the bottoms inside of cinerary urns from Wilts, Dorset, and Sussex.

The incense-cups have occasionally ornament on the bottoms of them which, like the crosses just mentioned, may have a symbolical significance.

Some of the urns from Ireland, Scotland, and the Isle of Man, are very beautifully decorated with sunk triangles and ovals.

¹ Ll. Jewitt's *Grave Mounds and their Contents*, p. 108. Folkton, Yorkshire.

² *Archæologia Cambrensis*, 3rd ser., vol. xiv., p. 271; *British Barrows*, p. 70.

The different types of urns are not all equally highly ornamented. The large flower-pot-shaped cinerary urns have least decoration, being sometimes quite plain, but in the majority of cases having a broad band of ornament round the top. The drinking-cups are more elaborately decorated than any other class of sepulchral pottery, although the food-vessels are also nearly as ornate.


The artistic quality of the decoration varies in different parts of Great Britain. Some of the most beautiful examples come from localities where there was a great mixture of aboriginal blood with that of the Celtic invaders, and it is not unlikely that the infusion of new blood may have had something to do with the excellence of the art.

The chevron, although it was more highly developed as a decorative art-motive in the Bronze Age than at any other period, was not unknown to the Neolithic inhabitants of Great Britain, and it is more than probable that the Goidelic Celts got the idea from them. Several shallow vessels with a band of chevron ornament round the rim were found in the chambered cairn at Unstan,¹ Orkney, which is of the later Stone Age. This particular chevron pattern occurs frequently in the Bronze Age. Each of the triangles formed by the chevron is filled in with hatched lines running diagonally, but alternately in directions at right angles to each other (Fig. 4, *d*, p. 30). The pattern had no doubt a structural origin, and was suggested by lashing of the description used for the hafting of stone axes, or by some similar bandaging of cords.²

¹ Dr. J. Anderson's *Scotland in Pagan Times: Bronze and Stone Ages*, p. 294.

² Prof. A. C. Haddon's *Evolution in Art*, p. 87.

A similar chevron pattern is to be seen on a bowl from the Dolmen du Port-Blanc, Saint Pierre, Quiberon, Morbihan, Brittany.¹ Possibly this may be the survival of a strengthening band of basketwork round the vessel.



Bronze Spear-heads ornamented with rows of dots

In the Museum of the Royal Irish Academy, Dublin

The decoration of the bronze implements, gold lunulæ, and jet necklaces of the Bronze Age corresponds very nearly with that of the sepulchral pottery. All the

¹ Paul du Chatellier's *La Poterie aux Époques préhistorique et Gauloise*, pl. 12, fig. 12.

designs are founded upon the chevron, and the only differences are in the methods of execution. On the objects of metal the patterns are produced by the



Gold Lunula from Killarney

Now in the Museum of the Royal Irish Academy, Dublin

hammer, punch, and graver,¹ and on the flat jet beads of the necklaces by a borer.

The bronze implements most frequently decorated are celts and razors, and more rarely dagger-blades and spear-heads.

¹ Sir W. Wylde's *Catal. Mus. R. I. A.*, p. 388.

Of the three classes of bronze celts, namely,¹

- (1) Flat celts,
- (2) Winged and flanged celts,
- (3) Socketed celts,

it is only the first two that are decorated with chevron patterns in the same way as the sepulchral pottery. The socketed celts, which are later than the others, are ornamented with concentric circles resembling those on certain Gaulish terra-cotta figures.²

On some of the bronze spear-heads in the Museum of the Royal Irish Academy the ornament consists of lines of small dots. The dotted patterns in the Irish MSS. of the Christian period may possibly be traced to this source.

The greatest number of gold lunulæ, most of which exhibit the characteristic chevron-motive decoration of the Bronze Age, have been found in Ireland. Dr. W. Frazer has compiled a list of known examples, which will be found in the *Journal of the Royal Society of Antiquaries of Ireland*.³ The numbers are as follows:—

Museum of the Royal Irish Academy	. 32
British Museum	11
Edinburgh Museum	4
Belfast Museum	1
Private Collections	3
Present owners unknown	9
Found in France	2

The decoration consists of very fine lines executed with chisel-edged punches,⁴ and it is concentrated on the edges and the two horns of the crescent, the broad

¹ *Early Man in Britain*, p. 350; and *British Museum Bronze Age Guide*, p. 40.

² *Archæologia Cambrensis*, ser. 3, vol. xiv., p. 308.

³ 5th ser., vol. vii., p. 41.

⁴ Sir W. Wilde's *Catal. of Antiquities of Gold in Mus. R. I. A.*, p. 10.

part of the crescent in the middle being quite plain, as will be seen in the specimen illustrated on page 40 from Killarney, now in the Museum of the Royal Irish Academy in Dublin.

The lunulæ were probably worn as head-dresses or else round the neck, and the contrast between the large expanse of burnished gold and the delicately engraved patterns must have been very effective when seen flashing in the bright sunlight.

Some of the finest examples of jet necklaces have been found with Bronze Age burials in Scotland, as at Balcalk, Forfarshire; Tayfield, Fife; Torrish, Sutherlandshire;¹ Assynt, Ross-shire;² Melfort, and Argyllshire. They have also been found occasionally in England, as at Middleton Moor,³ Derbyshire.

The beads of which the necklaces are composed are of three different shapes, ovoid, flat triangular plates, and four-sided flat plates. The flat beads are decorated with chevrons, triangles, and lozenges produced by rows of dots. Here again we have an instance of a kind of decoration which survived in Christian times.

The last class of remains exhibiting Bronze Age decoration are the sculptured rocks and stones. Some of the carvings are found on natural rock surfaces and boulders; others on such megalithic monuments as stone circles, dolmens, and chambered cairns; whilst numerous examples are on the slabs forming the covers or sides of sepulchral cists.

Although the megalithic structures called by the late Mr. James Ferguson "rude stone monuments" un-

¹ Dr. J. Anderson's *Scotland in Pagan Times: Bronze and Stone Ages*, pp. 53, 55, and 56.

² Daniel Wilson's *Prehistoric Annals of Scotland*.

³ Bateman's *Ten Years' Diggings*, p. 25.

doubtedly belong as a class to the Neolithic period, yet some of them exhibit decorative forms which are characteristic of the Bronze Age. This suggests the interesting speculation whether the ornamental patterns used by the Celts in the Bronze Age may not have been to a large extent borrowed from the Neolithic aborigines, and also whether the absorption of the Iberian peoples by the conquering Goidels may not have had a stimulating effect on decorative art.

However this may be, it is a curious fact that the best specimens of Bronze Age ornament sculptured on stone exist in the Co. Meath, in Ireland, where such an admixture of race would be most likely to occur, and the type of monument on which the carvings are found belongs to the Neolithic period. In Ireland, therefore, either the erection of dolmens, chambered cairns, and other similar structures must have survived during the Bronze Age, or else the characteristic patterns of the Bronze Age must have been derived from a Neolithic source.


The wonderful series of chambered cairns at Newgrange, near Drogheda, and at Sliabh na Calliaghe, near Oldcastle, both in the Co. Meath, have been well known to archæologists for many years, but it is only quite recently that their decorative sculpture has been studied scientifically by Mr. George Coffey, M.R.I.A., the Curator of the Museum of the Royal Irish Academy in Dublin. The following account has been compiled chiefly from Mr. Coffey's admirable monographs on the subject, published in the *Transactions of the Royal Irish Academy*.¹

The great prehistoric cemetery, which has been identified with the Brugh na Boinne mentioned in the

¹ Vol. xxx., p. 1.

Leabhar-na-h-Uidhri and in the Book of Ballymote, is situated five miles west of Drogheda, extending thence about three miles along the northern bank of the Boyne towards Slane. Amongst the most important of the sepulchral remains are the three great tumuli of Dowth, Newgrange, and Knowth, taking them in order from east to west. Two of the tumuli certainly contain chambers, access to which is gained by a passage leading from the exterior, and the third, judging from analogy, probably is also chambered. The Boyne tumuli are recorded in the *Annals of Ulster* to have been plundered by the Danes in A.D. 862. The chamber of the Dowth tumulus has been open since 1847; that of Newgrange since 1699, when it was first entered in modern times by Edward Lhuyd, the keeper of the Ashmolean Museum at Oxford; and that of Knowth still remains to be explored.

The sculptures at Newgrange are of such exceptional interest that it is desirable to give a brief description of the structure upon which they are found. The tumulus stands less than a quarter of a mile north-east of Newgrange House, the Dowth tumulus being $1\frac{1}{4}$ to the north-east, and the Knowth tumulus three-quarters of a mile to the north-west. The Newgrange tumulus is surrounded by a circle of stones originally consisting of thirty-five upright monoliths, twelve of which may still be traced. Four of the standing stones near the entrance are from 6 to 7 feet in height, but the remainder are of smaller size. Between the circle and the base of the mound is a ditch and a rampart of loose stones. The tumulus is also of loose stones, surrounded at the base by a continuous curb of great slabs of stone from 8 to 10 feet long, laid on edge, above which is a retaining wall of dry rubble 5 or 6 feet high. The tumulus is



Longitudinal section of Chamber and Passage of Tumulus at Newgrange, Co. Meath.

approximately circular in plan, 280 feet in diameter, and 44 feet high. The area occupied by the mound alone is at least an acre. The entrance to the passage leading to the chamber is on the S.E. side of the mound, and the passage runs in a N.W. direction. The chamber is not in the centre of the mound, but to the S.E. side of the centre. The plan of the passage and chamber is irregularly cruciform, the dimensions being as follows :—

	Feet.	Inches.
Length of passage	62	0
Length from end of passage to back of N.W. recess	18	0
Average width of passage	3	0
Width of chamber from back of N.E. recess to back of S.W. recess	21	0
Height of passage varies from 4 ft. 9 in. to	7	10
Height of chamber	19	6
Depth of N.E. recess	8	8
„ N.W. „	7	6
„ S.W. „	3	4

The side walls of the passage and chamber are constructed of tall upright stones, having the interstices filled in with rubble work. The passage is roofed over with single lintel stones. The roof of the chamber is in the form of an irregular six-sided truncated pyramid composed of stones corbelled out until they meet sufficiently near together at the top to be covered by a single slab. The floor was originally paved with carefully selected, water-rounded pebbles. These with equal originality and care have been removed by the Irish Board of Works, and placed in the bottom of the pit dug in front of the carved stone at the entrance.

There are on the floor four rudely made shallow stone

basins, one in each of the three recesses, and the fourth in the centre of the chamber. The one in the middle of the chamber was taken from the position it formerly occupied on the top of the basin in the N.E. recess (where it was seen by Edward Lhuyd in 1699), and placed where it now is by the over-officious zeal of the Irish Board of Works. The large stones used in the construction of the chamber are of the lower silurian grit of the district.


The following stones of the Newgrange Tumulus are sculptured :—

On exterior of Mound at Base.

- No. 1.—Above entrance of passage leading to chamber.
- No. 2.—Front of entrance.
- No. 3.—Nearly in a line with axis of passage prolonged to cut circumference of mound on N.W. side.
- No. 4.—N. side of monud.

In Passage.

- N.E. side—twenty-one uprights—Nos. 3, 12, 18, and 21 sculptured, counting from entrance inwards.
- S.W. side—twenty uprights—Nos. 10, 11, 17, and 20 sculptured, counting from entrance inwards.



Plan of Chamber and Passage of Tumulus at Newgrange, Co. Meath

In Chamber.

Seventeen uprights—Nos. 2, 3, 4, 10, and 16 sculptured, commencing at end of passage S. W. side, and counting round from right to left. Nos. 2, 3, and 4 are in S. W. recess, where there is also a horizontal stone above No. 3 sculptured. No. 10 forms the N. E. jamb of the N. W. recess. No. 16 forms the S. E. jamb of the N. E. recess, which has also a sculptured roofing-stone. The horizontal lintel-stone over the opening of the passage into the chamber is sculptured.

Analysing the sculptured decoration of the Newgrange tumulus, we find it to consist partly of chevron



Spiral Ornament at Newgrange,
Co. Meath.
Scale $\frac{1}{2}$ linear

patterns and chevron derivatives (such as combinations of the triangle and lozenge), and partly of spiral ornament, together with a few designs formed of circles grouped round a lozenge, and some cups and rings. The chevron patterns have already been noticed on sepulchral urns, bronze implements, and jet necklaces of Great Britain, and concentric circles on socketed bronze celts, but spiral ornament

is conspicuous by its absence on any of these classes of objects. Spirals are only known to occur on sculptured stones and rock-surfaces in Great Britain, and on a few of the remarkable stone balls with knobs found in Scotland. The following examples have been recorded :—



Slab with Spiral Ornament outside entrance to passage of Tumulus
at Newgrange, Co. Meath
From a drawing by George Coffey, M.R.I.A.

ENGLAND

CUMBERLAND.

Maughanby (Stone circle surrounding cist under tumulus).
Old Parks, Kirkoswald (Upright slab under tumulus).

LANCASHIRE. Calderstones, near Liverpool (Stone Circle).

NORTHUMBERLAND. Morwick (Rock surface).

Lilburn Hill Farm (Slabs of stone found in grave).

WALES

MERIONETHSHIRE. Llanbedr (Slab of stone found near hut-circles, now in Llanbedr churchyard).

SCOTLAND

ORKNEY. Eday (Stone in Pict's House, now in the Edinburgh Museum).

Firth (Slab of stone, now in the Edinburgh Museum).

ELGINSHIRE. Strypes (Standing stone).

Elgin (Stone ball).

ABERDEENSHIRE. Towie (Stone ball, now in the Edinburgh Museum).

Lumphanan (Stone ball, now in collection of Hugh W. Young, Esq., F.S.A., Scot.).

ARGYLLSHIRE. Achnabreac (Sculptured rock-surface).

AYRSHIRE. Coilsfield (Cist-cover).

Blackshaw (Rock-surface).

PEEBLESHIRE. La Mancha (Slab of stone, now in the Edinburgh Museum).

WIGTONSHIRE. Camerot Muir, Kirkdale (Standing stone).

DUMFRIESHIRE. Hollows Tower, Eskdale (Door-sill).

IRELAND

Co. MEATH. Newgrange (Chambered Cairn).

Dowth (Chambered Cairn).


Loughcrew (Chambered Cairn).

King's Mountain (Chambered Cairn).

- Co. LOUTH. Killing Hill, Dundalk (Sepulchral Chamber).
 Co. TYRONE. Knockmany (Chambered Cairn).
 Co. FERMANAGH. Castle Archdall (Sepulchral Chamber).
 Co. DONEGAL. Glencolumbkille (Sepulchral Chamber).

Spiral ornament is as conspicuously absent on the implements and objects of the Bronze Age in Gaul as in Britain. It is, then, to Scandinavia that we must look for the origin of the Bronze Age spirals found in this country.

In the museums at Copenhagen, Stockholm, and Christiania, may be seen splendid specimens of bronze axes, sword-hilts, and personal ornaments exhibiting spiral decoration in the greatest perfection. These are fully illustrated in A. P. Madsen's monograph on the Bronze Age, in the works of O. Montelius and J. H. A. Worsaae, and in the *Transactions* of the various archæological societies in Sweden and Denmark.




Spiral Ornament
on Bronze Axe-
head from
Denmark

The spirals with which the objects of the Bronze Age in Scandinavia are decorated are generally arranged with their centres at equal distances apart, and connected together by S- or C-shaped curves; the former being the most common.

When spirals are arranged in a single row, the problem of how to connect the whole together so as to form a continuous running pattern does not present much difficulty, but if it is required to cover a large surface with spirals in groups of three or of four, all properly connected, the solution is not so easy as it appears at first sight. Both the metal-workers who made the Scandinavian bronze implements, and the artist who designed the sculptured decoration of the Newgrange tumulus, seem to have been unable to

master the method of arranging the S- and C-shaped connections of the spirals in proper order,¹ so as to be capable of extension in every direction over a surface of any required size. The difficulty was got over by a most ingenious artifice, as Mr. George Coffey was



Bronze Axe-head with Spiral Ornament from Sweden

the first to point out in his monograph on "Newgrange, Dowth, and Knowth" in the *Transactions of the Royal Irish Academy* (vol. xxx., p. 25). When the spirals

¹ That is to say, the way of placing the centres of the spirals in relation to each other, and of determining how many S- or C-shaped curves should run to each centre.

are not arranged and connected together in accordance with the requirements of geometry, some of the bands which compose the ornament have loose ends, *i.e.* run to nowhere. The question was how to dispose of the loose ends so as to deceive the eye and give the appearance of a continuous pattern. It was effected very simply by carrying the loose ends right round one or more of the other spirals so as to enclose them. Good instances of this occur on the sculptured slabs at Newgrange (p. 48), and on the carved stone ball from Towie, Aberdeenshire, now in the Edinburgh Museum of Antiquities.

Mr. G. Coffey's theory, in which we feel inclined to agree, is that the spiral motive came to Ireland from Scandinavia across Scotland and the north of England. Both the geographical distribution of spirals sculptured on stone in Great Britain, and the fact that the same imperfect method of connecting the spirals together for all-over surface treatment is found in Ireland, Scotland, and Scandinavia certainly lend support to this view.

It is now generally admitted by archæologists that the spiral decoration of the Bronze Age in Scandinavia is of Mycenæan origin; and the clearest possible proof is furnished by an associated spiral and lotus motive design upon a bronze celt from Aarhøj,¹ near Aalborg, Jutland, which finds an exact parallel in the ornament upon a gold pectoral from Mycenæ.²

The Mycenæan spiral decoration has furthermore been clearly proved by Mr. Goodyear in his *Grammar of the Lotus* to have been borrowed from ancient Egypt; the best instance of the transference of a spiral and lotus motive pattern from Egypt to the

¹ *Mémoires de la Société Royale des Antiquaires du Nord*, 1887, p. 259.

² Perrot and Chipiez's *Art in Primitive Greece*, vol. i., p. 323.

Ægean being the sculptured ceiling of the beehive tomb at Orchomenos. In Egypt, the spiral is found by itself forming a continuous running border on the scarabs of Usertesen I.¹ (Twelfth Dynasty, B.C. 2758–2714), and combined with the lotus on a scarab at Turin² of the same period. The best examples of the use of the spiral as continuous surface ornament are to be seen, on the ceilings of Egyptian tombs of the Eighteenth Dynasty (B.C. 1633–1500).³

The spiral motive thus was most flourishing in Egypt from the Twelfth Dynasty to the Eighteenth, say from B.C. 2758–1700.⁴ After that it found its way to the Ægean, perhaps as early as 1400 B.C.,⁵ and thence to Hungary, Scandinavia, and Great Britain.

The chambered tumuli at Dowth, on the Boyne, and Loughcrew, near Oldcastle, Co. Meath, resemble the Newgrange tumulus in plan and construction, but the sculptures upon the stones of the chambers and passages are not so obviously of Bronze Age type as those at Newgrange. The designs seem to be more symbolical than ornamental, and from the frequent occurrence of star- and wheel-shaped designs may have to do with sun-worship. The Loughcrew tumuli and their sculptures have been very fully described by Mr. E. A. Conwell, in the *Proceedings of the Royal Irish Academy* (vol. ix., p. 355; and 2nd ser., vol. ii., p. 72); by Mr. George Coffey, in the *Transactions* of the same society (vol. xxxi., p. 23); and by Dr. W. Frazer, in the *Proceedings of the Society of Antiquaries of Scotland* (vol. xxvi., p. 294).

¹ Flinders Petrie, *Egyptian Decorative Art*, p. 21.

² *Ibid.*, p. 22.

³ Prisse d'Avannes, *Histoire de l'Art Egyptien après les Monuments*.

⁴ Flinders Petrie, *Decorative Art in Egypt*, p. 28.

⁵ *Journal of Hellenic Studies*, vol. xii., p. 203.

A certain proportion of the sepulchral cists of the Bronze Age in Great Britain exhibit symbolical or decorative designs. The following is a list of the examples which have been recorded :—

- ROSS-SHIRE. Bakerhill.
ARGYLLSHIRE. Kilmartin.
Carnbân.
CLACKMANNAN. Tillycoultry.
LINLITHGOWSHIRE. Caerlowrie.
Craigie Wood.
LANARKSHIRE. Carnwath.
AYRSHIRE. Coilsfield.
CUMBERLAND. Aspatria.
Redlands, near Penrith.
NORTHUMBERLAND. Ford West Field.
YORKSHIRE. Bernaldby Moor.
Co. TYRONE. Seskin.

The sculpture is usually on the cover-stone of the cist, but in the case of the examples at Kilmartin and at Carnbân it is on the vertical end slabs.

The sculptured designs consist of cups and rings, concentric circles, lozenges, triangles, axe-heads, curved meandering lines, and a few patterns composed of straight lines. The carvings show the same pick-marks that were observed at Newgrange.

The axe-heads on the end slab of the cist at Kilmartin¹ are of the wedge shape common in the early Bronze Age. Like the stone axes and axe-heads sculptured on the dolmens of Brittany, they probably have a symbolical meaning connected with the worship of some axe-bearing deity such as Zeus.

¹ *Jour. Brit. Archaeol. Assoc.*, vol. 36, p. 146.

The designs, composed of triangles alternately covered with dots and left plain, which occur on the cist-cover from Carnwath,¹ we have already seen sculptured at Newgrange and engraved on bronze axes and jet necklaces. The grouped circles on the cist-cover from Craigie Wood² may also be compared with those on the slabs in the Newgrange tumulus, on the stone ball from Towie in the Edinburgh Museum, and on the chalk drums from Folkton in the British Museum.

In three cases (viz. at Coilsfield,³ Carnwath, and Tillycultray)⁴ elaborately ornamented urns of the food-vessel type have been found in the sculptured cists, thus clearly proving the period to which the cists belong.

Sometimes slabs of stone sculptured with cup-marks, cups and rings, and spirals, have been found associated with Bronze Age burials, although not forming parts of a cist. One of the most remarkable discoveries of this kind was made at Old Parks,⁵ near Kirk Oswald, Cumberland. In 1894 a barrow composed of loose stones, 80 feet in diameter and 4 feet high, was opened by the late Chancellor R. S. Ferguson, F.S.A., and when the mound was removed a row of five slabs fixed upright in the ground was disclosed. The stones were in a line pointing north and south, cutting the site of the mound into two halves, and three of them are sculptured with spirals. As many as thirty-two deposits of burnt bones were found in holes scooped out of the natural surface of the ground, together with two orna-

¹ *Proc. Soc. Ant. Scot.*, vol. x., p. 62.

² *Ibid.*, vol. vi., *Appendix*, p. 28.

³ *Ibid.*, vol. vi., *Appendix*, p. 27.

⁴ *Ibid.*, vol. xxix., p. 190.

⁵ *Cumb. and West. Ant. Soc. Trans.*, vol. xiii., p. 389.

mented urns of incense-cup form, fragments of several other urns, and a necklace of canal-coal beads.

A slab of stone sculptured with spirals and concentric circles was found in 1883 on Lilburn Hill¹ Farm near Wooler, Northumberland, associated with seven deposits of burnt bones buried in small circular pits.

Stones sculptured with cups, or cups and rings, have been found either as cover-stones of urns or associated with burials in round barrows at the following places:—

NORTHUMBERLAND. Ingoe.

Black Hedon.

Kirk Whelpington.

CUMBERLAND. Maughanby.

YORKSHIRE. Kilburn.

Ayton Moor.

Claughton Moor.

Wykeham Moor.

DERBYSHIRE. Elkstone.

Sheen.

STAFFORDSHIRE. Stanton.

DORSETSHIRE. Came Down.

SUTHERLANDSHIRE. Dornoch Links.

ABERDEENSHIRE. Greenloan, Cabrach.

A link between the art of the Bronze Age in Britain and the art of Mycenæ is afforded by a rock-sculpture at Ilkley,² Yorkshire, which takes the form of a curved swastika. It belongs to a peculiar class of patterns composed of winding bands and small bosses or dots, of which there are numerous examples in the Scandinavian³ and Mycenæan⁴ metal-work. Perhaps some of


¹ *Archæol. Æliana*, ser. 2, vol. x., p. 220.

² *Jour. Brit. Archæol. Assoc.*, vol. xxxv., p. 18.

³ A. P. Madsen's *Antiquités préhistoriques du Danemark*.

⁴ Schlieman's *Mycenæ*, pp. 166, 167, 169, 264, and 265.

the Late-Celtic designs, in which the arrangement of the long sweeping S- and C-shaped curves is governed by the position of circular bosses they connect, may be descended from the winding-band patterns of the Mycenæan period. For instance, the designs on the enamelled handles of the bowl found at Barlaston,



Winding Band (curved Swastika), sculptured in rock
near Ilkley, Yorkshire
Scale $\frac{1}{2}$ linear

Staffordshire, and on the Ilkley rock-sculpture have obvious points in common, both being founded on the curved swastika.

There are in different parts of Great Britain a great number of rocks and boulders sculptured with cups, generally surrounded by concentric rings, and often having a radial groove leading from the cup outwards.



SPRAL ORNAMENT ON STONE BALL FROM
IOWIE, ABERDEENSHIRE; NOW IN THE
EDINBURGH MUSEUM

SCALE $\frac{1}{1}$ LINEAR



WINDING-BAND CURVED SWASTIKA
ON SWORD-HILT FROM DENMARK




BRONZE SWORD-HILT WITH
WINDING-BAND PATTERN
FROM DENMARK



BRONZE SWORD-HILT WITH
SPIRAL ORNAMENT
FROM DENMARK

The best-known instances are at Ilkley in Yorkshire, Wooler in Northumberland, the district on the east side of Kirkcudbright Bay between Kirkcudbright and the Solway Firth, and Lochgilphead and Kilmartin in



Cup-and-ring Sculptures on rock at Ilkley, Yorkshire

Scale $\frac{1}{2}$ linear

Argyllshire. In a few cases the cup-and-ring sculptures are associated with the wheel-symbol, as at Mevagh, Co. Donegal, and at Cochno, Dumbartonshire. Such sculptures are more likely to be symbolical than decorative, but it would take us too far afield to

discuss their meaning here. Those who wish to pursue the subject further may with advantage consult Sir James Simpson's valuable paper on "Ancient Sculpturings of Cups and Concentric Rings," forming the Appendix to vol. vi. of the *Proc. Soc. Ant. Scot.*

The sculptured rock-surfaces of Great Britain in some respects resemble the "Hällristningar" on the west coast of Sweden. The cup and ring, the wheel-symbol, and the curved swastika are common to both, but the Swedish sculptures are much more elaborate and include figure-subjects, ships, animals, etc. The age of some of the sculptures is indicated by the characteristic shape of the axes (evidently of bronze) held by the figures, and by the fact that the same set of symbols which occur on the rocks are also to be seen on the engraved knives of the Bronze Age found in Scandinavia. The Swedish rock-sculptures are fully described and illustrated in L. Baltzer's *Hällristningar fran Bohuslan*, A. Holmberg's *Skandinaviens Hällristningar*, and the *Mémoires* of the International Congress of Prehistoric Archæology at Stockholm.

Summing up the results of our investigations, we find that the peculiarities in the Pagan Celtic art of the Bronze Age which were transmitted to the Pagan and Christian styles of the Early Iron Age are as follows:—

- (1) The use of the closely coiled spiral.
- (2) The use of rows of dots.
- (3) The use of diagonal lines in preference to those running horizontally or vertically.
- (4) The use of designs founded on the curved swastika.

Of all these the spiral decorative motive is by far the most important, as we shall see in a subsequent chapter.

CHAPTER III

PAGAN CELTIC ART IN THE EARLY IRON AGE

INTRODUCTION OF THE USE OF IRON INTO BRITAIN BY THE BRYTHONIC CELTS, CIRCA B.C. 300

IN a previous chapter we pointed out the difference between the Q and the P Celts, the former being Goidels in the Bronze Age, and the latter Brythons in the Iron Age, when they first arrived in Britain. We will now proceed to consider the nature of the culture introduced with the use of iron into this country from Gaul by the Belgic or Brythonic Celts.

NATURE OF THE CIRCUMSTANCES WHICH HAVE LED TO THE FINDS OF OBJECTS OF THE EARLY IRON AGE IN GREAT BRITAIN

A great variety of circumstances have led to the discovery of objects of the Early Iron Age. Where they have not been buried at any great depth beneath the surface of the ground, the plough¹ has frequently been the means of bringing them to light. The making of roads² and railways,³ drainage of land for agricultural purposes,⁴ military fortifications,⁵ quarrying⁶ and

¹ As at Polden Hill, Somersetshire.

² As at Birdlip, Gloucestershire.

³ As at cuttings near Bedford and between Denbigh and Corwen.

⁴ As at Westhall, Suffolk.

⁵ As at Mount Batten, near Plymouth.

⁶ As at Hamdon Hill, Somersetshire.

mining,¹ have also had their share in helping the archæologist. A considerable number of antiquities which have found their way into the beds of rivers have been recovered in the course of dredging operations for the improvement of inland navigation² and building of bridge foundations.³ Tumuli,⁴ camps,⁵ caves,⁶ sites of towns⁷ and villages,⁸ crannogs,⁹ etc., have yielded a plentiful harvest to the scientific explorer. In some cases the denudation of the wind¹⁰ or the erosion of the sea¹¹ has removed the covering of sand by which the traces of the ancient inhabitants have been concealed for centuries. The rabbit,¹² although the enemy of the farmer, sometimes becomes the friend of the antiquary by throwing up priceless relics of the past out of his burrow. Lastly, pure accident¹³ is now

¹ As at Hunsbury, near Northampton.

² As in deepening the Shannon, Thames, and Witham.

³ As at Kirkby Thore, on the Eden, Westmoreland.

⁴ As at Arras, Yorkshire.

⁵ As at Mount Caburn, near Lewes.

⁶ As at Settle, Yorkshire; Deepdale, Derbyshire; and Kent's Cavern near Torquay.

⁷ As at Great Chesters and Silchester.

⁸ As at Glastonbury, Somersetshire.

⁹ As at Lisnacrogghera, Co. Antrim; Strokestown, Co. Roscommon; and Lochlee, Ayrshire.

¹⁰ As on the Culbin Sands, Elginshire, where in 1827 a sportsman having lost his gunflint, found a splendid Late-Celtic bronze armlet, whilst seeking for another flint on the site of a Neolithic settlement covered with blown sand, except where denuded by the wind.

¹¹ As at Hoylake, in Cheshire, where the encroachment of the sea on the portion of the coast lying between the estuaries of the Dee and the Mersey washes out antiquities of every period from the submarine forest and the sandhills above it.

¹² A beautiful Late-Celtic bronze armlet was found at Stanhope, Peeblesshire, by the tenant of the farm, whilst searching for a rabbit, under a large flat stone on the hillside.

¹³ As in the case of the hoard of gold objects of bullion value, amounting to £110, found at Shaw Hill, Peeblesshire, by a herd-boy who saw something glitter in the ground, and scraped out the torques and other relics with his foot.

and then the agent by which the position of a long-forgotten hiding-place for valuables is made known.

GENERAL CHARACTER OF THE FINDS OF OBJECTS
OF THE EARLY IRON AGE

The general character of the finds of objects of the Early Iron Age is almost as varied as the circumstances which have led to their recovery from oblivion, and they may be classified according to their nature, as follows:—

- (1) Sepulchral remains.
- (2) Remains found on inhabited or fortified sites.
- (3) Hoards of objects purposely concealed.
- (4) Objects accidentally lost.

Sepulchral Remains.—The sepulchral deposits of the Early Iron Age differ greatly, both as regards the methods of burial adopted in each case, and the kind of grave-goods placed with the deceased. This is to be accounted for by a difference of time rather than area; and it is only natural to find the Bronze and Iron Ages merging into one another, whilst towards the close of the Late-Celtic Roman and even Saxon influence began to be felt.

Possibly the earliest sepulchral remains of the Late-Celtic period that have been found in England are the burials under mounds at Arras, on the Yorkshire Wolds, which were explored by the Rev. E. W. Stillingfleet, D.D.,¹ in 1815–17, and the Rev. Canon W. Greenwell² in 1876. The bodies were not cremated, as was generally the case in the Bronze Age, and also subsequently during the Romano-British period; but were

¹ *Memoirs of the Meeting of the British Archæological Institute held at York in 1846*, p. 26.

² Greenwell's *British Barrows*, p. 454.

buried in excavations in the chalk, and the place of sepulture marked by a tumulus. The so-called Queen's Barrow at Arras, when opened by the Rev. W. Stillingfleet, was found to contain the skeleton of a female, with the feet gathered up, and the head to the north. The grave-goods consisted of one hundred glass beads, two bracelets, rings of gold and amber, and a pair of tweezers.

In another barrow at Arras, the Rev. W. Stillingfleet discovered the remains of a warrior resting on the smooth pavement of a circular excavation in the chalk, 8 to 9 yards in diameter, and 1 foot 6 inches deep, lying on his back, with his arms crossed over the breast. He had been interred with his chariot, a pair of horses completely harnessed, and two wild boars.

A third barrow explored by the Rev. W. Stillingfleet also covered the skeleton of a warrior with the remains of his martial equipment, consisting of the bosses of his shield, one wheel of his chariot, two of his horses' bridle-bits. Two wild boars' tusks (one of which was perforated with a square hole, and enclosed in a case of thin brass) were associated with this burial; indicating, perhaps, some religious or superstitious belief connected with this animal.¹

A portion of the antiquities mentioned are now in York Museum, and the Rev. W. Stillingfleet's manu-

¹ A Late-Celtic boar's head of bronze was found at Liechaston, in Banffshire, in 1816 (see Dr. J. Anderson's *Scotland in Pagan Times: Iron Age*, p. 117). Three little bronze figures of boars, from Hounslow, now in the British Museum, are illustrated in the *Proc. Soc. Ant. Lond.* (2nd ser., vol. iii., p. 90); and the splendid bronze shield from the Thames at Battersea, in the same collection, has a boar represented upon it (see Kemble's *Horæ Ferales*, pl. 14). The boar also occurs on one of the Scotch symbol-bearing slabs at Knock-na-Gael, near Inverness (see Stuart's *Sculptured Stones of Scotland*, vol. i., pl. 38). For a boar on a helmet, see account of Benty Grange tumulus on p. 67.

script notes on his diggings in 1815-17 are preserved in the Library of the York Philosophical Institute.

The barrow at Arras, opened by the Rev. Canon W. Greenwell, covered a circular grave, 12 feet in diameter, sunk in the chalk to a depth of 3 feet, on the floor of which was laid the skeleton of a woman, resting on the left side, with her left hand up to the face, and the head to the west: Two tame pigs were buried with the deceased, and the grave-goods comprised an iron mirror, a bronze harness-ring, a pair of iron chariot-wheels, two snaffle-bits, and what may have been a whip-shank.

In 1875 Canon Greenwell explored a tumulus near Beverley, in Yorkshire, which yielded two chariot-wheels and a bridle-bit, but no human or other bones.

In July, 1897, Mr. J. R. Mortimer, of Driffield, opened 16 out of a group of 178 barrows, called "Danes' Graves," near Pockthorpe Hall, two miles west of Kilham, E. R. Yorkshire.¹ The burial-mounds were from 10 to 33 feet in diameter, and from 1 foot 3 inches to 3 feet 6 inches high, covering graves, either oval or oblong with rounded corners, about 7 feet long by 5 feet wide by 2 feet deep. All the bodies were unburnt and buried in the doubled-up attitude characteristic of the Neolithic period. A beautiful bronze pin, inlaid with shell, was associated with the skeleton of a female in a grave beneath the largest of the mounds, and in another were found two male skeletons buried with a chariot, the iron tyres of the wheels and the iron hoops of the naves of which still remained together with the two iron snaffle bridle-bits of the horses. The antiquities derived from the "Danes' Graves" are now in the

¹ *Reliquary* for 1897, p. 224; *Proc. Soc. Ant. Lond.*, 2nd ser., vol. xvii., p. 119.

Museum of the York Philosophical Society. The average breadth index of the skulls was '735.

The burials just described bear a marked resemblance to those of Gaulish warriors at Berru¹ and at Gorge-Meillet,² both in the Department of the Marne in France, and may have belonged to the Celtic tribe of the Parisi, who gave their name to Paris in Gaul, and who colonised or conquered parts of Yorkshire.

Canon Greenwell describes the result of opening four barrows of the Early Iron Age in the parish of Cowlam,³ in Yorkshire, in all of which were found the skeletons of females, laid on the natural surface of the ground, resting on the left side, with the hands up to the face, and the head to the north-east. The grave-goods from the first barrow consisted of a bronze armet, a bronze fibula with an iron pin, and seventy exquisite blue glass beads; and from the second, of an ornamental armet. From the remaining two barrows only fragments of pottery were obtained.

Mr. J. R. Mortimer explored a grave dug in the chalk, but without any mound above it, in 1868, a quarter of a mile north-east of Grimthorpe⁴ House, near Pocklington, in Yorkshire. It measured 4 feet 6 inches long, by 2 feet 9 inches wide, by 4 feet deep, and contained the skeleton of a young man, placed on the floor of the grave, resting partly on the back, with the knees and head inclined to the left side, the lower extremities drawn up, the hands on the breast, and the head to the

¹ A. Bertrand, *Archéologie Celtique et Gauloise*, 2nd ed., 1889, p. 356.

² E. Fourdrignier, *Double Sépulture Gauloise de la Gorge-Meillet*.

³ *British Barrows*, p. 208, Nos. li. to liv. The results of the exploration are now in the British Museum. The bronze objects are engraved in Sir J. Evans' *Ancient Bronze Implements*, pp. 387, 388, and 400.

⁴ *Reliquary*, vol. ix., p. 180, and Ll. Jewitt's *Grave-Mounds and their Contents*, pp. 237 and 263.

south. Associated with the burial were sixteen bone implements, a sword-sheath, the umbo of a shield, a disc of bronze with repoussé ornament, and bits of rude pottery.

The number of burials of the Early Iron Age that have been found in Great Britain is extremely small as compared with those of the Ages of Stone and Bronze. This would seem to indicate that the period between the introduction of iron into this country and the commencement of the Roman occupation cannot have been very long; and that if the new metal was brought in by a foreign invasion rather than by peaceful commercial intercourse, nothing like the extermination of the native inhabitants, who used bronze and cremated their dead, can have taken place.

As we have seen, a large proportion of the sepulchral remains of the Early Iron Age have been derived from Yorkshire; but other instances have come to light in Derbyshire, Staffordshire, Kent, Gloucestershire, Devon, and Cornwall.

The Rev. Mr. Pegge has given an account in the *Archæologia*¹ of the opening of a tumulus on Garratt's Piece, Middleton Common, Derbyshire, a mile and a half south-east of Arbelows, and ten miles south-east of Buxton. The body had been laid on the surface of the ground, lying east and west. With it were found one of the circular enamelled discs to which reference will be made subsequently; a shallow basin of thin brass, much broken and crushed; and part of the iron umbo of a shield.

At Benty Grange, in Derbyshire, eight miles south-east of Buxton, on the road to Ashbourne, and one mile

¹ Vol. ix., p. 189: letter read May 8th, 1788; and T. Bateman's *Vestiges of the Antiquities of Derbyshire*, p. 24.

north-west of Arbelows, Mr. Thomas Bateman¹ excavated a barrow, about 2 feet high, surrounded by a fosse. The body had all decayed, except the hair; but in the spot where it had been deposited was a remarkable assemblage of relics, consisting of a leathern cup mounted with silver round the edge, and having wheel- or cross-shaped silver ornaments round the bowl; three circular enamelled discs of the same class as those from the Middleton Common tumulus previously described; an iron helmet surmounted by the figure of a hog of iron with bronze eyes, having a small silver cross inlaid on the nasal; a buckle; fragments of chains, etc. This burial, presenting some Celtic characteristics, belongs to a late period, possibly even after the Roman occupation.

Two Early Iron Age burials are recorded as having been discovered in Staffordshire, one at Alstonfield, the other at Barlaston. The barrow near Alstonfield, called Steep Lowe,² was composed of loose stones, and was 50 feet in diameter, and 15 feet high. The Iron Age interment was a secondary one, the tumulus having been made originally in the Bronze or Stone Age. The body was laid on its back; and amongst the grave-goods were a spear-head, a lance-head, and a knife (all of iron), some fragments of a highly ornamented drinking-cup, a stud of amber, and Roman coins of Constantine and Tetricus.

The burial at Barlaston,³ unlike the one just described, was not in a mound, but in a grave, 7 feet long by 2 feet wide, by 1 foot 3 inches deep, cut in the solid red sandstone rock. With the body were associated a

¹ *Ten Years' Diggings*, p. 28.

² Bateman's *Vestiges of the Antiquities of Derbyshire*, p. 76.

³ Ll. Jewitt's *Grave-Mounds and their Contents*, p. 258; and *Archæologia*, vol. lvi., p. 44.



**BRONZE MIRROR FROM BIRDLIP, GLOUCESTERSHIRE;
NOW IN THE GLOUCESTER MUSEUM**

R. W. Dugdale photo.

beautifully ornamented flat bronze ring of Late-Celtic character; three circular, enamelled discs of the type found in the barrow on Middleton Moor; some fragments of a bronze bowl, which Mr. Ll. Jewitt erroneously conjectured to have formed portions of a helmet; and blades of an iron sword and knife.

No discovery of sepulchral remains belonging to the Late-Celtic period surpasses in interest that made in 1879, between Birdlip¹ and Crickley, on the Cotteswold Hills, seven miles south-east of Gloucester, both on account of the completeness of the series of objects buried with the deceased, and the extreme beauty of some of them as works of art.

Whilst repairing the road, Joseph Barnfield unearthed three skeletons interred with the feet to the south, in graves protected by thin slabs of stone placed on edge. The central skeleton was that of a female, and those on each side males. The following grave-goods were associated with the female: a bronze bowl (laid on the face of the deceased); a silver fibula plated with gold; a necklace consisting of thirteen amber beads, two jet beads, and one marble bead; a tubular brass armet; a brass key-handle; a bronze knife-handle ornamented with a beast's head, having small knobs at the ends of the horns; and last, but not least, a superb bronze mirror.

Another very similar find of skeletons in graves formed of stones placed on edge was made in 1833 at Trelan Bahow,² in the parish of St. Keverne, in Cornwall, ten miles south-east of Helston. With one of

¹ See John Bellows, in *Trans. of Bristol and Gloucestershire Archæol. Soc.*, vol. v., p. 137. The objects found are now in the Gloucester Museum.

² See J. Jope Rodgers in *Archæol. Journ.*, vol. xxx., p. 267.

the skeletons was a beautiful bronze mirror, now in the British Museum.

Sepulchral deposits of the same period, which have also yielded mirrors, were brought to light in the course of military works at Mount Batten,¹ near Plymouth, in the spring of 1865. The burials, however, in this case were not in stone-lined graves near the surface, but in pits from 4 feet to 4 feet 6 inches deep, excavated in the disintegrated rock. In addition to a bronze mirror and the handles of two others, the following objects were obtained: two jointed bronze armlets, two plain bronze armlets, four fibulæ, three bronze rings, a bronze cup, an iron dagger, and a pair of shears, black pottery, and fragments of glass. Ancient British coins had been found previously at Mount Batten,³ indicating a settlement here, perhaps in the first century B.C.

The exploration of the Late-Celtic urn-field at Aylesford,³ in Kent, three miles north-west of Maidstone, by Dr. Arthur Evans, has been the means of extending our knowledge of the art of this period in a most unexpected manner, and has supplied the missing links between the culture of Britain in the first three or four centuries B.C., and that of La Tène on the Continent, which in its turn can be shown to have been strongly influenced by the civilisation of the ancient Venetian country at the head of the Adriatic.⁴ The shape of the tall, cordoned, pedestalled vases, and other peculiarities of the pottery from Aylesford, were

¹ See J. Spence Bate in *Archæologia*, vol. xl., p. 500.

² Sir J. Evans' *Ancient British Coins*, pp. 72 and 106.

³ *Archæologia*, vol. lii., p. 315.

⁴ Dr. Arthur J. Evans' third Rhind Lecture on the "Origins of Celtic Art," as reported in the *Scotsman*, December 14th, 1895.

things entirely unknown to archæologists previously, and enable a distinction now to be drawn between the fictile ware of the Late-Celtic period and that of the Romano-British period. The discovery also of bronze objects of Italo-Greek manufacture of the second century B.C., associated with Late-Celtic burials, clearly indicates that there must have been a much more intimate trade-intercourse between Britain and the southern parts of Europe, in pre-Roman times, than has hitherto been suspected.

The Late-Celtic urn-field at Aylesford was uncovered in 1886, at Messrs. Silas Wagon and Son's gravel-pit, in the course of removing the surface earth which here overlies the old river-deposits to a depth of 3 feet or so. One of the first burial-pits which attracted attention was circular, and about 3 feet 6 inches deep, the sides and bottom being coated with a kind of chalky compound. In the pit were found a bronze *situla*, or pail, splendidly ornamented with repoussé work in the Late-Celtic style, and containing calcined bones; an *œnochoe*, or wine-jug; and *patella*, or shallow pan, of imported Italo-Greek fabric; fragments of a second *situla*; a bronze fibula; and fragments of pottery.

From another grave, about 1 foot 6 inches deep, situated 200 yards north-west of Aylesford Church, was obtained a bronze-plated tankard with two handles, of the same class as the Trawsfynydd tankard, surrounded by a circle of five or six earthenware vases, one of these being the finest pedestalled urn collected from the site. All the antiquities from Aylesford are now in the British Museum.

Remains of the Early Iron Age found on Inhabited or Fortified Sites.—Next in importance to the sepulchral remains, as affording indications of the culture of the

Early Iron Age, come the remains derived from inhabited or from fortified sites. And it may be remarked in passing that it is impossible to separate the inhabited from the fortified sites, because in these early times the state of the country was so unsettled that no isolated place of residence, village or town, could afford to do without some means of defence, either natural or artificial.

The inhabited site which bids fair to rival all others in the varied nature of the relics obtained from it, and the light they help to throw on the arts and industries of the Early Iron Age in Great Britain, is the Glastonbury Marsh Village. As the explorations begun by Mr. Arthur Bulleid, F.S.A., in 1892 are still in progress, it would be premature to pass an opinion upon the finds until they are completely exhausted. For an account of what has been already discovered there, the reader is referred to Mr. Bulleid's paper on the subject, which appeared recently in the *Proceedings of the Somersetshire Archæological Society*.¹ A bronze bowl is there illustrated which seems to be of the same kind as those derived from the graves, but it is ornamented with raised bosses instead of with circular plaques of enamel. The handle of a mirror, like those from the graves, was also found at the Glastonbury Marsh Village in 1896.

From the exploration of this settlement we have obtained a knowledge of the peaceful pursuits and methods of life of the Late-Celtic inhabitants, which could never have been derived from their sepulchral remains. We now know that they were expert potters, wood-carvers, coopers, and weavers,² applying the

¹ Vol. xl. (1893).

² Ornamental weaving was, no doubt, practised. Although we have no absolute proof of this, the La Tène helmet from Gorge-Meillet (Marne), previously mentioned, has a sort of swastika pattern upon it, suggestive of a textile origin.

same beautiful flamboyant forms of decoration that are characteristic of the metal-work of the period to earthenware and wooden vessels. The long-handled weaving-combs, which are so well known in the Pictish towers, or *brochs*, of the north of Scotland, have been found here also. Amongst the iron implements was a bill-hook for lopping the branches of trees—a most useful appliance for clearing away undergrowth in forests, procuring firewood, and building wattled structures. Unbaked ovoid clay pellets have been dug up in hundreds. These were probably sling-stones, indicating that the inhabitants must have been expert fowlers.

The dwellings appear to have been circular or oval wattled huts, the rudeness of which stands out in marked contrast to the high artistic taste and technical skill of the inhabitants.

A few of the crannogs of Scotland¹ and Ireland,² whose structure is somewhat analogous to the Glastonbury Marsh Village, have also yielded Late-Celtic objects, but not in such quantities as to give evidence of permanent occupation over a considerable period.

Hunsbury,³ two miles south-west of Northampton, which has been called the English “La Tène,” is a good example of a Late-Celtic *oppidum*. The camp is of oval shape in plan, measuring 560 feet by 445 feet, and defended by a single earthen rampart and ditch.

¹ At Lochlee and at Lochspouts, Ayrshire; Dowalton, Wigtonshire; and Hyndford, Lanarkshire (see Dr. R. Munro's *Lake-Dwellings of Scotland*).

² Lisnacrogghera and Craigywarren, Co. Antrim; Strokestown and Ardakillen, Co. Roscommon; Lagore, Co. Meath; and Ballinderry, Co. Westmeath (see Wood Martin's *Lake-Dwellings of Ireland*).

³ See Sir Henry Dryden in *Associated Architectural Societies' Reports*, vol. xviii. (1885), p. 53.

The area enclosed is about four acres. Between 1880 and 1886 the whole of the interior was excavated to obtain ironstone, which lay in a bed 12 feet thick, at a depth of 7 feet 6 inches below the natural surface of the ground.

In the course of the excavations about three hundred refuse-pits, averaging 5 feet in diameter, and dug in the soil overlying the ironstone, were discovered. Amongst the contents of the pits were two bronze sword-sheaths, one of them highly ornamented in the Late-Celtic style;¹ three fibulæ, bridle-bits and cheek-pieces of bone, a chariot-wheel, iron saws, knives, spear-heads, etc.; one hundred and fifty quernstones, reckoning the upper and lower stones separately; eight spindle-whorls, long-handled weaving-combs, and pottery with Late-Celtic decoration. All these antiquities are now in the Northampton Museum.

The camp on Mount Caburn, two miles south of Lewes, in Sussex, explored by General Pitt-Rivers² in 1878, seems to have been an *oppidum* of the same class as that at Hunsbury, and the relics indicated the same kind of culture. The pits found at Mount Caburn were some of them oval, and others oblong, 5 to 7 feet in diameter, and 5 feet deep. The objects obtained from the pits included ornamental pottery, long-handled wearing-combs, an iron billhook like the one from the Glastonbury Marsh Village, and three ancient British tin coins.

The fine collection of Late-Celtic horse-trappings, etc., now in the Duke of Northumberland's private Museum at Alnwick Castle, was found in 1844, in a pit about 5 feet deep, within an earthen entrenchment

¹ Engraved in the *Archæologia*, vol. lii., p. 762.

² *Archæologia*, vol. xlvi., p. 423.

at Stanwick, in Yorkshire, seven miles north of Richmond.¹

A few Late-Celtic objects have been derived from Roman towns² and stations³ in England; and also from the *wæems*,⁴ or underground houses, and the *brochs*,⁵ or Pictish towers of Scotland.

The bone-caves which were the permanent habitations of Palæolithic and Neolithic man in Britain served as temporary places of refuge for the Brit-Welsh population during the troublous times immediately succeeding the Roman evacuation of this country. Gildas' account of the Britons leaving their houses and lands, and taking shelter in the mountains, forests and caves, whence they were able successfully to repel the inroads of the Picts and Scots,⁶ is fully borne out by archæological research.⁷

The principal caves which have yielded relics of this period are Kirkhead⁸ Cave in Lancashire; the Victoria,⁹

¹ *Memoirs of the Meeting of the Archæological Institute of Great Britain and Ireland at York in 1846*, p. 88; Dr. J. C. Bruce's *Catalogue of the Antiquities at Alnwick*, p. 38.

² As in Silchester. These have not been illustrated, but are to be seen in the Reading Museum.

³ As in Æsica (Great Chesters) (*Archæologia Æliana*, 2nd ser., vol. xvii., p. xxviii.).

⁴ As at Castle Newe, Aberdeenshire, and Grange of Conan, Forfarshire (see Dr. J. Anderson's *Scotland in Pagan Times: Iron Age*, pp. 141 and 160).

⁵ As at Okstrow and at Harray in Orkney (*Ibid.*, pp. 219, 236).

⁶ Gildas, xvii.; Bede's *Eccl. Hist.*, bk. i., chap. xiv.

⁷ Prof. W. Boyd Dawkins' *Cave-Hunting*, p. 106.

⁸ Three miles south of Cartmel, on the shore of Morecambe Bay (*Cave-Hunting*, p. 125).

⁹ A mile and a half north-east of Settle (*Cave-Hunting*, p. 81; and H. Eckroyd Smith in *Trans. of Hist. Soc. of Lancashire and Cheshire*, vol. for 1866, p. 199; and Roach Smith's *Collectanea Antiqua*, vol. i., p. 67).

Kelko,¹ and Dowkerbottom² Caves in Yorkshire; Poole's³ Hole and the Deepdale⁴ Cave in Derbyshire; Thor's⁵ Cave in Staffordshire; and Kent's⁶ Cavern in Devonshire.

The character of the antiquities derived from the caves does not differ materially from that of the remains from the crannogs and the *oppida*, although a few things of peculiar form have been found in some of the caves, such as the spoon-shaped bone-pins from the Victoria and Dowkerbottom Caves, and the bone whistles from Thor's Cave. The fibulæ from the Victoria and the Deepdale Caves are of remarkable beauty. Evidence of spinning is afforded by the long-handled comb from Thor's Cave, and the numerous spindle-whorls from others. The discovery of Roman coins and Samian ware indicate the period at which the Brit-Welsh sought refuge in these recesses of the rock.

Hoards of Late-Celtic Objects purposely concealed.—The horse-trappings found in an excavation at the bottom of one of several oblong pits, 7 feet long by 3 feet wide by 4 feet deep, at Hagbourne Hill⁷ in Berkshire, two miles south of Didcot, seem to have been purposely hidden; as also the horse-trappings which were discovered in the chink of the rock by quarrymen at Hamdon Hill⁸ in Somersetshire, five

¹ Overlooking Giggleswick, one mile north-west of Settle.

² Between Kilnsey and Arncliffe, ten miles north-east of Settle (*Proc. Geol. and Polytech. Soc. of W. Riding of Yorksh.* for 1859, p. 45).

³ A mile south-west of Buxton (*Cave-Hunting*, p. 126).

⁴ Three miles south-east of Buxton (*Derbyshire Archæol. Soc. Trans.*, vol. xiii., p. 196).

⁵ Near Grindon, eight miles north-west of Ashbourne (*Reliquary*, vol. vi., p. 201, and *Trans. Midland Sci. Assoc.*, 1864-5, p. 1).

⁶ One mile north-west of Torquay. There is a fragment of pottery, with Late-Celtic ornament upon it, from Kent's Cavern, in the British Museum.

⁷ *Archæologia*, vol. xvi., p. 348.

⁸ *Ibid.*, vol. xxi., p. 39.

miles west of Yeovil. Another instance of intentional concealment is afforded by the beautiful bronze mirror that was found, with other ornamental pieces of bronze, wrapped in a cloth, and covered by the upper stone of a quern, at Balmaclellan,¹ two miles north-east of New Galloway, Kirkcudbrightshire.

Late-Celtic Objects accidentally lost.—Besides the Late-Celtic objects which have been dropped by their original owners on dry land, and got covered with the soil and thus been preserved, it is remarkable in how many cases they have been lost whilst crossing or navigating rivers, especially the Thames,² Witham,³ Tyne,⁴ and Tweed.⁵

FINDS OF CELTIC COINS IN BRITAIN

The earliest native coinage of Britain belongs to the Iron Age, and dates from 200 to 150 B.C. Sir John Evans has collected together all the known facts relating to the numismatics of this period in his *Coins of the Ancient Britons*, and gives excellent maps showing the geographical distribution of the finds. Prof. John Rhys, in his *Celtic Britain* (p. 19), says :—

“The coinage of Britain had been modelled in the first instance after that of Gaul, which, in its turn, can be traced to the Phocæan Greeks of Massilia or Marseilles, through whom the continental Gauls became acquainted in the latter part of the fourth century before Christ with the gold stater of Philip II. of Macedon. This was a fine coin, weighing

¹ Dr. J. Anderson's *Scotland in Pagan Times: Iron Age*, p. 126.

² Shield (*Archæologia*, vol. xxiii., p. 96); helmet (in the British Museum); fibula (*Proc. Soc. Ant. Scot.*, 2nd ser., vol. xv., p. 191).

³ Shield (*Archæologia*, vol. xxiii., p. 96); sword-sheath (J. C. Bruce's *Catal. of Alnwick Mus.*); daggers (Kemble's *Horæ Ferales*, pl. 17).

⁴ Fibulæ (*Illustrated Archæologist*, vol. ii., p. 157).

⁵ Sword-sheath (*Archæologia*, vol. xlv., p. 45).

133 grains, and having on one side the head of Apollo wreathed with laurel, while the other showed a charioteer in a biga, with Philip's name underneath. It was imitated by the Gauls fairly well at first, but as it got further removed from the original in time and place, the figures degenerated into very curious and fantastic forms."

Before the landing of Julius Cæsar in Britain in 55 B.C. the Cantii, the Dutoriges, the Catuvelauni, and the Trinovantes each had coinages of their own, but entirely devoid of lettering. The lettered coins begin with those of Commios, dating from a period some time before 30 B.C., after which come those of his three sons—Tincommios, Verica, and Eppillos. Prof. J. Rhys¹ says:—

"The coins of Commios, and some of the earlier ones of Tincommios, continued the degenerate imitations of the Macedonian stater without showing any Roman influence; but it was not long after Augustus became emperor, in the year 30, that Tincommios copied the Latin formula, in which the former styled himself *Augustus Divi Filius*, or the son of his adoptive father, Julius Cæsar, who had now got to be officially called *Divus*, or the god. So Tincommios had inscribed on his money the legend *Tinc. Commi F.*, or even shorter abbreviations, meaning Tincommios son of Commios; and the grotesque traits derived from the stater soon disappear in favour of classical designs of various kinds, proving very distinctly that the influence of Roman art was beginning to make itself felt in the south of Britain."

The coins which have been assigned to the Dobunni (although their exact date, place of issue, and sequence are somewhat doubtful) belong to the series of the Macedonian stater, and show hardly any trace of Roman influence. Their probable date² seems to be between A.D. 1 and 41.

¹ *Celtic Britain*, p. 25.

² *Ibid.*, p. 35.

There was no native British coinage either in Scotland, Wales, or Ireland, and in England the finds do not extend further north than Newcastle-upon-Tyne. The greater part of the finds lie to the south of a line drawn from Wroxeter to the Wash, and east of a line drawn from the same place to Exeter. The geographical distribution of the finds is clearly shown on the map given in Sir John Evans' *Coins of the Ancient Britons*.

GEOGRAPHICAL DISTRIBUTION OF FINDS OF OBJECTS OF THE LATE-CELTIC PERIOD IN GREAT BRITAIN¹

In the present state of our knowledge no very satisfactory deductions can be made from a study of the geographical distribution of the finds of this period, partly because the discoveries have been so imperfectly recorded (more especially in Ireland), and partly because a large number of sites which are probably Late-Celtic still remain unexplored. Another difficulty to be reckoned with is that it is only within the last few years that archæologists have been able to distinguish between what is purely Celtic and what is Romano-British. Indeed, in many cases, in the absence of coins or other evidence, it is quite impossible to determine whether particular finds are of pre-Roman, Roman, or even post-Roman, as the Late-Celtic style of decoration was in vogue throughout the whole of the Pagan Iron Age in Britain, and survived in remote districts after the introduction of Christianity. Then, again, the fact must not be lost sight of that the greater frequency of finds in some districts than others can be accounted for by their having been covered with lakes where crannogs could be easily constructed, or on the limestone

¹ A complete list of the finds as far as recorded is given in the *Archæologia Cambrensis*, 5th ser., vol. xiii., p. 321.

formation, where rock-shelters and caves suitable for temporary places of refuge already existed.

We will take the geographical distribution of the sepulchral remains first. It is most remarkable that up to the present no Late-Celtic burials have been recorded in Wales, Scotland, or Ireland, although finds of objects of the period have been frequent in all three of these countries. The earlier Bronze Age burial customs may, of course, have survived after the introduction of iron, or interments of the Iron Age may have passed unrecognised owing to the rapid decay of the metal implements accompanying the body.

In England the greatest number of Late-Celtic burials have been found in the south-east corner of Yorkshire, near Beverley and Driffield. In most cases the tumuli covering the graves are in large groups, those at "Danes' Graves," near Kilham, numbering 178; those at Arras, near Market Weighton, 200; and those in Scarborough Park, near Beverley, 170. The people to whom these extensive cemeteries belonged probably invaded Britain from the Continent some few centuries before the Roman occupation, and landing at the mouth of the Humber, settled permanently on the east coast of Yorkshire. The people in question had long skulls, and buried their dead in a doubled-up attitude without cremation, which has suggested another less probable theory that they were the direct descendants of the more ancient Neolithic inhabitants of Yorkshire.

In Derbyshire one undoubted Late-Celtic burial has been found¹ and there are a few others which seem to belong to the transition towards the end of the Roman occupation or the beginning of the Saxon Pagan period.²

¹ In Deepdale.

² At Benty Grange, and on Middleton Moor.

In Kent¹ and Devonshire² cemeteries containing a large number of graves have been brought to light.

Isolated burials have been found in single localities in each of the counties of Stafford,³ Gloucester,⁴ Dorset,⁵ and Cornwall.⁶

The following lists show the geographical distribution of the inhabited or fortified sites of the Late-Celtic period in Great Britain :—

CAVES

YORKSHIRE. Dowkerbottom Hole, Arncliffe.

Victoria Cave, Settle.

Kelko Cave, Settle.

LANCASHIRE. Kirkhead Cave.

DERBYSHIRE. Thirst House, Deepdale.

Poole's Hole, near Buxton.

STAFFORDSHIRE. Thor's Cave, Dovedale.

DEVONSHIRE. Kent's Cavern, Torquay.

LAKE-DWELLINGS AND CRANNOGS

SOMERSETSHIRE. Glastonbury Marsh Village.

LANARKSHIRE. Hyndford Crannog.

AYRSHIRE. Lochlee Crannog.

Lochspouts Crannog.

WIGTOWNSHIRE. Dowalton Crannog.

Co. ANTRIM. Lisnacrogghera Crannog.

Craigyarwarren Crannog.

Co. ROSCOMMON. Strokestown Crannog.

Ardakillen Crannog.

Co. WESTMEATH. Ballinderry Crannog.

Co. MEATH. Lagore Crannog.

¹ At Aylesford.

³ At Barlaston.

⁶ In the Isle of Portland.

² At Mount Batten.

⁴ At Birdlip.

⁵ At Trelan Bahow.

CELTIC ART

PICTISH TOWERS

ORKNEY. Broch of Harray.

Broch of Okstrow.

CAITHNESS. Broch of Kettleburn.

SELKIRKSHIRE. Broch of Torwoodlee.

UNDERGROUND HOUSES

ABERDEENSHIRE. Castle Newe.

FORFARSHIRE. Grange of Conan.

CELTIC *OPPIDA* AND FORTIFIED VILLAGES

YORKSHIRE. Stanwick.

NORTHAMPTONSHIRE. Hunsbury.

KENT. Bigbury Camp.

SUSSEX. Mount Caburn.

BERKSHIRE. Northfield Farm, Long Wittenham.

DORSETSHIRE. Hod Hill.

Hambledown Hill.

Maiden Castle.

Rotherley.

SOMERSETSHIRE. Ham Hill.

NAIRNSHIRE. Burghead.

PERTSHIRE. Abernethy.

AYRSHIRE. Seamill Fort.

CARDIGANSHIRE. Castell Nadolig.

CARNARVONSHIRE. Treceiri.

ROMANO-BRITISH STATIONS AND TOWNS

NORTHUMBERLAND. Great Chesters (*Æsica*).

Risingham (*Habitancum*).

WESTMORELAND. Brough.

Kirkby Thore.

LANCASHIRE. Ribchester.

YORKSHIRE. New Malton.

NORTHAMPTON. Wellingborough.

SURREY. Farley Heath.

HAMPSHIRE. Silchester.

PERTSHIRE. Ardoch.

DUMFRIES. Birrenswark.

A study of the above lists discloses some interesting facts. It will be noticed that the caves are confined exclusively to the limestone districts of the counties of York, Lancaster, Derby, Stafford, and Devon. The lake-dwellings are found chiefly in the south-west of Scotland and the north-east and central part of Ireland, there being only one example in England and none in Wales. The *brochs* and *weems* (or underground houses) are Pictish structures, and therefore do not occur anywhere except in Scotland, chiefly in its north-eastern counties. The Celtic *oppida* are most common in the south of England where the Belgic settlements predominated, but there are a few examples in Scotland. Probably a more systematic examination of the hill-forts throughout Great Britain would show that those in which large areas are enclosed by double and triple ramparts of stone or earth¹ belong to the Late-Celtic period. At the present time practically nothing is known as to the age of the stone forts and earthen raths in Ireland or Wales.

Most of the Romano-British fortified sites which have yielded works of art of Late-Celtic type, although executed under Roman influence, are in the south of Scotland or in the north of England, on or near the Wall of Hadrian, or along the lines of the military roads leading to it.² At Farley Heath, near Guildford, Surrey, numerous specimens of Kelto-Roman enamelled bronze objects have been found, and this

¹ I refer here to defensive works in which the whole of the summit of the hill is enclosed. These forts are usually of approximately oval shape, and follow the conformation of the hill.

² As, for instance, at Risingham (*Habitancum*) on the road going north from the Wall into Scotland, and at Brough and Kirkby Thore on the road from York to Carlisle, which passes through upper Teesdale, and thence into the valley of the Eden.

site would no doubt produce a plentiful harvest of antiquities of a similar nature if properly explored. The great difficulty, however, as we have already pointed out in dealing with the Romano-British sites, is to determine to what extent the style of the art of the objects found there can be shown to be definitely Celtic. In our lists we have only included sites from which have been procured antiquities exhibiting Celtic enamel and flamboyant ornament, or fibulæ of known Celtic type.

If to the sepulchral deposits and inhabited sites just described be added all the miscellaneous finds of objects accidentally lost or purposely concealed, it will be observed that there is hardly a single county throughout England, Wales, Scotland, and Ireland which cannot show one or two such Late-Celtic finds at least. Some counties are nevertheless richer than others,¹ as, for instance, Aberdeen, Forfar, Perth, Ayr, Kirkcudbright, and Dumfries, in Scotland; Antrim, Meath, and Roscommon, in Ireland; Denbighshire, in Wales; and Northumberland, Durham, Yorkshire, Derbyshire, Suffolk, Middlesex, Kent, Gloucestershire, Oxfordshire, Berks, Wilts, Dorset, Hants, and Somerset, in England.

EVIDENCE AS TO DATES OF FINDS OF OBJECTS OF THE EARLY IRON AGE IN GREAT BRITAIN

The finds of objects of the Early Iron Age to which an approximate date can be assigned are as follows:—

- (1) Finds associated with burials of a particular kind.
- (2) Finds associated with objects of the Bronze Age.
- (3) Finds associated with objects of early Hallstatt type.

¹ *i.e.* have from four to ten localities where Late-Celtic finds have been made.

(4) Finds associated with fibulæ or other objects of La Tène type.

(5) Finds of objects associated with imported articles of Græco-Italic fabric.

(6) Finds of objects associated with Ancient British coins.

(7) Finds of objects, (a) on Romano-British inhabited or fortified sites, (b) associated with Roman coins, and (c) associated with articles of Roman manufacture.

There are at least three different methods of burial characteristic of the Late-Celtic period in Great Britain.

(1) Uncremated burials in excavated graves beneath barrows in which the deceased is generally found with his chariot and horses, as at Arras, Yorkshire.

(2) Cremated burials in pits without any exterior mound, the ashes being contained in cinerary urns and the burials in groups, as at Aylesford, Kent.

(3) Uncremated burials in graves formed of slabs of stone placed on edge, without any exterior mound, as at Birdlip, Gloucestershire.

The first class of burials correspond with those at Berru and Gorge-Meillet, Department of the Marne, and probably belong to the same period as these earlier Gaulish interments which, from the associated Greek and Etruscan relics,¹ are known on the Continent to belong to the third, fourth, and fifth centuries B.C.²

The second, or Aylesford urn field type of burial, is dated by associated vessels of Italo-Greek fabric at from 200 to 150 B.C.³

Implements of the Bronze Age have been occasionally discovered with objects of Late-Celtic character, as at

¹ Such as the Græcwyl bronze vase now in the Berne Museum; the bronze *arnochœ* and Etruscan cup from Somme-Bionne (Marne); and the two-handled cup from Rodenbach, Bavaria (described and illustrated in A. Bertrand's *Archéologie Celtique et Gauloise*, pp. 328 to 347).

² Arthur Evans in *Archæologia*, vol. lii., p. 72.

³ *Ibid.*, vol. lii., p. 66.

Hagbourn Hill,¹ Berks, where a Late-Celtic bridle-bit and harness-rings were associated with some small spear-heads and a socketed celt; and at Hounslow,² Middlesex, where three figures of boars and two of other animals were found with celts and gouges of the Bronze Age.

Up to the present time, no specimen has yet been found in this country of the great iron sword of Hallstatt type, with its massive ivory handle encrusted with amber.³ Of the smaller Hallstatt sword with an iron blade and a bronze handle, having antennæ-like projections at the top,⁴ one specimen from the Thames is to be seen in the British Museum, and there are about half a dozen others in the Museum of the Royal Irish Academy in Dublin.

Tall vessels made of thin sheets of bronze riveted together and furnished with two round ring-handles at the top have been found in Ireland (at Montiaghs,⁵ Co. Armagh; and Dowris,⁶ King's Co.) and in Scotland (at Cardross,⁷ Dumbartonshire); the form of these vessels shows that they are akin to the *situlæ* of the late Hallstatt or early La Tène period on the Continent.

In the instances where other objects have been associated either with the swords *à antennes* or *situlæ* in Great Britain they have been of purely Bronze Age type, showing that the Hallstatt period on the Continent was earlier than the Late-Celtic period in this country.

The forms of the *fibulæ* associated with Late-Celtic

¹ *Archæologia*, vol. xvi., p. 348.

² *Proc. Soc. Ant. Lond.*, 2nd ser., vol. iii., p. 90.

³ A. Bertrand and S. Reinach's *Les Celtes dans les Vallées du Pô et du Danube*, p. 125.

⁴ *Ibid.*, p. 85.

⁵ *Jour. Royal Soc. Ant. Ireland*, ser. 5, vol. vii., p. 437. Another example found in Ireland is figured in Sir W. Wyld's *Catal. Mus. R.I.A.*, p. 531.

⁶ Now in the British Museum. Evans' *Ancient Bronze Implements*, p. 410.

⁷ R. Munro's *Prehistoric Scotland*, p. 40.

finds afford specially valuable evidence as to date. The pre-Roman, or La Tène, type of fibula was made in one piece on the same principle as the modern safety-pin, and therefore differed from the Roman Provincial harp, or bow-shaped fibula, in which the pin was separate from the back and worked on a hinge. Fibulæ of the earlier kind have been found with Late-Celtic burials at Cowlam, Yorkshire; Aylesford, Kent; and Birdlip, Gloucestershire; and on inhabited and fortified sites at Hod Hill, and Rotherley, Dorset. The fibulæ from the Stamford Hill Cemetery, near Plymouth, and the Polden Hill hoard of horse-trappings belong to the later class. As the forms of the different fibulæ will be discussed subsequently, no more need be said on the subject here.

Ancient British coins have been found near the Late-Celtic cemeteries at Aylesford,¹ Kent, and Stamford Hill,² near Plymouth; also within the fortifications of the Late-Celtic *oppida* at Mount Caburn,³ near Lewes, Sussex, and Hod Hill,⁴ near Blandford, Dorset. General Pitt-Rivers came across ancient British coins during his excavations on the site of the Romano-British village at Rotherley⁵ in Cranbourne Chase, Dorset, and numerous specimens (especially of the coins of Verica, one of the three sons of Commios) have turned up from time to time at Farley Heath,⁶ near Guildford, Surrey.

The Romano-British inhabited or fortified sites from which objects of Late-Celtic character have been derived, have already been specified. The following lists show the instances where Late-Celtic finds have been associated with Roman coins or with objects of Roman manufacture:—

¹ *Archæologia*, vol. lii., p. 315.

² *Ibid.*, vol. xl., p. 500.

³ *Ibid.*, vol. xlvi., p. 423.

⁴ *Archæol. Jour.*, vol. lviii., p. 52.

⁵ *Excavations in Cranbourne Chase*, vol. ii., p. 188.

⁶ F. Martin Tupper's *Farley Heath*, p. 10.

Late-Celtic Finds associated with Roman Coins.

Place.	Nature of Find.	Date of Coins.
Victoria Cave, Settle, Yorkshire	Inhabited Site	Trajan to Con- stans, A.D. 98-
Kelko Cave, Giggles- wick, Yorkshire	Inhabited Site	(?) [353-
Dowkerbottom Cave, Arncliffe, Yorkshire	Inhabited Site	Claudius Gothicus to Tetricus, A.D. 268-273
Kirkhead Cave, Cart- mel, Lancashire	Inhabited Site	Domitian, A.D. 81-
Poole's Cavern, Buxton	Inhabited Site	(?) 96
Thirst House, Deep- dale, Derbyshire	Inhabited Site	Antoninus Pius to Gallienus, A.D. 138-268
Thor's Cave, Stafford- shire	Inhabited Site	(?)
Broch of Torwoodlee, Selkirkshire	Fortified Tower	Vespasian, A. D. 69-79
Rotherley, Dorset	British Village	Trajan to Gallie- nus, A.D. 98-268
Kirkby Thore, West- moreland		Vespasian to Sev- erus, A.D. 69-211
Hod Hill, Dorset	Fortified Site	Augustus to Tra- jan, B.C. 27— A.D. 117
Æsica, Northumber- land	Romano - British Station	Mark Antony to Magnentius, B.C. 32-A.D. 353
Farley Heath Alstonfield, Stafford- shire	British Village Burial	(?) Tetricus and Con- stantine, A.D. 268-337
Ham Hill, Somerset	Fortified Site	Valerian to Theo- dosius I., A.D. 379-395
Westhall, Suffolk Chorley, Lancashire	Horse-trappings Fibulæ	Faustina Hadrian, A.D. 117- 138

Place.	Nature of Find.	Date of Coins.
Backworth, Northumberland	Fibulæ	Antoninus Pius, A.D. 138-161
Kingsholm, Gloucestershire	Horse-trappings	Claudius, A.D. 41-54
Castlethorpe, Bucks	Silver Armlet	Verus, A.D. 161-169

Late-Celtic Finds associated with Samian Ware.

Place.	Nature of Find.
Broch of Okstrow, Orkney	Pictish Tower.
Lochlee	Crannog.
Lochspouts	Crannog.
Settle, Yorkshire	Cave.
Deepdale, Derbyshire	Cave.
Thor's Cave, Staffordshire	Cave.
Isle of Portland	Burial.
Westhall, Suffolk	Horse-trappings.

Late-Celtic Finds associated with Objects of Roman Manufacture.

Place.	Nature of Late-Celtic Find.	Class of Roman Object.
Dowalton, Wigtownshire	Crannog	Saucepan
Stanhope, Peeblesshire	Armlet	Saucepan
Polden Hill, Somersetshire	Horse-trappings	Fibulæ
Stamford Hill, near Plymouth	Cemetery	Fibulæ
Castlethorpe, Bucks	Armlet	
Æsica, Northumberland	Fibulæ	Silver necklace, etc.
Hay Hill, Cambridge-shire	Fire-dog	Amphora
Mount Bures, Essex	Fire-dog	Six amphoræ, glass, etc.
Stanfordbury, Bedfordshire	Fire-dog	Bronze jug, Samian ware, etc.

CHAPTER IV

PAGAN CELTIC ART IN THE EARLY IRON AGE

GENERAL NATURE OF THE MATERIALS AVAILABLE FOR THE STUDY OF THE DECORATIVE ART OF THE EARLY IRON AGE IN GREAT BRITAIN

THE materials available for the study of Late-Celtic art in this country may be classified as follows :—

METALWORK.

Arms of Offence and Defence.
Horse-trappings.
Chariot Fittings.
Personal Ornaments.
Toilet Appliances.
Domestic Appliances.
Musical Instruments.
Objects for Religious Use.
Objects of Unknown Use.

POTTERY AND GLASS.

Sepulchral Urns.
Vessels for Domestic Use.
Beads for Necklaces.

WOODWORK AND BONEWORK.

Vessels for Domestic Use.
Dress-fasteners.
Spatulæ.

STONWORK.

Sculptured Monuments.

The arms of offence and defence of the Late-Celtic period are made of metal; the sword-blades, dagger-blades, and lance-heads being of iron; and the sword-sheaths, dagger-sheaths, shields, and helmets of bronze. In this country the bronze objects only are ornamented.¹

Bronze sword- and dagger-sheaths have been found in considerable numbers in England, and also less frequently in Scotland and Ireland, as will be seen from the lists given below.

List of Localities in Great Britain where Bronze Sword-sheaths of the Late-Celtic Period have been found.

Carham	Northumberland.
Embleton	Cumberland.
Houghton le Skerne	Co. Durham.
Sadberge	Co. Durham.
Warton	Lancashire.
Stanwick	Yorkshire.
Catterdale	Yorkshire.
Flasby	Yorkshire.
Grimthorpe	Yorkshire.
Lincoln	Lincolnshire.
Hunsbury	Northamptonshire.
Amerden	Buckinghamshire.
Water Eaton	Oxfordshire.
Dorchester	Oxfordshire.
Boxmoor	Hertfordshire.
London	Middlesex.
Battersea	Middlesex.
Icklingham	Suffolk.
Hod Hill	Dorsetshire.
Moreton Hall	Midlothian.
Glencotho	Peeblesshire.
Bargany House	Ayrshire.
Lisnacrogghera	Co. Antrim.

¹ A lance-head of iron from La Tène, in Switzerland, is ornamented with engraved patterns, but nothing of a similar kind has been found in Great Britain (E. Vouga, *Les Helvètes a La Tène*, pl. 5).

List of Localities in Great Britain where Bronze Dagger-sheaths of the Late-Celtic Period have been found.

River Witham	Lincolnshire.
North Hinksey	Oxfordshire.
Wandsworth	Surrey.
Southwark	Surrey.
Cookham	Berkshire.
Athenry	Co. Galway.

Some of these sheaths are elaborately ornamented, more especially the specimens from Hunsbury, Lisnacroghera, and the River Witham. The shape of the sheaths was evidently derived from a foreign source, as may be seen by comparing those found in Great Britain with the examples from Hallstatt and La Tène.

Bronze shields of the Late-Celtic period are not by any means common, but the British Museum is fortunate enough to possess the only two perfect specimens now in existence. One of these came out of the River Thames at Battersea, and the other from the River Witham, near Lincoln. The former is, perhaps, on the whole, the most beautiful piece of Late-Celtic metalwork that has survived to the present time. It is of oblong shape with rounded corners like the Gaulish shields,¹ and is made out of plates of thin hammered bronze, strengthened all round the edge by a roll moulding. The body of the shield consists of a plain plate upon which are riveted three circular pieces of ornamental repoussé work, the largest one in the centre, and the other two smaller ones at the top and bottom. In the middle of each of the circular pieces of ornament is a raised boss, the annular space surrounding which

¹ See article on the Gaulish statue from Montdragon (Vaucluse) now in the Musée Calvet at Avignon in the *Revue Archéologique*, N.S., vol. xvi. (1867), p. 69; also *Diodorus*, bk. 5, ch. 30.



**IRON DAGGER WITH BRONZE HILT AND SHEATH
FROM RIVER WITHAM**

Reproduced from Kemble's "Hvæ Ferales"

is filled in with gracefully flowing S- and C-shaped curves raised above the rest of the surface, and starting from and returning to small circular plaques of enamel with a swastika design on each. No written description can give any idea of the subtle decorative effect produced by the play of light on the surfaces of the flamboyant curves as they alternately expand and contract in width and rise and fall above the surrounding level background. The drawing of the curves is simply exquisite, and their beauty is greatly enhanced by the sharp line used in all cases to emphasise the highest part of the ridge. It will be observed that the design is set out with regard to small circular bits of enamel placed in definite positions symmetrically round a central boss. If closely coiled spirals like those of the Bronze Age were to be substituted for the enamelled discs, we should then have a style of decoration exactly similar to that of the Christian Celtic MSS. The metalworker who made this shield seems to have possessed the true artistic feeling which told him instinctively exactly how much plain surface of shining bronze should be left to set off the ornament to the greatest advantage. The other shield in the British Museum, from the River Witham, is very inferior to the one just described, and is probably of later date.

Late-Celtic bronze helmets are of great rarity. There are two in the British Museum, one from the Thames at London, and the other from an unknown locality. A third from Torrs, Kirkcudbrightshire, is now preserved at Abbotsford, near Melrose. The specimen from the Thames is furnished with two conical horns terminating in small turned knobs, all the different pieces of wrought metal being riveted together with extreme neatness. The front of the helmet is orna-

mented with small, round enamelled discs and repoussé work in very low relief. The other helmet in the British Museum is shaped like a jockey's cap, and is particularly ugly in appearance.

The helmet at Abbotsford has been so fully described by Dr. Joseph Anderson in his *Scotland in Pagan Times: The Iron Age* (p. 113) that it will not be necessary to say more about it here.

Decorated bronze helmets of the La Tène period have been found in France at Berru¹ (Marne) and Gorge-Meillet² (Marne).

It will be seen from the list given below how extremely common finds of Late-Celtic horse-trappings have been.

*List of Localities in Great Britain where Late-Celtic
Horse-trappings have been found.*

South Shields	.	.	.	Co. Durham.
Stanwick	.	.	.	Yorkshire.
Arras	.	.	.	Yorkshire.
Rise	.	.	.	Yorkshire.
Danes' Graves	.	.	.	Yorkshire.
Kirkby Thore	.	.	.	Westmoreland.
Hunsbury	.	.	.	Northamptonshire.
Locality unknown	.	.	.	Lincolnshire.
Leicester	.	.	.	Leicestershire.
The Fens	.	.	.	Cambridgeshire.
Saham Toney	.	.	.	Norfolk.
Westhall	.	.	.	Suffolk.
Norton	.	.	.	Suffolk.
London	.	.	.	Middlesex.
Canterbury	.	.	.	Kent.
Bapchild	.	.	.	Kent.
Stouting	.	.	.	Kent.
Alfriston	.	.	.	Sussex.
Chessell Down	.	.	.	Isle of Wight.

¹ A. Bertrand's *Archéologie Celtique et Gauloise*, 2nd ed., 1889, p. 356.

² E. Fourdrignier's *Double Sepulture Gauloise de la Gorge-Meillet*.



BRONZE HARNESS-RINGS FROM POLDEN HILL, SOMERSETSHIRE
NOW IN THE BRITISH MUSEUM
SCALE $\frac{1}{4}$ LINEAR

Hagbourn Hill	Berkshire.
Polden Hill	Somersetshire.
Hamdon Hill	Somersetshire.
Abergele	Denbighshire.
Neath	Glamorganshire.
Clova	Aberdeenshire.
Crichie	Aberdeenshire.
Ardoch	Perthshire.
Middleby	Dumfriesshire.
Kirriemuir	Forfarshire.
Henshole	Roxburghshire.
Torwoodlee	Selkirkshire.
Stanhope	Peeblesshire.
Lochlee	Ayrshire.
Dowalton	Wigtownshire.
Birrenswark	Dumfriesshire.
Auchendolly	Kirkcudbrightshire.
Ballycostello	Co. Mayo.
Clooncunra	Co. Roscommon.
Emlagh	Co. Roscommon.
Tara	Co. Meath.
Ballynaminton	King's Co.
Kilkeeran	Co. Monaghan.

Under the head of horse-trappings are included a large number of miscellaneous objects, such as bridle-bits, harness-rings, -buckles, and -mountings, pendants, head ornaments, etc. In fact, the term has been much abused by museum curators, who, when in doubt, say horse-trappings. Much the most important finds, consisting in each case of a large number of objects, have been those made at Polden Hill, Somersetshire, in 1801; Hagbourne Hill, Berks, in 1803; Westhall, Suffolk; Stanwick, Arras, and Rise, Yorkshire; all the objects being now in the British Museum. The specimens from the Saham Toney find, which was equally important, are to be seen in the Norwich Museum.

Other smaller finds are preserved in the museums at Edinburgh and Dublin.

Nearly all the big finds of horse-trappings have included several bridle-bits. These are usually quite plain, but there are, at least, four highly ornamented examples known (1) from Rise,¹ Yorkshire, now in the British Museum; (2) from Birrenswark,² Dumfriesshire, in the Edinburgh Museum; (3) found near Tara,³ Co. Meath, now in the Dublin Museum; and (4) from Kilkeeran,⁴ Co. Monaghan, also at Dublin. These bridle-bits are formed of three or four separate pieces linked together, as in a modern one, and the decoration, which is concentrated on the terminal rings, consists of the usual Late-Celtic trumpet-shaped expansions and coloured *champlevé* enamels.


In nearly all the finds of horse-trappings rings of various shapes and sizes are of frequent occurrence. They were probably used for passing the reins or other parts of the harness through, and perhaps also to act as strap buckles. Most of the rings are round in cross-section, except a segment separated from the rest by projecting flanges, the cross-section of which is made rectangular, apparently to enable the ring to be more rigidly fixed to the harness. The decoration of the rings usually consists of curious projections of various shapes, some resembling pairs of mushrooms placed with the convex tops together and the stems inclined at an angle; whilst others are more like segments of an orange. Many of the rings are ornamented with engraved patterns composed of lines

¹ *Magazine of Art* for 1885, p. 456.

² Dr. J. Anderson's *Scotland in Pagan Times: Iron Age*, p. 124.

³ Sir W. Wilde's *Catal. of Mus. R. I. A.*, p. 605.

⁴ *Journ. R. Hist. and Archæol. Assoc. of Ireland*, N.S., vol. i., p. 423.



Lower ends of Bronze Sword-sheaths from Hunsbury
Now in the Northampton Museum

H

and dots, or are enamelled. The best specimens in the British Museum have been derived from the finds already described at Stanwick, Yorkshire; Polden Hill, Somerset; and Westhall, Suffolk.

The harness-mountings are either in the form of a cross or a sort of rosette, with petals like a flower, some pointed and some round. At the back of the mounting are a pair of rectangular loops for passing a strap through. The front is, in many cases, beautifully enamelled. There is an extremely pretty little cruciform mounting of this kind in the British Museum, but unfortunately the locality whence it came is unknown. Two similar specimens have been recorded, one in the Uffizi Museum at Florence,¹ and another from Saham Toney,² Norfolk, now in the Norwich Museum. The most elaborately decorated harness-mounting of the rosette type is the one from Polden Hill,³ Somersetshire, in the British Museum.

A large number of objects found in Ireland, resembling a spur or the merry-bone of a chicken in shape, have been conjectured to be horses' head ornaments.⁴ One of them was found near Tara, Co. Meath, with the bridle-bit already mentioned.

Iron tyres of chariot-wheels have been found at Stanwick, Arras, Beverley, and Danes' Graves in Yorkshire, and Hunsbury, Northamptonshire; but the bronze objects associated with them, which are believed

¹ Kemble's *Horæ Ferales*, pl. 19, fig. 5.

² *Norfolk Archæology*, vol. ii., p. 398.


³ Kemble's *Horæ Ferales*, pl. 19, fig. 3.

⁴ There are more than thirty-two in the Museum of the Royal Irish Academy (see Wilde's *Catal.*, p. 109). Others have been found in the counties of Roscommon, Sligo, and Cork (see *Proc. R. I. A.*, vol. vii., p. 161; Vallancey's *Coll. de Rebus Hibernicis*, vol. iv., p. 54; and Wood Martin's *Pagan Ireland*, p. 462).



LATE CELTIC BRONZE FIBULA
FROM WALMER, KENT; NOW
IN THE BRITISH MUSEUM

SCALE $\frac{1}{2}$ LINEAR



LATE CELTIC FIBULA FROM IRELAND;
NOW IN THE MUSEUM OF THE ROYAL
IRISH ACADEMY, DUBLIN



ENAMELLED BRONZE FIBULA FROM
KINGTONHAM, NORTHUMBERLAND;
NOW IN THE NEWCASTLE MUSEUM



BRONZE FIBULA, WATER EATON,
OXON; NOW IN THE BRITISH
MUSEUM

SCALE $\frac{1}{2}$ LINEAR

to be the fittings of the chariots, do not afford sufficiently characteristic decoration to need description here.

The personal ornaments of the Late-Celtic period consist chiefly of fibulæ, pins, collars, and armlets, usually of bronze, but in rare instances of gold or silver.

The evolution of the Roman Provincial type of fibula from earlier La Tène type can be nowhere better studied than in this country during the transition from the Late-Celtic to the Romano-British period.

To anyone who is acquainted with the elaborate studies¹ made by Scandinavian archæologists on the origin and development of the various forms of fibulæ found in northern Europe it must be a matter of surprise that up to the present no attempt has been made to do the same thing for our own country. With the exception of Dr. Arthur Evans' paper in the *Archæologia*,² absolutely nothing has been written on the subject in England, nor do the curators of our public museums make the faintest attempt to classify the different kinds of fibulæ of the Romano-British period according to their shapes.

Looked at from a purely mechanical point of view, a fibula, or brooch, belongs to the same class of appliances as an ordinary door-lock; being, in fact, a device for fastening applied to dress. The fibula was probably in its earlier stages evolved from a simple pin by endeavouring to invent some way by which the pin might be prevented from slipping out once it had been

¹ Hans Hildebrand's *Industrial Arts of Scandinavia*; Oscar Montelius' "Spännen från bronsåldern" in the *Antiquarisk Tidskrift för Sverige*; and O. Almagren's *Studien über nordens europäische Fibelformen*.

² Vol. iv., p. 179.

inserted in the fabric of the dress. A sufficiently obvious plan for effecting this is to connect the head of the pin with the point by means of a rigid bar sufficiently bent into the shape of an arch to avoid pressing too closely upon the portion of the dress between it and the pin. When fixed in its place the brooch forms a complete ring, so that a locking and unlocking contrivance is necessary in order to enable it to be removed when not in use.

The modern safety-pin, which is also one of the most ancient inventions, is perhaps the simplest kind of dress-fastener, and yet it is the parent of the almost endless series of European fibulæ from the Bronze Age to the present time. It can be constructed in the easiest possible manner out of a single piece of metal wire of uniform thickness by making a coil in the middle of its length to act as a spring and a point at one end and a hook at the other. The pointed end is then bent round until it catches in the hook, and the thing is complete.

There are two other classes of brooches which do not belong to the safety-pin type or its descendants, namely, (1) the Celtic penannular brooch;¹ and (2) the Northern Bronze Age brooch,² which has a pin with a hole through the head enabling it to slide, turn, and move about loosely on the body of the brooch. With these we are not concerned at present.

Although the safety-pin type of fibula was, in its earlier stages, made out of a single piece of wire, it may be considered to consist of four different parts, each of which performs a function of its own, namely, (1) the head, containing the spring or hinge; (2) the tail, containing the catch, or locking apparatus; (3)

¹ Dr. J. Anderson's *Scotland in Early Christian Times*, 2nd ser., p. 7.

² J. J. A. Worsaae's *Industrial Arts of Denmark*, p. 92.



BRONZE FIBULA FROM CLOGHER,
CO. TYRONE; NOW IN THE
BRITISH MUSEUM

SCALE $\frac{1}{4}$ LINEAR



LATE-CELTIC BRONZE FIBULA,
LOCALITY UNKNOWN; NOW IN
THE BRITISH MUSEUM

SCALE $\frac{1}{4}$ LINEAR



S-SHAPED ENAMELLED BRONZE
FIBULA. LOCALITY UNKNOWN;
NOW IN THE BRITISH MUSEUM

SCALE $\frac{1}{4}$ LINEAR



S-SHAPED FIBULA OF ENAMELLED
BRONZE. FROM NORTON, E. RIDING
OF YORKSHIRE; NOW IN THE
BRITISH MUSEUM

SCALE $\frac{1}{4}$ LINEAR

the body or framework, connecting the head with the tail; and (4) the pin, moving on a hinge or spring at one end and with the pointed end fitting into the catch. In all fibulæ derived from the safety-pin the pin is straight and the body bent into a more or less arched shape, like a bow. An infinite variety of forms were produced (1) by increasing the number of coils in the spring and their size; (2) by expanding the tail end into a thin triangular plate; and (3) by increasing the thickness of the body, or by making a coil in the middle of its length to act as a secondary spring. Much the most important modifications, however, in the safety-pin brooches were those which gradually led up to the harp-shaped, T-shaped, and cruciform fibulæ of the Romano-British period. Dr. Arthur J. Evans, in his paper in the *Archæologia* (vol. lv., p. 179) on "Two Fibulæ of Celtic Fabric from Æsica," has traced the evolution of the harp-shaped fibula from the bow-shaped fibula in a most interesting way. The different stages in the process appear to have been as follows:—

(1) The tail end of the fibula was extended and bent backwards so as to make an S-shaped curve with the bow; (2) the retroflected end of the tail was fixed to the middle of the convex side of the bow by means of a small collar, made in a separate piece; (3) the whole of the back was formed out of one piece of metal, with the collar surviving as a mere ornament; and (4) the triangular opening at the tail, bounded by the retroflected end, part of the bow, and the catch for the point of the pin, was filled in solid with a thin plate. It will be noticed that during this process of evolution the extended and retroflected end of the tail has become part of the continuous curve of the convex side of the bow, whilst what was previously one half of the outside


of the bow is now on the inside of the triangular plate at the tail end. This, together with the expansion of the head to suit the increased number of coils in the spring, produced the characteristic harp-shape of the Romano-British fibula, in many of which the knob ornament in the middle of the back is the last survival of the collar for fixing the retroflected end of the tail in its place.

The cruciform and T-shaped fibulæ, which began in Roman times and continued to be used by the Anglo-Saxons, resulted from extending the coils of the spring at the head symmetrically on both sides of the pin. In this class of fibula the two outside ends of the coil were joined by a loop passing through the inside of the bow so as to give extra leverage to the spring, or sometimes serving merely as a loop for suspension by means of a chain.

A specimen of silver was found at the Warren,¹ near Folkestone, and is now in the British Museum. The lower portion is, unfortunately, broken off, but the retroflected end of the tail remains, with the little ornamental knob which is the survival of the practically useful collar for securing it to the back of the bow. The coils of the spring on each side of the pin and the connecting loop are clearly seen, together with the loose ring passing through the coils of the spring and a portion of the chain for suspension.

An exceedingly pretty pair of harp-shaped fibulæ of silver, with a well-wrought chain for suspension, were found near Chorley, Lancashire, with Roman coins dating from Galba to Hadrian, and are now in the British Museum. At the top of each fibula is a loop for attachment to the chain, and the bodies are beauti-


¹ *The Reliquary* for 1901, p. 197.




BRONZE FIBULA FROM POLDEN HILL,
SOMERSETSHIRE; NOW IN THE
BRITISH MUSEUM
SIDE VIEW, SCALE $\frac{1}{2}$ LINEAR



BRONZE FIBULA FROM POLDEN HILL,
SOMERSETSHIRE; NOW IN THE
BRITISH MUSEUM
FRONT VIEW, SCALE $\frac{1}{2}$ LINEAR



BRONZE FIBULA FROM RIVER CHURN,
NOW IN THE BRITISH MUSEUM
SIDE VIEW, SCALE $\frac{1}{2}$ LINEAR



BRONZE FIBULA FROM RIVER CHURN;
NOW IN THE BRITISH MUSEUM
FRONT VIEW, SCALE $\frac{1}{2}$ LINEAR

fully ornamented with Late-Celtic flamboyant patterns. The knob, which is the survival of the collar already referred to, has here assumed a highly ornamental form resembling two floriated capitals of columns placed together.

The specimen represented on p. 104 is one of a pair of silver-gilt fibulæ, similar to the preceding, but larger and without the chain, although possessing the loops for suspension. They were purchased in Newcastle about the year 1811, and are now in the British Museum. It is stated in Hodgson's *History of Northumberland* (vol. iii., Appendix x., p. 440) that the locality from whence they came was somewhere in the county north-east of Backworth. The fibulæ were discovered in a silver patera bearing a dedicatory inscription to the Deæ Matres, and containing, in addition—

- 5 gold rings.
- 1 silver ring.
- 2 gold chains with wheel pendants.
- 1 gold bracelet.
- 3 silver spoons.
- 1 mirror.
- 280 denarii.
- 2 large brass coins of Antoninus Pius.

A full account of the find is given in E. Hawkins' "Notice of a remarkable collection of ornaments of the Roman period, connected with the worship of the Deæ Matres, and recently purchased for the British Museum" in the *Archæological Journal* (vol. viii., p. 35).

We may here call attention to the intensely Celtic character of the fibulæ just described. The wearing of brooches in pairs with a chain attachment was a Celtic and not a Roman custom, as has already been pointed

out in a previous volume of *The Reliquary* (for 1895, p. 157). A pair of bronze fibulæ, of the same kind as the one from the Warren, Folkestone, fastened together by a double chain, was found in one of the Gaulish cemeteries in the Department of Marne¹ in France, and



One of a pair of silver-gilt Fibulæ found in Northumberland, with Denarius of Antoninus Pius (A.D. 139)

Drawn by C. Praetorius

is now to be seen in the museum of St. Germain, near Paris. It may, therefore, be fairly assumed that all the fibulæ found in this country with chains attached to

¹ Engraved in the *Dictionnaire Archeologique de la Gaule*. Other examples from the cemeteries of Somme Bionne, Courtois, Bussy-le-Château, and Sommesous in the Department of the Marne, are given in the *Album* accompanying L. Morel's *La Champagne souterraine* (pls. 13, 29, 34, and 40).

them or with loops for a chain at the top are more Celtic than Roman.

Amongst the Late-Celtic antiquities in the British Museum are three specimens which illustrate the evolution of the harp-shaped fibula very well. One ornamented with a coral boss and gold stud, probably from the Marne district, was presented by the late Sir A. W. Franks; another came from a chalk pit near Walmer, Kent; and the third was found at Clogher, Co. Tyrone.

Broadly speaking, it may be said that the safety-pin type of fibula made in one piece is earlier in date than the Roman occupation of Britain, and the specimens found in this country are obviously either imported from abroad or copied from foreign originals, such as those found at La Tène, in Switzerland, and in the Champagne district of France. The fibula in use in Britain, after it became a province of the Roman Empire, has a massive harp or bow-shaped back made in a separate piece from the pin and spring. In the earlier, or La Tène type of the fibula, the catch for the end of the pin forms one side of a triangular opening, which, as we have already mentioned, is filled in with a thin plate in the later or Roman Provincial fibula. There is also a sort of transitional kind, with ornamental piercings in the plate.

There was yet another description of fibula belonging to the Romano-British period, having a flat plate for the body in the shape of a circular disc, or sometimes in the shape of a fish or animal.

The different classes of Late-Celtic fibulæ are given in the following lists.

*List of Localities in Great Britain where Late-Celtic
Fibulæ have been found.*

LA TÈNE AND MARNIAN TYPE, WITH TAIL BENT BACKWARDS.

Cowlam (Brit. Mus.)	Yorkshire.
Hammersmith (Brit. Mus.)	Middlesex.
Avebury (Brit. Mus.)	Wiltshire.
Water Eaton (Brit. Mus.)	Oxfordshire.
Clogher (Brit. Mus.)	Co. Tyrone.

LA TÈNE AND MARNIAN TYPE, WITH TAIL BENT BACKWARDS
AND ATTACHED TO BOW.

Aylesford (Brit. Mus.)	Kent.
Folkestone (Brit. Mus.)	Kent.
Walmer (Brit. Mus.)	Kent.
Locality not given (Liverpool Mus.)	Kent.
Datchet	Oxfordshire.

LA TÈNE AND MARNIAN TYPE, WITH FLATTENED
AND EXPANDED BOW.

Ringham Low	Derbyshire.
Hod Hill (Brit. Mus.)	Dorsetshire.
London (Guildhall Mus.)	Middlesex.
Bonville (Brit. Mus.)	Co. Armagh.
Navan Rath (Mus. R.I.A.)	Co. Armagh.
Locality unknown (Mus. R.I.A.)	Ireland.
Hunsbury (Northampton Mus.)	N'hamptonshire.

TRANSITIONAL TYPE, WITH ORNAMENTAL HEAD AND EITHER
PLAIN OR PIERCED TAIL-PLATE.

Birdlip (Gloucester Mus.)	Gloucestershire.
London (Guildhall Mus.)	Middlesex.

ROMAN PROVINCIAL TYPE, WITH HARP-SHAPED PROFILE,
T-SHAPED TOP, OR SPRING-CASE, AND PIERCED TAIL-PLATE.

Poldeen Hill (Brit. Mus.)	Somersetshire.
Stamford Hill, Plymouth	Devonshire.
Cricklade (Brit. Mus.)	Wiltshire.

ROMAN PROVINCIAL TYPE, WITH HARP-SHAPED PROFILE,
EXPANDED TRUMPET-SHAPED TOP, AND FLORIATED
KNOB IN MIDDLE OF BOW.

Backworth (Brit. Mus.)	Northumberland.
Chorley (Brit. Mus.)	Lancashire.
Great Chesters (Newcastle Mus.)	Northumberland.
River Tyne (Newcastle Mus.)	Northumberland.
Risingham (Newcastle Mus.)	Northumberland.
Ribchester	Lancashire.
Farley Heath	Surrey.

KELTO-ROMAN DISC-SHAPED TYPE, WITH
REPOUSSÉ ORNAMENT.

Brough (Brit. Mus.)	Westmoreland.
Victoria Cave, Settle	Yorkshire.
Silchester (Strathfieldsaye House)	Hampshire.

KELTO-ROMAN S-SHAPED OR ZOÖMORPHIC TYPE,
WITH ENAMELLED ORNAMENT. ✓

Kirkby Thore	Westmoreland.
Dowkerbottom Cave, Settle	Yorkshire.
Malton	Yorkshire.
Thirst House Cave, Deepdale	Derbyshire.
Kilnsea	Yorkshire.
Cirencester	Gloucestershire.
Locality unknown (Brit. Mus.)	

Metal pins do not seem to have been much used as dress-fasteners during the Late-Celtic period, judging from the number to be seen in our public museums. One of the most beautiful pins of this period now in existence is the one found with the burial previously mentioned at Danes' Graves,¹ near Driffild, Yorkshire, and now in the York Museum. The pin is of bronze, with a peculiar crook near the top and a circular head

¹ *Proc. Soc. Ant. Lond.* ser. 2, vol. xvii., p. 120.

(resembling a chariot-wheel with four spokes) inlaid with shell, or, according to another account, enamelled. Two bronze pins, with plain turned heads, were amongst the objects derived from the Thirst House Cave,¹ Deepdale, Derbyshire.

Several pins of the class known as "hammer-headed" have been discovered from time to time, chiefly in Ireland and Scotland. These pins are of considerable size, some being ten inches long, and have semi-circular heads with the convex side facing downwards. The top of the pin is bent at right angles, and the head fixed on in front of it. At the top of the head are usually from three to five projecting studs, and the face of the head is enamelled with Late-Celtic designs. From the associations in which such pins have been found and the style of their decoration, they would seem to belong to the transition period between Paganism and Christianity. There is one in the British Museum from Moresby, Cumberland, which was associated with a small bronze ornament of Late-Celtic character; another in the same collection from Craigyarwarren,² Co. Antrim, has spiral patterns upon it; whilst a third in the Edinburgh Museum, from Norrie's Law,³ Forfarshire, was associated with coins of the seventh century, and silver leaf-shape pendants engraved with the same mysterious symbols which occur so frequently on the early Christian sculptured stones of Scotland. A hammer-headed pin of silver from Gaulcross,⁴ Banffshire, has spiral designs upon the head, but of a kind more nearly resembling

¹ *The Reliquary* for 1897, p. 96.

² Wood Martin's *Lake Dwellings of Ireland*, p. 110.

³ Dr. J. Anderson's *Scotland in Early Christian Times*, 2nd ser., p. 36.

⁴ Dr. J. Stuart's *Sculptured Stones of Scotland*, vol. ii., pl. 9.



**BRONZE HOOK-AND-DISK ORNAMENT FROM IRELAND;
NOW IN THE DUBLIN MUSEUM**



**BRONZE PIN, ENAMELLED,
FROM DANES GRAVES, NEAR
DRIFFIELD, YORKSHIRE;
NOW IN THE YORK MUSEUM**



**BRONZE DISC FIBULA WITH LATE-CELTIC
ORNAMENT, FROM SILCHESTER; NOW AT
STRATHFIELDSAYE HOUSE**

S. Victor White, of Reading, photo.

that found on the Christian crosses of about the ninth century in Argyllshire than the Late-Celtic flamboyant designs of Pagan times. Other examples of pins of this kind have been found at Lagore,² Co. Meath, Urquhart,³ Elginshire, on the Culbin Sands, Nairnshire, and in the island of Pabbay, Hebrides.

Unquestionably the finest Late-Celtic personal ornaments are the collars for wearing round the neck, of which, at least, two in gold and about ten in bronze are known to exist. Being larger than any other class of personal ornament, they naturally afford greater scope for the display of the elaborate forms of flamboyant designs in which the art metalworker of the period used to revel. One of the gold collars just referred to came from Broughter, on the western shore of Lough Foyle, near Limavady, Co. Londonderry. It was in the British Museum, but has recently been removed to Dublin. The collar, which formed part of one of the most valuable finds of gold ornaments yet made in Great Britain, is unique both as regards its form and the extraordinary artistic skill displayed in its decoration. The hoard was accidentally brought to light in 1896 whilst ploughing a field on the farm occupied by Mr. J. L. Gibson. We give a list of the various objects comprising the find below.

List of Objects in the Limavady Find of Gold Ornaments.

(1) Model of a boat, $7\frac{1}{4}$ inches long by 3 inches wide, weighing 3 ozs. 5 dwts., with benches and rowlocks for eighteen oarsmen (nine on each side) and rowlock for steering-paddle in the stern.

(2) Boat-fittings in miniature, consisting of fifteen oars,

¹ Wood Martin's *Lake Dwellings of Ireland*.

² *Proc. Soc. Ant. Scot.*, vol. xxxv., p. 279.

one grappling-iron, three forked implements, one yard-arm, and one small spar.

(3) Bowl, $3\frac{1}{2}$ inches in diameter by 2 inches deep, weighing 1 oz. 5 dwts. 12 grs., provided with four small rings for suspension.

(4) Two twisted necklets (one broken), the perfect one 5 inches in diameter, weighing 3 ozs. 7 dwts. 9 grs.

(5) Two chains of plaited wire, one 1 foot $2\frac{1}{2}$ inches long, weighing 2 ozs. 7 dwts., and the other 1 foot $4\frac{1}{2}$ inches long, weighing 6 dwts. 12 grs.

(6) Late-Celtic collar, $7\frac{1}{2}$ inches in diameter, made of a tubular ring $1\frac{1}{8}$ inch in diameter.

The collar must have had a joint of some kind, which is now missing; and the fastening is a most peculiar one, consisting of a T-shaped projection on the end, one-half of the tubular ring fitting into a slot in the end of the other half of the ring. The locking is effected by giving the slotted end a half turn after the T-shaped projection has been inserted. The whole of the exterior surface of the tube is decorated with long sweeping curves, narrow in the middle and with trumpet-shaped expansions at each end, combined with helixes resembling a snail-shell. The background is shaded with a sort of engine-turned pattern of fine lines drawn with a pair of compasses. This remarkable gold collar has been fully described and illustrated by Dr. Arthur Evans in the *Archæologia* (vol. lv., p. 397), and the facts relating to its discovery are related in detail by Mr. R. Cochrane, F.S.A., in a paper in the *Journal of the Royal Society of Antiquaries of Ireland* (vol. xxxiii., p. 211). An account of the evidence given by Mr. C. H. Read, F.S.A., before the committee appointed to inquire into the respective rights of the British Museum and the Museum of the Royal Irish Academy at Dublin to



BRONZE BEADED TORQUE, FROM MOWROAD, NEAR ROCHDALE,
LANCASHIRE
SCALE $\frac{1}{4}$ LINEAR



BRONZE COLLAR FROM WRAXHALL, SOMERSETSHIRE;
NOW IN THE BRISTOL MUSEUM

the possession of the hoard of gold ornaments will be found in the report of the inquiry in the Blue Book issued in 1899.

A second collar of gold now in the Museum of the Royal Irish Academy in Dublin, said to have come from Clonmacnois, King's Co., is illustrated in Sir W. Wilde's *Catalogue of Antiquities of Gold in Museum R.I.A.*, p. 47. It consists of a plain hollow ring $5\frac{1}{2}$ inches in diameter with an ornamental bulb on each side, one of which seems to be made in imitation of one of the glass beads of the period.

The Bristol Museum possesses a perfect flat-jointed bronze collar, of a different kind from any of those just described, from Wraxhall,¹ Somerset, and a portion of another from Llandyssyl,² Cardiganshire. In the British Museum there are two similar collars, one from Trenoweth,³ Cornwall, and the other from the Isle of Portland,⁴ Dorsetshire. The Edinburgh Museum has also an exceedingly good example from Stitchell,⁵ Roxburghshire. All these collars are elaborately ornamented in the Late-Celtic style. The date of the collar from the Isle of Portland is approximately fixed by its having been associated with a dish of Samian ware.

The existence of other Late-Celtic collars has been recorded at Mowroad,⁶ near Rochdale, Lancashire; Embsay,⁷ near Skipton, Yorkshire; Perdeswell,⁸ Worcestershire; Lochar Moss,⁹ Dumfriesshire; and

¹ *Archæologia Cambrensis*, ser. 6, vol. i., p. 83.

² *Ibid.*

³ *Archæologia*, vol. xvi., p. 127.

⁴ *Ibid.*, vol. liv., p. 496.

⁵ Dr. J. Anderson's *Scotland in Pagan Times*.

⁶ H. Fishwick's *History of the Parish of Rochdale*, p. 5.

⁷ *Archæologia*, vol. xxxi., p. 517.

⁸ *Ibid.*, vol. xxx., p. 554.

⁹ D. Wilson's *Prehistoric Annals of Scotland*, vol. ii., p. 141, and *Archæologia*, vol. xxxiii., p. 347.

Hyndford Crannog,¹ near Lanark. These five belong to a special class of what are not inaptly called "beaded torques," because rather more than one-half the collar is composed of bronze beads of two different shapes, (one convex and the other concave) strung



Bronze Beaded Torque from Lochar Moss, Dumfriesshire
Now in the British Museum

alternately on an iron rod of square cross-section, so as to prevent the beads from revolving. The remaining and smaller segment of the circle consists of a bronze tube of rectangular cross-section, ornamented on the exterior with a Late-Celtic flamboyant design.

¹ *Proc. Soc. Art. Scot.*, vol. xxxiii., p. 385.



**BRONZE ARMLET FROM THE CULBIN SANDS;
NOW AT ALTYRE, NEAR FORRES, N.B.**



**BRONZE ARMLET FROM THE CULBIN SANDS;
NOW AT ALTYRE, NEAR FORRES, N.B.**

The Perdeswell collar is incomplete, and the part which remains is formed of twenty beads resembling vertebrae strung on to an iron wire or bar, as in the case of the Lochar Moss collar.

The last class of personal ornaments of the Late-Celtic period to be noticed are the armlets. The most remarkable of these are of the Scottish type, as it may fairly be called, only one specimen having been found outside Scotland.¹ The armlets of this type are very heavy and massive, and their general form appears to have been suggested by a coiled serpent; as in the one from the Culbin Sands, Nairnshire, the ends of the coil terminate in actual serpents' heads. The armlets are usually found in pairs, and are highly ornamented with flamboyant work, and in some cases enamelled. Although they are of cast-bronze, the style of the decoration is evidently copied from the repoussé designs of the wrought metalwork of the period. Dr. J. Anderson has devoted a considerable portion of his Rhind Lectures on *Scotland in Pagan Times: Iron Age*, to the examination of the Scottish group of armlets, most of which are in the Edinburgh Museum. The following is a list of the known examples:—

List of Localities where Armlets of the Scottish Type have been found.

Culbin Sands, Nairnshire.	Bunrannoch, Perthshire.
Auchenbadie, Banffshire.	Seafeld Tower, Fifeshire.
Castle Newe, Aberdeenshire.	Stanhope, Peeblesshire.
Belhelvie, Aberdeenshire.	Plunton Castle, Kirkcud- brightshire.
Aboyne, Aberdeenshire.	Locality unknown.
Pitalpin, Forfarshire.	Newry, Co. Down.
Grange of Conan, Forfarshire.	
Pitkelloney, Perthshire.	

¹ At Newry, Co. Down.

The armlet from Stanhope, Peeblesshire, was associated with a Romano-British saucepan, which suggests that this type belongs to the later part of the Celtic Pagan Iron Age.

Bronze armlets of La Tène, or continental type, have been derived from the burial mounds at Cowlam and Arras, Yorkshire. The bronze armlet from the Stamford Hill Cemetery, near Plymouth, is jointed like the collars, and decorated with flamboyant work.

A pair of penannular ring armlets of silver terminating in serpents' heads, which may possibly be Late-Celtic, was disposed of at the sale of the Bateman Collection from Lomberdale House, Derbyshire. They were found at Castlethorpe,¹ Buckinghamshire, in 1827, in a small urn containing Roman silver and brass coins, none later than the reign of Verus (A.D. 161-169), and a massive silver ring set with a carnelian engraved with a figure of Bonus Eventus. A similar pair of base silver armlets were found near the Carlswark Cavern,² in Middleton Dale, Derbyshire.

Three very elegant armlets of twisted and looped bronze wire were associated with a Late-Celtic burial outside Thirst House Cave,³ Deepdale, Derbyshire. Armlets of the same make are illustrated in Lidenschmit's *Alterthümer*, (vol. ii., pt. 5, pl. 3).

The Late-Celtic toilet accessories are of three kinds, namely, hand-mirrors, hair-combs, and châtelaines. The mirrors are of bronze and circular in shape, with an ornamental handle. The back, or unpolished face of the mirror, is in nearly all cases decorated with incised circles of different sizes, combined with curved

¹ *The Reliquary*, vol. xiii., pl. 18; and *Jour.*; and *Brit. Archæol. Assoc.*, vol. ii., p. 353.

² *The Reliquary*, vol. 1867, p. 113.

³ *Ibid.*, 1897, p. 101.



LATE-CELTIC BRONZE MIRROR, IN THE MAYER MUSEUM,
LIVERPOOL; LOCALITY UNKNOWN

lines and a peculiar sort of background filled in with cross hatching. A list of mirrors such as those described is given below.

List of Localities where Late-Celtic Mirrors have been found.

Warden (Bedford Mus.)	Bedfordshire.
Stamford Hill, near Plymouth (Plymouth Mus.)	Devonshire.
Birdlip (Gloucester Mus.)	Gloucestershire.
Trelan Bahow (British Mus.)	Cornwall.
Balmaclellan (Edinburgh Mus.)	Kirkcudbrightshire.
Locality unknown (Liverpool Mus.)	

Unornamented mirrors have been found with burials at Arras,¹ Yorkshire, and Gilton,² Kent.

The hair-combs are of bone, and will therefore be described subsequently when dealing with bonework.

The châtelines of the Late-Celtic period are pretty little objects of bronze, generally enamelled. At the top is a loop for suspension ; there is a little rod below, from which are hung tweezers, picks, files, etc. Specimens have been discovered in the Thirst House Cave,³ Deepdale, Derbyshire, and at Canterbury,⁴ and Craven Arms,⁵ Shropshire.

The domestic utensils and cooking appliances of the Late-Celtic period include wooden tankards and buckets with bronze mountings, bronze bowls and saucepans, and iron fire-dogs. Some of the riveted caldrons possibly also belong to this period, but as they cannot be distinguished from those of the Bronze Age it will be unnecessary to describe them here.

¹ W. Greenwell's *British Barrows*, p. 454.
² B. Faussett's *Inventorium Sepulchrale*, p. 30.
³ *The Reliquary* for 1897, p. 95.
⁴ *Proc. Soc. Ant. Lond.*, ser. 2, vol. vi., p. 376.
⁵ *Archæologia Cambrensis*, ser. 5, vol. vi., p. 90.

There is a very perfect wooden tankard mounted with bronze in the Mayer Museum, Liverpool, from Trawsfynydd,¹ Merionethshire, having a handle ornamented in the Late-Celtic style with flamboyant tracery, which might easily be mistaken for Gothic work of the fourteenth century were it not for the trumpet-shaped expansions which occur in the details. Handles of similar tankards have been found at Aylesford,² Kent; Elveden,³ Essex; Okstrow,⁴ Orkney; and Carlingwark Loch,⁵ Kirkcudbrightshire.

Late-Celtic wooden buckets with bronze mountings are of the greatest rarity, so much so that only two are known to exist, one from Aylesford,⁶ Kent, in the British Museum, and the other from Marlborough,⁷ Wilts, in the Devizes Museum. They are both decorated with repoussé designs representing men, animals, etc., treated much in the same way as on the Ancient British and Gaulish coins of the same period.

Bronze bowls have been frequently found on Late-Celtic inhabited sites and with Late-Celtic burials. A quite plain but extremely well-made bronze bowl is to be seen in the British Museum side by side with the beaded torque from Lochar Moss,⁸ Dumfriesshire, which accompanied it. There is another plain bowl in the Gloucester Museum which was associated with the burial at Birdlip,⁹ Gloucestershire, already described. A bronze bowl ornamented with projecting bosses is

¹ *Archæologia Cambrensis*, ser. 5, vol. xiii., p. 212.

² *Archæologia*, vol. lii., p. 44.

³ *Ibid.*, vol. lii., p. 45.

⁴ J. Anderson's *Scotland in Pagan Times: Iron Age*, p. 242.

⁵ *Proc. Soc. Ant. Scot.*, vol. vii., p. 7.

⁶ *The Reliquary* for 1897, p. 35.

⁷ Sir R. Colt Hoare's *Ancient Wilts.*

⁸ D. Wilson's *Prehistoric Annals of Scotland*, vol. i., p. 465, pl. 9.

⁹ *Trans. of Bristol and Gloucestershire Archæol. Soc.*, vol. v., p. 137.

amongst the objects derived from the Glastonbury¹ Marsh Village; and a bowl in the Dublin Museum from Keshkerrigan,² Co. Leitrim, has a very characteristic Late-Celtic handle in the form of a beast made up of flamboyant curves. A special type of bronze bowls with zoömorphie handles and enamelled decorations will be dealt with subsequently.

Most of the saucepans in use during the Late-Celtic period were either imported from Italy and Gaul or were so nearly copied by local metalworkers as to be indistinguishable from the originals. None of these saucepans, as far as I am aware, have Celtic decoration upon them, although several are inscribed with Celtic names, and others are highly enamelled. Two specimens in the British Museum are of exceptional interest, one of bronze enamelled and inscribed with the name "BODVOGENVS," from Prickwillow,³ near Ely, Cambridgeshire, and the other of silver, with a highly ornamented inscribed handle, which was found at Backworth,⁴ Northumberland, with the pair of Kelto-Roman fibulæ previously mentioned. The more elaborate saucepans were probably used in connection with religious ceremonies and not for cooking, as is borne out by the dedicatory inscriptions upon the handles and the circumstances under which many of them have been found. A list has already been given of the saucepans associated with finds of Late-Celtic objects.

The metalworkers of the Late-Celtic period were not only capable of executing some of the finest pieces of repoussé bronze that the world has ever seen, but they

¹ *Proc. of Somersetshire Archæol. Soc.*, vol. xl., p. 149.

² *Reliquary* for 1900, p. 247.

³ *Archæologia*, vol. xxviii., p. 436.

⁴ *Archæol. Jour.*, vol. viii., p. 39.

also excelled in producing works of art in wrought-iron of great merit. As an example of their skill in this direction we have the remarkable pair of fire-dogs from Capel Garmon, Denbighshire,¹ now in the possession of Colonel Wynne Finch of Pentre Voelas, near Bettws-y-coed. The fire-dogs consist of two upright bars, each surmounted by the head of a beast with horns, and standing on an arched foot, connected near the bottom by a horizontal bar on which to rest the logs of wood used for the fire. The uprights are ornamented on each side with thinner pieces of iron bent into undulations and scrolls, and fixed to the uprights at intervals with rivets having large round heads.

Each of the beasts' heads has a very curious sort of crest ornamented with a row of circular holes and round knobs. Other fire-dogs of the same kind, made of plain iron bars, and with horned beasts' heads on the top of the uprights (each horn terminating in a round knob), have been found at Mount Bures,² Essex, Hay Hill,³ near Cambridge, and Stamfordbury,⁴ Bedfordshire, associated with Romano-British burials.

The only objects of the Late-Celtic period which may conjecturally have been used for religious purposes are the little bronze figures of animals from Hounslow,⁵ Middlesex, now in the British Museum.

Under the head of musical instruments come the bone flutes from Thor's Cave, Staffordshire, and the magnificent bronze trumpet found in 1794 at Loughnashade, Co. Armagh, and now in the Museum of the Royal Irish Academy at Dublin. Most of the trumpets

¹ *Archæologia Cambrensis*, ser. 6, vol. i., p. 40.

² C. Roach Smith's *Collectanea Antiqua*, vol. ii., p. 25.

³ *Archæologia*, vol. xix., p. 57.

⁴ *Publications of Cambridge Ant. Soc.* for 1845


⁵ *Proc. Soc. Ant. Lond.*, ser. 2, vol. iii., p. 90.

of this kind are of the Bronze Age, but the style of the decoration on the annular disc at the mouth of the one from Loughnashade shows clearly that it is of the Iron Age.¹

Amongst the objects of unknown use of the Late-



Late Celtic Bronze Spoon from
Brickhill Lane, London



Late Celtic Bronze Spoon from
Crosby Ravensworth, Westmoreland

Celtic period are certain so-called spoons, some peculiar disc-and-hook ornaments, and a few highly ornamented circular pieces of repoussé bronze with a cup-shaped depression nearly in the centre.


The spoon-like objects have been very fully dealt

¹ Sir W. Wilde's *Catal.*, pp. 627 and 631.

with in a paper by Mr. Albert Way in the *Archæological Journal* (vol. xxvi., p. 52), and below is given a list of all the known specimens.

List of Localities where Spoon-like Objects with Late-Celtic Decoration have been found.

Crosby Ravensworth (British Mus.) . Westmoreland.
 London, Brickhill Lane (British Mus.) . Middlesex.



Late Celtic Spoon. One of a pair from Weston, near Bath.
 Now in the Edinburgh Museum. Scale † linear

London, Thames (British Mus.) . . .	Middlesex.
Weston, near Bath (Edinburgh Mus.) . . .	Somersetshire.
Llanfair (Edinburgh Mus.)	Denbighshire.
Penbryn (Ashmolean Mus.)	Cardiganshire.
Locality unknown (Liverpool Mus.) . . .	Ireland.
Locality unknown (Dublin Mus.)	Ireland.
Walmer	Kent.

The body of these objects is shaped like a very shallow spoon with a pointed end, and the handle (if such it may be called) is circular or nearly circular, in many cases with two little round ears or projections at each side. The so-called spoons are generally found in pairs, one spoon having a cruciform design in the middle of the bowl; whilst its fellow has a small hole bored through the edge of the bowl. The handles of the spoons are always ornamented, sometimes on the front only, but more commonly on the back as well.

There are specimens of the other Late-Celtic objects of unknown use—namely, the hook-and-disc ornaments¹ and the circular pieces of repoussé metalwork with a cup-shaped depression—in the British Museum² and the Dublin Museum.³

No satisfactory explanation has been given of the use of certain wheel and triskele pendants of which examples have been found in Berkshire, Kingsholm, near Gloucester, Hunsbury, N. Hants, Seamill Fort, Ayrshire, and Treceiri, Carnarvonshire.

POTTERY AND GLASS

The pottery of the Late-Celtic period differs from that of the Bronze Age in being turned on a wheel instead of being hand-made. The firing is also better

¹ *The Reliquary* for 1901, p. 56.
² *Proc. Soc. Ant. Scot.*, vol. xix., p. 254.
³ Sir W. Wyld's *Catal. Mus. R.I.A.*, p. 637.

done, and the quality of the ware superior in every way. Since the discovery of the Aylesford cemetery in Kent, in 1886, it has been possible to differentiate Late-Celtic pottery from Romano-British by the peculiar forms of the vases. Dr. Arthur Evans has dealt with this subject pretty exhaustively in his paper in the *Archæologia* (vol. lii., p. 315).

The most characteristic of the Aylesford urns is tall, with a narrow base and wide mouth. The base is in the shape of a low truncated cone, the top of which is the narrowest part of the vase, and from this point it gradually gets wider until the top rim is nearly reached, when it contracts again slightly. The curve thus produced is of such extreme elegance as to at once suggest a classical origin. The exterior surface of some of these pots is plain, but in many cases it is divided into bands by horizontal projecting bead mouldings. Dr. A. Evans does not find much difficulty in showing that the peculiarities of form can be directly traced to the metal *situlae* from which the vases were copied. With regard to this, he says:—

“In most cases these (*i.e.* the Aylesford) vases, which for elegance of form may almost vie with the ceramic products of Italy or Greece, are divided into zones by the small raised ridges or cordons described above, the zones themselves being, in turn, decorated with finely incised linear striations. This type of vase, beautiful as it is in itself, is still more interesting from the comparisons to which it inevitably leads us. No one familiar with the ceramic forms of an important group of North-Italian cemeteries, belonging, for the most part, to the fourth or fifth centuries before our era, and of which the whole series of objects so admirably excavated and arranged by Professor Prosdocimi at Este¹ forms the most splendid illustration, can fail to be struck with the

¹ *Notizie degli Scavi*, etc., 1882, pp. 5-37.



LATE-CELTIC POTTERY FROM HUNSBURY;
NOW IN THE NORTHAMPTON MUSEUM



LATE-CELTIC POTTERY FROM HUNSBURY;
NOW IN THE NORTHAMPTON MUSEUM

manifold points of resemblance presented by the urns before us with the most characteristic of the vase-types there represented. The contour of the type referred to, with its shoulders sometimes angular, sometimes abruptly rounded off, its inverted conical body divided into vertical zones by raised cordons, and tapering off to a pedestal below, can only be described as identical with that of some of the finest of the Aylesford specimens. The only perceptible difference is that, whereas the British urns are almost uniformly covered with a black or brown coating—the colouring



Late Celtic urns from Shoebury, Essex
Now in the Colchester Museum

matter may have been supplied by pounded charcoal—zones of the Euganean cineraries are coloured alternately with bands of graphite and red ochre. Some of the earlier of the Este vases are, however, of plain dark brown *bucchero*, and others, again, of later date, of an uniform red or grey. These North-Italian parallels have a still further value, inasmuch as they throw the clearest possible light on the actual genesis of this type. The cordoned vases of Este are, in fact, nothing more than copies in clay of certain forms of bronze *situlae*; the commonest form of these, which is distributed through the whole of the geographical area where these vases are discovered, is zoned in the same

way as the pots, the zones answering to an universal method of early metal industry, in accordance with which vessels were built up of bands of thin metal riveted together at the edges, each zone being often, in turn, defined by cordons or beads of metal. These cordons themselves in their more prominent form represent the wooden rings that surrounded and kept together the framework of wooden staves, to which in early times the metal plates themselves were riveted."

Besides the pedestalled vases from Aylesford,¹ made in imitation of the cordoned *situlae* of bronze from the North-Italian region, there are others, perhaps derived from them, with elegantly formed bases. There are also vases without pedestals, and having somewhat globular bodies as well as bowl-shaped and saucer-shaped pots. Most of these are now in the British Museum.

The following list gives the finds of pottery of a similar kind:—

List of Localities where Finds of Late-Celtic Pottery of the Aylesford Type have been made.

Kit's Coty House (Maidstone Mus.)	Kent.
Allington (Maidstone Mus.)	Kent.
Northfleet	Kent.
Elveden	Essex.
Shoebury	Essex.
Braintree	Essex.
Locality unknown (Cambridge Mus.)	
Hitchin	Herts.
Aston Clinton (Aylesbury Mus.)	Bucks.
Abingdon (Ashmolean Mus.)	Berks.
Whitechurch (Dorchester Mus.)	Dorset.
Weymouth (British Mus.)	Dorset.

Another class of pottery is recognised to belong to the Late-Celtic period, not so much by the forms of

¹ A fine example of this type from Sandy, Beds, is illustrated in T. Fisher's *Bedfordshire*.



LATE-CELTIC POTTERY FROM YARNTON, OXFORDSHIRE;
NOW IN THE BRITISH MUSEUM
SCALE $\frac{1}{2}$ LINEAR



LATE-CELTIC POTTERY FROM KENT'S CAVERN, NEAR TORQUAY,
DEVONSHIRE; NOW IN THE BRITISH MUSEUM
SCALE $\frac{1}{2}$ LINEAR

the vases (because most of them are in a very fragmentary condition) as by the patterns upon them, which consist of incised curved lines, circles, dots, and different kinds of cross-hatching and shading. A list of the finds is given below.

List of Localities where Finds of Late-Celtic Pottery, ornamented with Incised Lines, Circles, Dots, and Shading, have been made.

Hunsbury (Northampton Mus.)	.	Northamptonshire.
Mount Caburn (Pitt-Rivers Coll.)	.	Sussex.
(British Mus.)		
Brighton (Brighton Mus.)	.	Sussex.
Highfield Pits, near Salisbury (Blackmore Mus., Salisbury)	.	Wiltshire.
Kent's Cavern, Torquay (British Mus.)	.	Devonshire.
Glastonbury Marsh Village (Glastonbury Mus.)	.	Somersetshire.
Kingsholm (Ashmolean Mus.)	.	Gloucestershire.
Yarnton (British Mus.)	.	Oxfordshire.

Those who wish to compare the Late-Celtic pottery of Britain with Gaulish pottery of the same character may, with advantage, consult the *Dictionnaire Archéologique de la Gaule*, and Paul du Chatellier's *La Poterie aux époques préhistoriques et gauloise en Armorique*.

As far as the available evidence goes, glass does not seem to have been used for any other purpose by the Late-Celtic people except the manufacture of personal ornaments, the most important of which were beads for necklaces. Some of the beads from Ireland and Scotland, specimens of which may be seen in the museums at Dublin and Edinburgh, are most artistically fashioned from twisted rods of glass of variegated colour bent into peculiar shapes. They have been obtained from the Irish crannogs at Lagore, Co. Meath, and Lough Ravel.

A bracelet of green glass, with a cable-like ornament in white and blue strands surrounding its outer surface, was found a few years ago in the crannog at Hyndford, Co. Lanark.

WOODWORK, BONEWORK, AND THE KIMMERIDGE
SHALE INDUSTRY

Owing to the perishable nature of the material very few examples of carved woodwork of the Late-Celtic period are now in existence. Those which we do possess have been derived from the Glastonbury Marsh Village and from the crannog at Lochlee, Ayrshire. Mr. Arthur Bulleid, F.S.A., has illustrated three specimens in an article on "Some Decorated Woodwork from the Glastonbury Lake Village" in the *Antiquary* for April, 1895, p. 109. No. 1 was dug up from the peat at a depth of 6 feet 6 inches below the surface, near the south-east edge of the village. It is a rectangular piece of wood dressed smooth all over, 1 foot 7 inches long by $3\frac{3}{4}$ inches wide by $\frac{1}{2}$ inch thick, decorated on one side with a step-pattern shaded after the fashion of chequerwork, with a cross-hatching of diagonal lines. No. 2 is the stave of a small bucket, which, when complete, must have been 7 inches high by $5\frac{1}{2}$ inches in diameter, decorated with a lozenge pattern shaded with parallel straight lines. No. 3 is a portion of a tub 6 inches high by 1 foot in diameter, cut out of a solid piece of ash, and having its exterior surface decorated with flowing lines of extreme beauty, resembling scrolls of foliage converted into geometrical ornament by successive copying. Where the flowing lines diverge, the trumpet-shaped expansions are shaded with diagonal cross-hatching and dots. There is a good model of this tub in the British Museum. The designs on the woodwork from Glastonbury are

produced by incising the surface with some fine sharp-pointed tool, and afterwards burnt in by passing a heated piece of metal along the incisions.

The specimen from the Lochlee crannog, which is illustrated in Dr. R. Munro's *Ancient Scottish Lake Dwellings* (p. 134), is a piece of ash 5 inches square, ornamented on one side with a triple spiral, and on the other with Late-Celtic flamboyant work.

A wooden bowl with a carved handle, found in a bog near Rathconrath, Co. Westmeath, and now in the Museum of the Royal Irish Academy in Dublin, may possibly belong to the same category.

Amongst the objects of bone belonging to the Late-Celtic period the most remarkable are the spatulæ, or flakes, of which no less than 5,000 are said to have been derived from cairn H of the Slieve-na-Caillighe series, near Oldcastle, Co. Meath. These chambered cairns were in the first instance erected as burial-places at the end of the Neolithic Age or the beginning of the Bronze Age, and the one marked H on the plan given in the *Proc. Soc. Ant. Scot.* (vol. xxvi., p. 294) appears to have been used as a workshop by an artificer in bone during the Early Iron Age. Ninety-one of the bone spatulæ from the cairn in question were engraved by compass, with circles, curves, and ornamental puncturings, and twelve were decorated on both sides. Unfortunately the whole of the bones have been lost, and we only know what they were like from the illustrations in E. Conwell's *Tomb of Ollamh Fodhla* (p. 53). A fragment of one of these bones which had been overlooked by the previous explorers of the cairn has recently been brought to light by Mr. E. Crofton Rotheram.¹ Perhaps the most interesting feature connected with the bones from Slieve-na-Caillighe is the discovery with them of

¹ *Journ. R. Soc. Ant. Ireland*, ser. 5, vol. vi., p. 257.

the pair of iron compasses used in producing the incised designs upon them.

Besides the bones just described, the other principal objects of the same material belonging to the Late-Celtic period are certain toilet-combs and spoon-shaped fibulæ, or dress-fasteners. Bone combs with Late-Celtic ornament have been found on the inhabited site at Ghegan Rock, near Seacliff, Haddingtonshire, and in the crannogs at Lagore,¹ Co. Meath, Ballinderry,² Co. Westmeath; and at Longbank crannog on the Clyde, near Glasgow. Spoon-shaped fibulæ of bone have been derived from the Victoria Cave, Settle, the Kelko Cave, Giggleswick, and Dowkerbottom Cave, Arncliffe, Yorkshire. The ornament upon them consists of concentric circles and dots.³

In addition to wood and bone, the Late-Celtic people used Kimmeridge shale for the manufacture of objects, chiefly turned vases with cordons, like the Aylesford pots previously described. Vessels of this kind have been found at Old Warden,⁴ Bedfordshire, Great Chesterford⁵ and Colchester,⁶ Essex, and Corfe Castle,⁷ Dorset.

STONWORK

Only three sculptured monuments decorated with Late-Celtic patterns are known to exist at present.⁸ They are all in Ireland and are fully described by Mr. G. Coffey in the *Proceedings of the Royal Irish Academy* (vol. xxiv., sect. c, p. 257).

¹ Sir W. Wilde's *Catal. Mus. R.I.A.*, p. 271, fig. 176.

² *Ibid.*, p. 271, fig. 177.

³ Prof. W. Boyd Dawkins' *Cave Hunting*, pp. 91 and 131.

⁴ "On the Materials of Two Sepulchral Vessels found at Warden, Co. Beds, by the Rev. J. S. Henslow (*Cambridge Ant. Soc. Publ.*, 1846).

⁵ *Archæol. Jour.*, vol. xiv., p. 85.

⁶ Henslow, *loc. cit.*, p. 87.

⁷ *Archæol. Jour.*, vol. xxv., p. 301.

⁸ At Mullaghmast, Co. Kildare; Castle Strange, Co. Roscommon; and Turoe, Co. Galway.



**GRANITE MONOLITH, WITH LATE-CELTIC
SCULPTURE, AT TUROE, CO. GALWAY.**

HEIGHT OF STONE, 4 FT.

*Reproduced from a photograph by Mr. A. McGoogan
illustrating Mr. George Coffey's paper in the
"Proceedings of the Royal Irish Academy"*

CHAPTER V

PAGAN CELTIC ART IN THE EARLY IRON AGE

TECHNICAL PROCESSES EMPLOYED DURING THE EARLY IRON AGE IN BRITAIN

THE fact must never be lost sight of that the picture presented to our mind of any particular prehistoric stage of culture must necessarily be extremely imperfect, since the extent of our knowledge is limited entirely by the number of relics which specially favourable circumstances have preserved from destruction. Of the textile fabrics of the Late-Celtic period, for instance, hardly anything is known, although we are certain that spinning and weaving must have been extensively practised from the quantities of long-handled weaving-combs, spindle-whorls, and loom-weights that have been found on almost every inhabited site. A people who showed such a high capacity for decorative design could not have failed to produce good artistic effects by means of pattern-weaving.¹ What such textile patterns may have been can only be guessed at by survivals (like the Scottish tartans) or by ornament of a textile character occurring on objects made of less perishable materials (like the step-pattern on a piece of wood from the Glastonbury Marsh Village).

¹ "The cloth was covered with an infinite number of little squares and lines as if it had been sprinkled with flowers, or was striped with crossing bars which formed a chequered design. Their favourite colour was red or a pretty crimson." C. Elton's *Origins of English History*, p. 114, quoting Pliny and Diodorus Siculus.

The Celts had already become expert workers in metal before the close of the Bronze Age; they could make beautiful hollow castings for the chapes of their sword-sheaths; they could beat out bronze into thin plates and rivet them together sufficiently well to form water-tight caldrons; they could ornament their circular bronze shields and golden diadems with repoussé patterns, consisting of corrugations and rows of raised bosses; and they were not unacquainted with the art of engraving on metal.

The Celt of the Early Iron Age attained to a still higher proficiency in metallurgy than his predecessor of the Bronze Age. Casting in bronze was applied to a much larger number of objects than before, such as—


- Handles of swords and daggers.
- Chapes of sword and dagger sheaths.
- Bridle-bits.
- Harness-mountings and rings.
- Chariot fittings.
- Collars and armlets.
- Handles of tankards and mirrors.
- Spoon-like objects of unknown use.

Wrought-bronze was used for—


- Sword and dagger sheaths.
- Shields and helmets.
- Mountings of wooden buckets and tankards.
- Caldrons and buckets.
- Circular discs of unknown use.

The ornamental features of the objects of cast-bronze were produced chiefly during the process of moulding, although the surface was in many cases further beautified afterwards by chasing, engraving, and enamelling.

Objects of wrought-bronze were usually decorated by means of repoussé-work, *i.e.* designs in relief



Late-Celtic Bronze Mirror from Trehan Bahow, Cornwall
Now in the British Museum



Upper part of Bronze
Sword-sheath from
Hunsbury
Now in the Northampton
Museum

hammered up from the back. Occasionally enamel was added (as, for example, on the shield from the Thames, now in the British Museum), in the form of small plaques fixed on with rivets. In place of the more or less crude corrugations and rows of raised pellets of the Bronze Age we get the most marvellous curved surfaces and conchoids, executed with an unerring eye and a skill which it would be difficult to surpass. The repoussé-work of the Late-Celtic period is seen in its greatest perfection on the circular discs of unknown use¹ in the Museum of the Royal Irish Academy in Dublin, and the British Museum.

Both cast and wrought objects of bronze were decorated with patterns composed of finely engraved lines shaded in places with a peculiar kind of cross-hatching or with dots. The mirror-backs,² the sword-sheaths,³ and the harness-rings⁴ afford good examples of this class of work.

Brazing and soldering appear to have been unknown to the metalworkers of the Late-Celtic period, as they pieced their metalwork together by means of rivets. The practice of riveting was learnt from the artificers

¹ See p. 121.

² See list on p. 115.

³ See list on p. 91; especially the one from Lisnacrogghera.

⁴ See list on p. 94; especially those from Polden Hill, Somerset.

who constructed the caldrons of the late Bronze Age already referred to, and they, no doubt, in their turn, acquired their knowledge from a foreign source. The bronze helmet from the Thames at Waterloo Bridge, now in the British Museum, illustrates the riveting of the Late-Celtic period at its best. The rivets generally have pointed conical heads, producing a good decorative effect. The way in which the different pieces of metal are held together is often ingeniously disguised by making the rivet-heads form part of the ornament, or by concealing the head behind a circular disc of enamel.

The evidence of both history and archæology tends to show that the art of enamelling on metal was, in the first instance, a British one. The historical evidence is confined to an oft-quoted passage from the *Icones* of Philostratus (a Greek sophist in the court of Julia Domna, wife of the Emperor Severus), which is as follows :—

“They say that the barbarians who live in the ocean pour these colours on heated brass, and that they adhere, become hard as stone, and preserve the designs that are made upon them.”

Philostratus wrote this at the beginning of the third century A.D.; and by “the barbarians who live in the ocean” (τοὺς ἐν Ὠκεανῷ βαρβάρους) he no doubt meant the Britons rather than the Gauls, as some French writers have assumed.¹

The earliest enamels are those which occur on objects decorated in the pure Late-Celtic style without any trace of Roman influence, such as—

Bridle-bits from Rise, near Hull, Yorkshire; and Birrenswark, Dumfriesshire.

¹ A. W. Franks in Kemble's *Horæ Ferales*, p. 186.

Harness-rings and mountings from—

Norton	Suffolk.
Westhall	Suffolk.
Alfriston	Sussex.
Polden Hill	Somersetshire.
London	Middlesex.
Saham Toney	Norfolk.
Uffizi Museum	Florence.
British Museum	Locality unknown.

Armlets from Castle Newe, Aberdeenshire; and Pitkel-loney, Perthshire.

Handles of bowl from Barlaston, Staffordshire.

Next, in order of age, come objects which from their general form or from the associations they were found in are known to belong to the Romano-British period, but yet have Late-Celtic decoration upon them, such as—

Harp-shaped fibulæ from Risingham, Northumberland, River Tyne, in the Newcastle Museum.

S-shaped fibulæ from Norton, Yorkshire, and other places (see list on p. 107).

Seal-box from Lincoln, in the British Museum.

Four-legged stand, with round hole in the top, from Silchester, in the Reading Museum.

Lastly, there are survivals of the use of discs of Late-Celtic enamel in the decoration of bowls of early Saxon, and therefore post-Roman, age, the following examples of which have been found :—

List of Localities where Bowls of the Saxon Period, but with Late-Celtic enamelled decoration, have been found.

Crosthwaite (British Mus.)	Cumberland.
Middleton Moor (Sheffield Mus.)	Derbyshire.
Over-Haddon	Derbyshire.
Benty Grange	Derbyshire.

Chesterton (Warwick Mus.)	Warwickshire.
Caistor (now lost)	Lincolnshire.
Oxford (Pitt-Rivers Collection)	Oxfordshire.
Needham Market (now lost)	Suffolk.
Barrington (Sir John Evans' Collection)	Cambridgeshire.
Lullingstone (Sir W. Hart Dyke's Collection)	Kent.
Greenwich (Mr. J. Brent's Collection)	Kent.
Kingston Down	Kent.

The hammer-headed pins, a list of which has already been given on page 108, are also instances of the use of Celtic enamel in post-Roman times.

Before going further it may be as well to say a few words about the art of enamelling in general, so as to show the position occupied by the Late-Celtic examples.

The term enamel is used to designate a particular kind of mixture or paste which can be applied to the surface of metals or other materials, so that when it has been vitrified by the application of heat, and afterwards cooled, it forms a decoration of great beauty and durability. The base of all enamels is a flux composed of silica (in the shape of silver sand or powdered flint), red lead, and potash. To this flux are added certain metallic oxides to produce different colours, and, if necessary, oxide of tin to render it opaque. The materials are mixed together, fused in a crucible, reduced to a fine powder when cold, made into a paste with water, and then applied to the surface of metal to be decorated. After vitrification in a furnace and polishing, the enamel is complete.

Mr. A. W. Franks¹ divides enamels into the following classes :—

(1) *Inlaid Enamel*, where the outlines are formed by metal divisions.

(2) *Transparent Enamel*, where the outlines and all the markings are produced by variations of depth in the sculptured ground over which the vitreous material is floated.

(3) *Painted Enamel*, where the outlines are made by a difference in the tint of the enamel itself, which completely conceals the metal base beneath.

The divisions between each of the colours in inlaid enamel are produced in two different ways, namely :—

(a) *Champlevé Enamel*, where the field (*champ*) or area to be occupied by each colour is dug out and removed (*levé*), so as to leave a very narrow band of metal at the level of the original surface to form the dividing line between the fields.

(b) *Cloisonné Enamel*, where the divisions or partitions (*cloison*) between the fields consist of thin strips of metal bent into the required shape and fixed to the surface to be enamelled.

All the enamels of the Late-Celtic period belong to the *champlevé* kind. The colours used are bright red, yellow and blue, and the designs are more often curvilinear than not, like those on the repoussé metalwork. The patterns were probably traced on the surface of the metal to be decorated with a finely pointed instrument, and the hollows to receive the enamel dug out with a scooping tool, in the case of small work, or with a long thin chisel and a chaser's hammer where the work was larger.

The late Sir Wollaston Franks, than whom no better

¹ Afterwards Sir Wollaston Franks; see *Glass and Enamel*, by J. B. Waring and A. W. Franks.



CRUCIFORM HARNESS MOUNTING OF BRONZE
ENAMELLED. LOCALITY UNKNOWN; NOW
IN THE BRITISH MUSEUM

SCALE $\frac{1}{2}$ LINEAR



BRONZE ENAMELLED HARNESS MOUNTING FROM POLDEN HILL,
SOMERSETSHIRE; NOW IN THE BRITISH MUSEUM

SCALE $\frac{1}{2}$ LINEAR

authority can be quoted, always maintained the Celtic origin of the art of enamelling in Western Europe, and gave the distinctive name of *opus Britannicum* to the special kind of enamel which was produced in greater perfection by the Celts inhabiting the British Isles than by any other people. The art of enamelling in the purely Celtic style commenced before the arrival of the Romans in this country, and after continuing throughout the whole period of their occupation, survived for some centuries after their departure from our shores. There are, however, numerous enamels which, though very possibly of Celtic workmanship, are altogether Roman as far as the ornamental patterns upon them are concerned. Dr. Joseph Anderson has described an exquisitely enamelled patera of this kind found in Linlithgowshire, and now in the Museum of Antiquities of Edinburgh. He says of it:—¹

“Apart from the singular beauty of its decoration it is possessed of this special interest, that it is the only vessel of its kind and character known to exist in Scotland. It is, however, one of a class of objects, which, though few in number, are pretty widely distributed over the area, which may be termed the outskirts of the Roman Empire, towards the north and west—that is Britain, North Germany, and Scandinavia. We look in vain for anything like it within the area of the Roman Empire proper, and it may therefore be regarded as a product of a culture of some portion of the area of north-western Europe, where it was touched and modified by the Roman culture.”

Other similar examples of enamelled vessels have been found at Braughing,² near Standon, Herts; the

¹ “Notice of an enamelled cup or patera of bronze found in Linlithgowshire, recently purchased for the Museum,” in the *Proc. Ant. Scot.*, vol. xix., p. 45.

² *Proc. Soc. Ant. Lond.*, 2nd ser., vol. iv., p. 514.

Bartlow Hills,¹ Essex; Maltbeck,² Denmark; and Pymont,³ in the Rhine valley. In addition to these we have two other enamelled vessels, but differing in their style of ornament, one from Rudge,⁴ Wilts, now in the Duke of Northumberland's private museum at Alnwick Castle, and the other from Prickwillow,⁵ Cambridgeshire, now in the British Museum.

Of the art of enamelling as carried on elsewhere than in Britain Dr. Anderson says:—⁶

“The Gauls as well as the Britons—of the same Celtic stock—practised enamel-working before the Roman conquest. The enamel workshops of Bibracte, with their furnaces, crucibles, moulds, polishing-stones, and with the crude enamels in their various stages of preparation, have been recently excavated from the ruins of the city destroyed by Cæsar and his legions. But the Bibracte enamels are the work of mere dabblers in the art compared with the British examples. The home of the art was Britain, and the style of the patterns as well as the associations in which the objects decorated with it were found, demonstrate with certainty that it had reached its highest stage of indigenous development before it came in contact with the Roman culture.”

A full account of the discoveries made at Bibracte will be found in J. G. Bulliot's *Fouilles de Mont Beuvray*. Several beautiful enamels have been derived from the Belgo-Roman cemetery at Presles.

Romano-British enamels, without distinctively Celtic

¹ *Archæologia*, vol. xxvi., p. 300.

² *Mem. de la Soc. Royale des Antiquaires du Nord*, 1866-71, p. 151.

³ *Jahrbücher des Vereins von Alterthumsfreunden in Rheinlande*, heft 38, p. 47.

⁴ *Catal. of Mus. of R. Archæol. Inst. at Edinburgh*, 1856.

⁵ *Archæologia*, vol. xxviii., p. 436.

⁶ *Loc. cit.*, p. 49.

patterns upon them, have been dug up at many places in Great Britain, but more especially at Prickwillow.

We shall see in a subsequent chapter how the divergent spiral patterns on the circular discs of enamel used to decorate the bronze bowls of the end of the Late-Celtic period were transferred bodily to the pages of the early Irish illuminated MSS. of the Gospels.

Another method of ornamenting metalwork besides enamelling was by means of settings of different materials fixed in place by small pins or rivets. As instances we have the bronze shield from the River Witham,¹ now in the British Museum, set with red coral; the bronze fibula from Datchet, Oxon,² set with amber and blue glass; and most curious of all, a bronze object of unknown use from Carlton,³ Northamptonshire, now in the Northampton Museum, inlaid with portions of the stem of a fossil encrinite.

A very effective kind of decorative metalwork may be made out of wire, bent so as to form a series of loops, of which we have British examples in the bracelets from the Early Iron Age burial in Deepdale,⁴ Derbyshire; and a foreign specimen in a fibula from the cemetery of the La Tène period at Jezerine,⁵ in Bosnia-Herzegovina.

More or less akin to the looped wirework just mentioned are certain gold and silver chains made of fine wire. Dr. Arthur Evans has gone pretty fully into this subject in his paper in the *Archæologia* (vol. lv., p. 394), describing the find of gold ornaments at Broughter, near Limavady, Co. Londonderry, amongst

¹ J. Kemble's *Horæ Ferales*, p. 14, and pl. 15.

² *Proc. Soc. Ant. Lond.*, ser. 2, vol. xv., p. 191.

³ *Ibid.*, ser. 2, vol. xvii., p. 166.

⁴ *The Reliquary for 1897*, p. 101.

⁵ R. Munro's *Bosnia-Herzegovina*, p. 170.

which were two chains of the kind referred to. The art of making these chains was no doubt of foreign origin, as they have been found in Etruscan tombs of the fifth century B.C. in Italy; with burials of the La Tène period in the cemetery of Jezerine, in Bosnia; and in a tomb in the Gaulish cemetery of Ornavasso, in the province of Turin. In Britain such chains were used during the period of the Roman occupation for the attachment of fibulæ worn in pairs, as in the case of those from Chorley,¹ Lancashire, and from Newcastle-on-Tyne,² Northumberland. We shall see in a subsequent chapter that the manufacture of these finely wrought chains of silver survived in early Christian times in Ireland, the best-known examples being those attached to the Tara brooch,³ and to an enamelled pin from Clonmacnois.⁴ With regard to the date of the chains, Dr. Arthur Evans says:—⁵

“It thus appears that these fine chains were in use among the Celtic peoples during the first two centuries before and after our era.⁶ In Britain, however, the finest class is, as far as I am aware, confined to the latter half of this period; the chains attached to the earlier British fibulæ, like the one in the British Museum from the Warren,⁷ near Folkestone, which may date from the second century B.C., being, like those referred to from the Champagne⁸ cemeteries, of simpler and coarser construction.”

¹ *The Reliquary* for 1901, p. 198.

² *Ibid.* for 1895, p. 157.

³ M. Stokes' *Early Christian Art in Ireland*, p. 75.

⁴ *Jour. R. Soc. Ant. of Ireland*, ser. 5, vol. i., p. 318.

⁵ *Archæologia*, vol. lv., p. 396.

⁶ Dr. A. Evans appears to have forgotten the Christian survivals in Ireland.

⁷ *The Reliquary* for 1901, p. 197.

⁸ The coarser chains are made of ordinary circular or oval links, sometimes double (see illustrations given in the *Dictionnaire Archéologique de la Gaule* of those from the Marnian cemeteries).

Ornamental ironwork of the Late-Celtic period is extremely rare, either because the smiths were too busily employed in making weapons for the warrior and tools for the artisan to devote their time to decorative work, or because the specimens of their handiwork have disappeared in consequence of the perishable nature of the material of which they were made. Fortunately, however, the fire-dogs from Capel Garmon,¹ now at Colonel Wynne Finch's house at Voelas, are still in existence to show us what fine ornamental ironwork the Welsh smiths of the Romano-British period were capable of producing.

Turning now from the metalwork to the pottery of the Late-Celtic period, we find it to consist of unglazed vessels made on a wheel, fired in a kiln, and ornamented either by mouldings or by patterns engraved on the surface with a pointed instrument. The technical processes employed in its manufacture do not seem to have differed essentially from those of the Romano-British potters, except that slip-ware was unknown. As far as I am aware, no painted pottery like that from Mont Beuvray² (Bibracte), nor vessels incrustated with pebbles and polished with graphite like the one from Plouhinec³ (Finistère) now in M. Paul du Chatellier's collection at the Château de Kernuz, near Quimper, have yet been discovered in this country.

As far as the existing evidence goes no ornamental glasswork was made during the Late-Celtic period in Britain except certain beads and armlets already described. The technical process of manufacturing these beads consisted in twisting together fine rods of different


¹ *Archæologia Cambrensis*, ser. 6, vol. i., p. 39.

² See J. G. Bulliot's *Fouilles de Mont Beuvray*.

³ See *Revue Archéologique* for 1883, p. 11.

coloured glass, and then bending the composite rod into loops round a mandril so as to form the bead.

The art of the ornamental worker in wood in the Late-Celtic period is displayed at its best in the tankards, buckets, and tubs of which, fortunately, a



Late-Celtic Pottery from the Glastonbury Lake Village

few interesting specimens have been preserved. The tankard from Trawsfynydd,¹ Merionethshire, now in the Liverpool Museum, shows great ingenuity of construction, the staves of which it is composed being kept together at the bottom by a corrugated wire let

¹ *Archæologia Cambrensis*, ser. 5, vol. xiii., p. 212.

into the ends of the staves. Another tankard, belonging to Mr. T. Layton,¹ F.S.A., has the staves fastened together with wooden dowels and pins.

We have already described how the engraved patterns were produced on the ornamental woodwork from the Glastonbury Marsh Village by a finely pointed instrument, and afterwards burnt in.

Ornamental objects were also made out of bone and Kimmeridge shale during the Late-Celtic period, but there is nothing special to call for any comment in the technical methods employed, except to mention that the patterns on the bone objects were often engraved by means of a pair of compasses, and that the vessels of Kimmeridge shale were turned on a lathe.

Of the basketry in which the Celts excelled in the time of Cæsar² no specimens are now extant, but no doubt their natural talent for decorative art showed itself in this native industry of Britain, as in all others.

LEADING CHARACTERISTICS OF THE LATE-CELTIC
STYLE OF ART

Once the eye of a trained archæologist has become familiar with the general appearance of the art products of the Late-Celtic school, it is comparatively easy for him to recognise other products of the same school almost by intuition ; but he would find it a much more difficult task if he were asked to define exactly what the peculiarities are by which he is enabled to distinguish this particular style from any other. Most of the decorative elements composing the style are of so fantastic and original a nature as to impress themselves first on the retina of the eye, and then on the mind ; yet, on that very account, they seem to elude the

¹ *Archæologia*, vol. lii., p. 359.

² C. Elton's *Origins of English History*, p. 122.

descriptive powers of the writer. The motives employed are neither purely geometrical in character nor have they been obviously arrived at by conventionalising natural forms, but are something between the two, being (like the designs on the ancient British coins) the result of successive copying. We will, however, notwithstanding the difficulties that have been pointed out, endeavour to analyse the decoration of the Late-Celtic period as far as it is possible to do so.

Unlike the art of the Bronze Age, the art of the Late-Celtic period does not appear to have been in any way influenced by religious symbolism, and therefore must be looked upon as purely decorative. The designs may be divided into three classes as regards the method of their execution, namely:—

- (1) Designs engraved on a flat surface.
- (2) Designs in relief on a flat surface.
- (3) Designs in the round.

The designs themselves may be classified as follows:—

- (1) Anthropomorphic designs.
- (2) Zoöomorphic designs.
- (3) Designs derived from foliage.
- (4) Curvilinear geometrical designs.
- (5) Rectilinear geometrical designs.

Anthropomorphic and zoöomorphic designs are extremely rare in Late-Celtic art in Great Britain, and the two best-known examples—the buckets from Marlborough¹ and Aylesford²—have, according to Dr. Arthur Evans, been imported from Gaul. The Marlborough bucket is encircled by four horizontal metal bands, the upper three of which are decorated with human heads

¹ Sir R. C. Hoare's *Ancient Wills*, vol. ii., p. 34, and W. Cunnington's *Catal. of Stourhead Coll. in Devizes Museum*, p. 88.

² *Archæologia*, vol. lii., p. 374.

and pairs of animals in repoussé work. The projections at each side of the rim, to which the crossbar at the top is attached, have pairs of human heads upon them. The mountings of the Aylesford bucket consist of three bronze bands, the lower two of which are plain and the uppermost one ornamented with pairs of animals and a peculiar kind of scrollwork. Each of the attachments for the handle at the top has upon it a single human head surmounted by a sort of crested helmet.

The style of the art of the two buckets is the same, and corresponds in some respects with that of the Gaulish coins,¹ and in others with that of the sword-sheaths from La Tène² and the bronze *situlae* from Hallstatt, Watsch, and Certosa.³ Dr. Arthur Evans has dealt so exhaustively with the details of these buckets and the origins of the art they exhibit in his paper on the Aylesford find in the *Archæologia*,⁴ that there is really little more to be said on the subject. It may, however, be worth while directing attention to the scrolls hanging down from the mouths of one of the pairs of beasts on the Marlborough bucket. Anyone unacquainted with the origin of these scrolls would probably mistake them for the animal's tongue protruding from its mouth, but on comparing the designs on the Marlborough bucket with those on the *situlae* just referred to, the scrolls will be seen to be simply degraded copies of the branch of a tree on which the animal is feeding. The art metalworkers who made the *situlae* were, in fact, in the habit of using a simple convention for emphasising the difference between the

¹ *Dictionnaire Archéologique de la Gaule.*

² E. Vouga, *Les Helvètes à La Tène.*

³ Illustrated in the second edition of Dr. R. Munro's *Bosnia Herzegovina*, p. 407.

⁴ Vol. liii., p. 360.

herbivorous and carnivorous animals by showing, in one case, the branch of a tree, and in the other the leg of its prey protruding from its mouth. The Celtic copyists were either ignorant of this convention or disregarded it, so that in their hands both the branches and legs were soon converted into meaningless scrolls bearing hardly any resemblance to the original. Throughout the whole range of Celtic art there is displayed a tendency when dealing with plants and animals to transform first the details and afterwards the whole thing represented into curvilinear geometrical ornament.

Besides the buckets just described, there are a few other examples of zoöomorphic designs in Late-Celtic art, amongst which are the small bronze figures of animals found at Hounslow,¹ Middlesex, now in the British Museum; the bronze armlet, terminating in serpents' heads, from the Culbin Sands,² Elginshire; the knife-handle, terminating in a bull's head, from Birdlip,³ Gloucestershire; the iron fire-dogs,⁴ with up-rights terminating in horned beasts' heads, from Mount Bures, Essex, Hay Hill, Cambridgeshire, and Shefford, Bedfordshire; the horned bronze helmet from Torrs,⁵ Kirkcudbrightshire, now at Abbotsford; the swine's head from Liechestown,⁶ Banffshire, now in the Banff Museum; and the bull's head from Ham Hill,⁷ Somerset, in the Taunton Museum.

The heads of the bull on the knife-handle from

¹ *Proc. Soc. Ant. Lond.*, ser. 2, vol. iii., p. 90.

² Dr. J. Anderson's *Scotland in Pagan Times: Iron Age*, p. 156.


³ *Trans. Bristol and Gloucestersh. Archæol. Soc.*, vol. v., p. 137.

⁴ *Archæologia Cambrensis*, ser. 6, vol. i., p. 41.

⁵ Dr. J. Anderson's *Scotland in Pagan Times: Iron Age*, p. 113.

⁶ *Ibid.*, p. 117.

⁷ *Proc. Somersetsh. Archæol. Soc.*, ser. 3, vol. viii., p. 33.



Engraved Ornament on Late-Celtic Wooden Tub found at the Glastonbury Lake Village



Ornament on backs of handles of pair of Late-Celtic Spoons from Weston, near Bath
Scale † linear

Birdlip, and the beasts on the fire-dogs from Hay Hill and Shefford, have horns with round knobs on the end of each. Beasts with knobbed horns of this kind are represented on the Scandinavian gold bracteates¹ of the Early Iron Age, generally associated with the swastika symbol. Similar horns are to be seen on the helmet of a small bronze figure found in Denmark;² on a figure depicted on the silver bowl from Gundestrup,³ Jutland; and on the handles of gold vessels from Rönninge,⁴ Boeslund,⁵ and Fyen,⁶ Denmark. The horns probably have some religious significance.

Foliage so slightly conventionalised as to be easily recognised as such cannot be said to exist in Late-Celtic art, yet the foliaceous origin of many of the designs at once betrays itself in the undulating curves with scrolls repeated at regular intervals on each side of what may be called the stem-line. We cannot select any better examples as illustrating this than the two beautiful bronze sword-sheaths from the crannog at Lisnacrogghera,⁷ Co. Antrim. Here the portions of the designs which represent the principal stem consist of two lines running close together parallel to each other until they reach the point where a smaller stem branches off, when they diverge. The smaller stems, like the principal stem, consist of parallel lines running close together, and these, again, diverge to form what re-

¹ Prof. G. Stevens' *Old Northern Runic Monuments*.

² J. J. A. Worsaae's *Industrial Arts of Denmark*, p. 109.

³ Sophus Müller in *Nordiske Fortidsminder*, pt. 2, pl. 10.

⁴ A. P. Madsen's *Bronse Age*, ii., pl. 25.

⁵ *Industrial Arts of Denmark*, p. 105.

⁶ P. B. Du Chaillu's *Viking Age*, vol. i., p. 97.

⁷ *Jour. R. Hist. and A. A. of Ireland*, ser. 4, vol. vi., pp. 384-90. The decoration of a wooden tub found at the Glastonbury Marsh Village affords another very good instance of a Late-Celtic pattern derived from foliage.



UPPER PART OF BRONZE
SWORD-SHEATH, FROM
LISNACROGHERA,
CO. ANTRIM;
NOW IN THE
BRITISH MUSEUM



LOWER PART OF BRONZE
SWORD-SHEATH, FROM
LISNACROGHERA,
CO. ANTRIM;
NOW IN THE
BRITISH MUSEUM

presents the leaf. The ends of the leaves terminate in small spirals and their general shape resembles that of what are known as arabesques. We thus get the long sweeping S-shaped curves and the alternate contractions and expansions of the space between the two boundary lines which are common to nearly all Late-Celtic ornament. Now, for some inscrutable reason, the natural forms of plant life never seem to have appealed to the Celtic mind in the way they did, for instance, to the ecclesiastical sculptors of the twelfth and thirteenth centuries. Consequently the designs which were in the first instance copied from foliage soon became transformed into a succession of beautiful flamboyant curves, pleasing to the eye unquestionably, but suggesting but little to the mind as to their meaning. In reference to this, Dr. Arthur Evans remarks:—¹

“The tendency of all Late-Celtic art was to reduce all naturalistic motives borrowed by it from the classical world to geometrical schemes. . . . Yet the whole history of Late-Celtic art instructs us that this geometrical scheme, elaborate as it is, was originally based on ornaments of a naturalistic kind.”

Once the foliageous origin of the flamboyant patterns was lost sight of or disregarded, it became easy to elaborate fresh designs by placing the forms derived from the leaves and stems of plants in all sorts of unnatural positions relatively to each other, as, for instance, on the pair of bronze spoon-like objects from Weston, near Bath, which are now in the Edinburgh Museum of Antiquities, and in a particular class of pierced ornaments, several of which are illustrated in

¹ *Archæologia*, vol. lv., p. 404.

L. Lindenschmit's *Die Alterthümer unserer heidnischen Vorzeit*.¹

A still further transformation resulted from the practice of drawing the various curves by means of a pair of compasses, and once this mechanical method had been adopted the temptation to introduce complete circles of different sizes into the designs would follow as a matter of course. This is very clearly seen on the ornamented bone spatulæ from Slieve-na-Caillighe, Co. Meath, already referred to as having been found with a pair of iron compasses; and also on backs of the bronze mirrors, of which a list is given on p. 115. It is most remarkable that the Late-Celtic artists should have succeeded in doing what has baffled everyone else before or since, namely, in producing "sweet" curves by means of a combination of circular arcs.



Engraved Bone
object from
Slieve-na-
Caillighe,
Co. Meath

Lastly, when the patterns which had thus been evolved from natural foliage on a flat surface were transferred to the relief of the repoussé metalwork, and raised bosses, volutes, and round plaques of enamel substituted for the complete flat circles, an entirely new style of decoration was brought into existence. The most appropriate name that can be given to this particular kind of Celtic ornament is *flamboyant* work. The French word *flamboyer* means to blaze, and the Gothic window tracery of the fourteenth century, in which S-shaped curves predominate, is called *flamboyant*

¹ Vol. i., pt. x., pl. 6; vol. ii., pt. viii., pl. 5; vol. iii., pt. vii., pl. 6. Compare these with the ornament found at Silchester, illustrated in the *Archæologia*, vol. liv., p 470.



HANDLE OF LATE-CELTIC BRONZE
TANKARD FROM TRAWSFYNYDD,
MERIONETHSHIRE; NOW IN THE
MAYER MUSEUM, LIVERPOOL



BRIDLE-BIT OF BRONZE ENAMELLED FROM RISE, NEAR HULL,
NOW IN THE BRITISH MUSEUM

SCALE $\frac{1}{2}$ LINEAR

on account of its resemblance to tongues of flame. The handle of the Late-Celtic tankard from Trawsfynydd,¹ Merionethshire, now in the Liverpool Museum, if reproduced in stone on a larger scale, would certainly be mistaken for a piece of Gothic tracery, so that it may almost be looked upon as a blasphemous anticipation of Christian art by the Pagan Celt.

The best examples of the Late-Celtic flamboyant work, for purposes of study, are the bronze shield from the river Thames, a circular disc of unknown use from Ireland, both in the British Museum; the gold collar from Limavady, Co. Londonderry, in the Museum of the Royal Irish Academy, Dublin; and the Æsica fibula, in the Newcastle Museum. There is also a disc in the Dublin Museum of similar design to the one in the British Museum, which is worth comparing with it.

The whole design of the shield from the Thames is arranged with a due regard to symmetry. The small circular plaques of enamel, which are a leading feature in the scheme of decoration, are placed in definite positions, in groups of four and eight, around a central plaque within a raised boss. The plaques are connected by S-shaped curves in relief, which vary in width and in height above the background in different places. The highest part of the curve is emphasised by a sharp ridge which does not traverse the whole length of the curve midway between the margins, but at one place approaches near one edge, and a little further on approaches the other. An extremely complicated solid, bounded by curved surfaces, is thus formed, the appearance of which can only be realised by seeing the thing itself or a model of it.

¹ *Archæologia Cambrensis*, ser. 5, vol. xiii., p. 212.

The circular bronze discs and the gold collar from Ireland exhibit a class of flamboyant work which is somewhat different from that on the shield from the



Fibula of Bronze Gilt from Æsica
Now in the Newcastle Museum. Scale $\frac{1}{2}$ linear

Thames, and is still further removed from the original foliage motive designs. Here conchoids take the place of the circular enamelled plaques arranged in symmetrical positions, and the curves connecting them



**DETAIL OF ORNAMENT ON LATE-CELTIC BRONZE SHIELD
FROM THE THAMES AT BATTERSEA; NOW IN
THE BRITISH MUSEUM**

with each other have the trumpet-shaped terminal expansions, which are so characteristic of the Late-Celtic style, very highly developed. A further modification that disguises the foliageous origin of the design is the substitution of two C-shaped curves meeting at an angle for the more gracefully flowing S-shaped curves. Examples of a running pattern composed of C-shaped curves meeting at an angle in the way described, occur on a bronze collar from Lochar Moss,¹ Dumfriesshire, now in the British Museum (see p. 112). A running pattern composed of C and S-shaped curves alternately meeting at an angle occurs on the enamelled mounting of a bronze bowl from Barlaston,² Staffordshire. We have pointed out the changes due to copying in relief a design engraved on a flat surface; but curiously enough when the decoration of the repoussé metalwork was again transferred to a flat surface, as in the enamelled fittings of the bronze bowls and in the spiral ornamentation of the illuminated MSS. of the Christian period, it did not return to what it was before, but became still



Flamboyant Ornament on Collar from Broighter, Limavady, Co. Londonderry

¹ *Archæologia*, vol. xxxiii., p. 347.

² *Ibid.*, vol. lvi., p. 44.

more unlike its foliageous prototype. It will be noticed that the ends of the trumpet-shaped expansions on the bronze discs and gold collar being in the highest relief catch the light. In the MSS. and enamels this effect is imitated by small almond-shaped spots of a different colour from the rest. The beautiful repoussé ornament on the bronze mirror from Balmaclellan,¹ Kirkcud-



Spiral Ornament in Illuminated MS.
copied from repoussé metalwork

brightshire, now in the Edinburgh Museum of Antiquities, supplies us with another instance of little raised bosses which were afterwards reproduced on the flat by means of colour in the Christian MSS.

Many of the curvilinear Late-Celtic patterns which are used to fill a circular space are based upon the triskele and the swastika. A good example of a curved swastika pattern occurs on each of the three enamelled handles of a bronze bowl found at Barlaston,² Staffordshire. Triskele designs are much more common, especially on the round disc fibulæ, specimens of which have been found at Silchester,³ Hampshire; Brough,⁴ Westmoreland; and in the Victoria Cave,⁵ near Settle, Yorkshire. There are other instances on the bronze

¹ Dr. J. Anderson's *Scotland in Pagan Times: Iron Age*, p. 127.

² *Archæologia*, vol lvi., p. 44.

³ Now at Strathfieldsaye House.

⁴ *Proc. Soc. Ant. Lond.*, ser. 1, vol. iv., p. 129.

⁵ *Historic Soc. of Lanc. and Cheshire, Trans.* for 1866, p. 199.



CIRCULAR DISC OF BRONZE WITH REPOUSSÉ ORNAMENT
FROM IRELAND; NOW IN THE BRITISH MUSEUM



BRONZE ENAMELLED HARNESS-RING FROM WESTHALL,
SUFFOLK; NOW IN THE BRITISH MUSEUM

SCALE $\frac{1}{4}$ LINEAR

tankards from Elveden,¹ Essex, and Trawsfynydd,² Merionethshire; on the bronze shield from the Thames,³ now in the British Museum; on a bronze disc-and-hook ornament in the Dublin Museum;⁴ on a bronze plate in the Welshpool Museum;⁵ on some bronze harness-mountings (?) from South Shields;⁶ on bronze wheel-shaped pendants from Seamill Fort,⁷ Ayrshire, from Berkshire, now in the British Museum, from Kingsholm,⁸ near Gloucester, and from Treceiri, Carnarvonshire. These designs may have had a symbolical origin, as the triskele was a well-known sun symbol in the Bronze Age. The triskele arrangement of three spirals round a central spiral survived in the decoration of the illuminated MSS. of the Christian period.

In the repoussé metalwork of the Late-Celtic period certain portions of the design are thrown into relief in order to enable them to be distinguished from the rest which is not in relief. Much the same artistic effect can be obtained when the design is engraved on a flat surface by means of shading, and in the case of enamelled plaques, by employing different colours. In fact, by the use of relief, shading, or colour, the decorative effect of a pattern is doubled, because there are two things for the mind to comprehend, namely, the shape of the pattern itself and the shape of the background. Anyone who endeavours to realise both shapes simultaneously will find it an impossibility.

Several different kinds of shading are used in Late-

¹ *Archæologia*, vol. lii., p. 359.

² *Archæologia Cambrensis*, ser. 5, vol. xiii., p. 212.

³ Kemble's *Horæ Ferales*, pl. 15.

⁴ *The Reliquary* for 1901, p. 56.

⁵ Unpublished.

⁶ *Jour. Brit. Archæol. Assoc.*, vol. xxxix., p. 90.


⁷ R. Munro's *Prehistoric Scotland*, p. 378.

⁸ Douglas' *Nenia Britannica* p. 134.

Celtic art, chiefly in ornament engraved on metal, wood, bone, and pottery, as will be seen by the following list :—

List showing different kinds of shading used in Late-Celtic Art, and the objects on which they occur.

(1) Shading of parallel lines.




On spoon-like bronze objects from Crosby Ravensworth, Westmoreland, and Ireland.

On bronze mirror from Stamford Hill, near Plymouth.

On engraved pottery from Glastonbury Marsh Village.


On bronze sword-sheath from Embleton.

(2) Cross-hatching placed diagonally.




On engraved piece of wood and engraved pottery from the Glastonbury Marsh Village.

(3) Cross-hatching placed diagonally, with dots in each of the square meshes.




On engraved wooden tub from the Glastonbury Marsh Village.

(4) Cross-hatching of double lines placed diagonally.



On engraved piece of wood from the Glastonbury Marsh Village.


(5) Chequerwork grass-matting shading.



On bronze sword-sheath from crannog at Lisnacrogghera.


On bronze mirrors from Trelan Bahow, Cornwall ; Birdlip, Gloucestershire ; from unknown locality, now in the Liverpool Museum ; and from Stamford Hill, near Plymouth.

(6) Engine-turned shading.



On gold collar from Limavady.

(7) Dotted shading.



On bronze spoon-like objects in the Dublin Museum.

On bronze harness-ring from Polden Hill, Somersetshire.

On silver armlet from Stony Middleton, Bucks.


Besides the Late-Celtic objects just described, which exhibit curvilinear surface decoration derived from foliage, there are others with very peculiar forms "in the round." Amongst these are the harness-rings with projecting knobs from Polden Hill, Somersetshire ;

Stanwick, Yorkshire, and elsewhere; the beaded torques from Lochar Moss, Dumfriesshire; Hynford, Lanark; and the beaded bracelets from Arras and Cowlam, Yorkshire.

The projections on the harness-rings generally occur at three points round the circumference, and their shapes will be better understood from the illustrations than from any written description. It is not easy to say what the meaning or origin of these projections can be, as they bear no obvious resemblance to any natural or artificial object.

The beaded torques mentioned are composed of separate metal beads (usually of two different shapes) strung on a square iron rod, so that they cannot rotate or rattle about. The bracelets are, however, cast in one piece, and made in imitation of a string of beads. This style of bracelet is of foreign origin, as specimens have been found in France¹ and Germany,² many of which are elaborately ornamented with spiral-work in high relief.

Rectilinear patterns are of comparatively rare occurrence in Late-Celtic art, as the designers of the period appear to have had a rooted objection to using straight lines if they could possibly be avoided. There are, however, a few exceptions. The small circular enamelled plaques with which the bronze shield from the Thames, now in the British Museum, is decorated, have a swastika pattern on each. The swastika was probably a foreign importation, as it



Swastika design on Shield from the Thames

¹ *Dictionnaire Archéologique de la Gaule.*

² Lindenschmit's *Alterthümer.*

is used in the decoration of the Gaulish bronze helmet from Gorge-Meillet¹ (Marne), and of the iron lance-head from La Tène,² Switzerland.

The step-pattern in Late-Celtic art may have had a textile origin, *i.e.* have been copied from a woven belt or other fabric. Instances of it occur on a piece of engraved wood from the Glastonbury³ Marsh Village; on the bronze mountings of a shield from Grimthorpe,⁴ Yorkshire, now in the British Museum; on the bronze ferrule of a spear-shaft from the Crannog at Lisnacroghera,⁵ Co. Antrim; and on a sculptured monolith at Turoe, Co. Galway. The step-pattern survived after the Pagan period in the Christian enamels, as in the bowl from Möklebust,⁶ Norway, and the fragment at St. Columba's College,⁷ Dublin. The key-pattern, or Greek fret, is unknown in Late-Celtic art.

The chequerwork pattern may also have had a textile origin. There is an example of it on the bronze sword-sheath from Embleton,⁸ Cumberland, now in the British Museum.

The chevron and lozenge patterns are possibly survivals from the preceding Bronze Age. We have instances of the chevron pattern on the bronze mirror from Trelan Bahow,⁹ Cornwall, and on a potsherd from the Glastonbury¹⁰ Marsh Village; and of the lozenge on the stave of a bucket¹¹ from the same site.

¹ A. Bertrand's *Archéologie Celtique et Gauloise*, p. 367.

² E. Vouga's *Les Helvètes à La Tène*, pl. 5.

³ *The Antiquary* for 1895, p. 110.

⁴ Ll. Jewitt's *Grave Mounds and their Contents*, p. 246.

⁵ *Jour. R. Hist. and Archæol. Assoc. of Ireland*, ser. 4, vol. vi., p. 394.

⁶ *Mém. de la Soc. Ant. du Nord*, 1890, p. 35.


⁷ J. B. Waring's *Manchester Fine Art Treasures Exhibition*.

⁸ Kemble's *Horæ Ferales*, pl. 18, fig. 3.

⁹ *Archæol. Jour.*, vol. xxx., p. 267.

¹⁰ *Proc. Somersetsh. Archæol. Soc.*, vol. xl.

¹¹ *The Antiquary* for 1895, p. 110.



Engraved Step Ornament on piece of wood found at the Glastonbury Lake Village

Drawn by Arthur Bulleid, F.S.A.

CHAPTER VI

CELTIC ART OF THE CHRISTIAN PERIOD (A.D. 450 to 1066)

THE INTRODUCTION OF CHRISTIANITY INTO BRITAIN, AND ITS EFFECT ON NATIVE ART

IT must always be borne in mind that the conversion of the inhabitants of Britain from Paganism to Christianity was a very gradual process, extending over a period of two hundred years at least. It seems probable that during the last hundred years or so of the Roman occupation of Britain the Christian faith may have been accepted by a limited number of the native population; but almost as soon as the new religion began to take root in England it was entirely swept away by the Saxon conquest, and the few converts who were not exterminated by the ruthless Pagan invaders fled for refuge to Wales and Cornwall. The archæological evidence of the existence of Romano-British Christianity is extremely scanty. Out of the hundreds and hundreds of inscribed and sculptured monuments belonging to the period of the Roman occupation of Britain there is not one which bears a Christian symbol or shows a trace of Christian art. There are only two instances of the occurrence of a Christian symbol on a Romano-British structure, namely, (1) at Chedworth,¹ where the Chi-Rho Mono-

¹ *Journ. Brit. Archæol. Assoc.*, vol. xxiii., p. 228.

gram is carved twice upon a stone in the foundation of the steps leading into the corridor of a Roman villa there; and (2) at Frampton,¹ Dorsetshire, where the same Monogram forms part of the decoration of a mosaic pavement in one of the rooms of a Roman villa. As Romano-British Christianity produced no effect on the art of this country, we are not further concerned with it.

Whilst England remained under the dominion of Saxon Pagandom for a century and a half in some parts, and for nearly two centuries in others, Christianity spread rapidly from Gaul to Cornwall, Wales, and the south-west of Scotland, and thence to Ireland. After the Saxons were converted by St. Augustine, in A.D. 597, there was a return wave of Celtic Christianity from Ireland to Iona, and from Iona to Lindisfarne, in Northumbria, which was founded A.D. 635. The localities where Christianity was first planted in Britain are indicated archæologically by the geographical distribution of monuments bearing the Chi-Rho Monogram, which is as follows:—

CORNWALL. St. Just.
St. Helen's Chapel.
Phillack.
Southill.

CARNARVONSHIRE. Penmachno.
WIGTOWNSHIRE. Kirkmadrine.
Whithorn.

As the Chi-Rho Monogram does not occur on the early inscribed stones of Ireland, but in place of it the cross with equal arms expanded at the ends, enclosed in a circle, which is derived from the Monogram,² it

¹ S. Lysons' *Reliquiæ Brittanico Romanæ*, No. 3, pl. 5.

² See J. R. Allen's *Christian Symbolism*, p. 94. The Chi-Rho Monogram occurs on inscribed monuments in Gaul between A.D. 377 and 493.

naturally follows that Irish Christianity is later than that of Cornwall, Wales, and the south-west of Scotland.

Setting aside the vague and unsatisfactory statements of the mythical period (such as the one about the presence of three British at the Council of Arles in A.D. 314), we find that the real history of the Christianising of this country begins with the opening years of the fifth century, and that it followed directly from the foundation of the school of learning and centre of missionary enterprise by St. Martin at Tours, in France. In A.D. 397 St. Martin died, and not long after, in A.D. 412, his disciple, St. Ninian, built a stone church dedicated to his master at Whithorn, Wigtownshire. In A.D. 429 Germanus, Bishop of Auxerre, and Lupus, Bishop of Troyes, visited Britain in order to suppress the Pelagian heresy. About the same time the conversion of Ireland is believed to have been commenced by either St. Patrick or by St. Palladius (*circa* A.D. 432). The sixth century witnessed the foundation of the great school of ecclesiastical learning at Llantwit Major, Glamorganshire, where St. David, St. Samson, and Gildas the historian were educated; but an event of even greater importance was the landing of St. Columba at Iona in A.D. 563, and the subsequent conversion of the northern Picts. The sixth century ends with the conversion of Kent by St. Augustine in A.D. 597. It was eighty-four years more before the South Saxons accepted Christianity and the conversion of England became complete. In the meantime the differences between the Saxon and Celtic Churches had been settled in favour of the former at the Synod of Whitby in A.D. 664.

Reviewing the historical facts just mentioned, it

appears that for about 200 years (from A.D. 450 to 650) there was a separate Celtic Church in Britain, which may appropriately be called the pre-Augustinian Church. The question now naturally suggests itself, to what extent did the introduction of Christianity influence the native art of Britain during the 200 years which followed the departure of the Romans from its shores? The answer supplied by archæology is that before about A.D. 650 there was no distinctively Christian art existing in this country.

The monuments belonging to the pre-Augustinian Church consist of rude pillar-stones with incised crosses of early form, or with Latin inscriptions in debased Roman capitals, sometimes with Celtic inscription in Ogam in addition. The monuments of this class do not, as a rule, show any trace of ornament or sculpture beyond the crosses and inscriptions. The only recorded exceptions are—

An Ogam-inscribed stone from Pentre Poeth,¹ Brecknockshire, now in the British Museum, having on one face a bishop with his crozier, St. Michael and the Dragon, and very rude zigzag ornament.

An Ogam-inscribed stone from Glenfahan,² Co. Kerry, now in the Dublin Museum, with rude spiral ornament, a figure of a man, a looped pattern, and several crosses.

An Ogam-inscribed stone at Killeen Cormac,³ Co. Kildare, lying prostrate near the entrance gate, with a bust of Christ carrying the cross over the right shoulder.

St. Gobnet's Stone at Ballyvourney,⁴ Co. Cork, with a cross enclosed in a circle, surmounted by the figure of a bishop holding his crozier.

¹ *Archæologia Cambrensis*, ser. 6, vol. i., p. 240.

² *Trans. Royal Irish Academy*, vol. xxxi., p. 318.

³ *Journ. R. Hist. and A. A. of Ireland*, ser. 4, vol. ii., p. 546.

⁴ *Archæol. Jour.*, vol. xii., p. 86.

A stone, with a minuscule inscription, at Reask,¹ Co. Kerry, having on the same face a cross in a circle, with incised spiral ornament at each side of the shaft.

The stones, with incised symbols of unknown meaning, which are so common in the north-east of Scotland,



Enamelled Handles of Bronze Bowl found at Barlaston, Staffordshire
Now in the possession of Miss Amy Wedgwood. Scale † linear

possibly belong to the same early period. The ornament on some of them has a very marked Late-Celtic character.

There are no Celtic MSS. with illuminations or ornament of any kind to which a date earlier than A.D. 650

¹ *Archæologia Cambrensis*, ser. 5, vol. ix., p. 147.

can be assigned, but there are a certain number of metal objects which illustrate the overlap of the Pagan and Christian styles of Celtic art. Amongst the most important of these are the bronze bowls with enamelled mountings and zoö-morphic handles which have been



Enamelled Handle of Bronze Bowl from Chesterton-on-Fossway,
Warwickshire

• Now in the Warwick Museum. Scale † linear

described at some length by the author in the *Archæologia* (vol. lvi., p. 43). The chief peculiarities of the bowls is the hollow moulding just below the rim and the three or four handles with rings for suspension. The upper part of each handle is like a hook, terminating in a beast's head, which rests on the rim of the bowl and projects inwards over it. The lower part of

each handle is circular, or in the shape of the body of a bird, and is fixed to the convex sides of the bowl. The circular form is most common in the examples found in England, and the disc is either ornamented with *champlevé* enamel¹ or with piercings, giving a cruciform appearance.²



Enamelled Handle of Bronze Bowl from Chesterton-on-Fossway,
Warwickshire

Now in the Warwick Museum. Scale † linear

The earliest of the series from Barlaston, Staffordshire, now in the possession of Miss Wedgwood, has three handles all alike, ornamented with discs of enamel,

¹ As in the specimens from Barlaston, Staffordshire; Chesterton-on-the-Fossway, Warwickshire; Barrington, Cambridgeshire; Crosthwaite, Cumberland; Middleton Moor, Derbyshire; Oxford; and Greenwich.

² As in the specimens from Wilton, Wilts; and Faversham, Kent.

the designs on which are distinctly Late-Celtic in style, and consist of small circles connected by C- and S-shaped curves. In the case of the enamelled handles of the other specimens, closely coiled spirals of the Bronze Age type take the place of the circles, and by this trifling alteration the character of the design is so completely changed as to be almost identical with the spiral decoration of the Book of Durrow and other Irish MSS. of the same period. We see here exactly



Spiral Ornament from the Book of Durrow

when and how the flamboyant ornament of Pagan Celtic art became transformed into the spiralwork of the Christian illuminated MSS. which was afterwards applied to the decoration of the sculptured crosses and ecclesiastical metalwork. The circumstances under which the bowls have been found show that they belong to the Pagan Saxon period between A.D. 450 and 600.

In the museum of the Society of Antiquaries at Burlington House there is the cast of an object from

the collection of Mr. Albert Way, the well-known antiquary, which exhibits a curious mixture of styles. Where the original is, or where it came from, is unfortunately not known, but it has every appearance of having been of metal. In the middle of the object is a square panel of triangular pierced work, exactly like that on the cover of the Stowe Missal¹ (made A.D. 1023 to 1052); whilst at each of the rounded ends are curved designs with trumpet-shaped expansions of pronounced Late-Celtic type.

Plaitwork, which is, of course, one of the leading motives of Celtic art of the Christian period, occurs occasionally in association with Pagan flamboyant ornament, as on a brooch from the Ardakillen² crannog, near Stokestown, Co. Roscommon (now in the Dublin Museum), and on a gold armet from Rhayader,³ Radnorshire (now in the British Museum).

Amongst objects belonging to the early Christian Celtic period before A.D. 600, may probably be classed the leaf-shaped silver plates engraved with symbols from Norrie's Law,⁴ Forfarshire, and the terminal link of a silver chain, also engraved with symbols, from Crawfordjohn,⁵ Lanarkshire (all in the Edinburgh Museum of Antiquities). The hammer-headed pins also, a list of which has already been given (p. 108), seem, from the enamelled designs upon them, to belong to the transitional period between Celtic Paganism and Christianity.

Although, as we have just seen, the introduction of

¹ Miss M. Stokes' *Early Christian Art in Ireland*, p. 92. The Stowe Missal is in the Museum of the R.I.A. at Dublin.

² Sir W. Wilde's *Catal. Mus. R.I.A.*, p. 569.

³ *Archæologia Cambrensis*, ser. 5, vol. xvi., p. 261.

⁴ Dr. J. Anderson's *Scotland in Early Christian Times*, 2nd ser., p. 38.

⁵ *Ibid.*, p. 44.



CAST OF METAL OBJECT (LOCALITY UNKNOWN) FROM THE ALBERT WAY COLLECTION; NOW IN THE MUSEUM OF THE SOCIETY OF ANTIQUARIES, BURLINGTON HOUSE, LONDON



COVER OF THE STOWE MISSAL IN THE MUSEUM OF THE ROYAL IRISH ACADEMY, DUBLIN

(A.D. 1023 TO 1052)

Christianity into Britain did not immediately affect the native Pagan art to any appreciable extent, yet as soon as the Saxons were converted and communication with the Continent became easier and therefore more frequent, an entirely new style of decoration came into existence with extraordinary rapidity. The flamboyant designs of the Late-Celtic period were modified by combining them with the closely coiled spiral of the Bronze Age, and several new motives, such as interlaced-work, key-patterns, zoömorphs, and foliage, were introduced from foreign sources. At the same time a complete revolution took place in the class of objects to the decoration of which the skill of the artificer was applied. The priest took the place of the warrior as the patron of the fine arts, and monopolised all the available time of the metalworker and enameller in making beautiful vessels for the service of the church. Then, too, with Christianity came the art of writing and illuminating ecclesiastical MSS., which was unknown to the Pagan Celt. The influence of the draughtsman upon other arts was now possible for the first time, and the introduction of MSS. soon worked far-reaching changes. Fresh motives could be more easily transferred from one art centre to another, and decorative designs could be combined and elaborated in a way that was impossible when working in such intractable materials as metal or stone instead of drawing on parchment with a facile pen. The new Celtic style of the Christian period soon took a definite shape, and after the patterns had been fully developed in the illuminated MSS. they were afterwards applied to decorative work in stone and metal.

GENERAL NATURE OF THE MATERIALS AVAILABLE FOR
THE STUDY OF CELTIC ART OF THE CHRISTIAN
PERIOD IN GREAT BRITAIN

The materials available for the study of Celtic Art of the Christian period may be divided into four classes, namely :—

- (1) Illuminated MSS.
- (2) Sculptured Stones.
- (3) Metalwork.
- (4) Leatherwork, Woodwork, and Bonework.

The most important collections of Irish and Hiberno-Saxon MSS. in this country are in the libraries of Trinity College, Dublin ; of the Royal Irish Academy, Dublin ; and the British Museum, London. There are other smaller collections, or in some cases single volumes only, in the University and College libraries of Oxford and Cambridge ; in the Cathedral libraries at Durham, Lichfield, and Hereford ; and in the Archiepiscopal library at Lambeth. The chief libraries on the Continent which are fortunate enough to possess specimens of Irish calligraphy and illumination (either acquired by purchase or still the property of monasteries originally founded by Irish missionaries) are at Stockholm, St. Petersburg, Paris, St. Gall and Basle in Switzerland, and at Nuremberg, Fulda, and Trèves in Germany. The Irish MSS. from the monastery founded by St. Columbanus in A.D. 613 at Bobio, in Piedmont, are distributed over the libraries at Milan, Turin, and Naples. For descriptions and illustrations of these MSS. the reader may be referred to Prof. J. O. Westwood's *Palæographia Pictoria Sacra* and *Miniatures of the Anglo-Saxon and Irish MSS.* ; C. Purton Cooper's *Report on Rymer's Fœdera, Appendix A*,

Sir H. James' *Facsimiles of the National MSS. of Ireland*; *Publications of the Palæographical Society*; Miss Margaret Stokes' *Early Christian Art in Ireland*; Dr. J. Stuart's *Book of Deer*, published by the Spalding Club of Aberdeen; J. A. Bruun's *Illuminated Manuscripts of the Middle Ages*; and Dr. W. Reeve's paper on "Early Irish Caligraphy" in the *Ulster Journal of Archæology*, vol. viii., p. 210.

The following is a list of Irish MSS. selected on account of the beauty of their illuminated pages :—

GOSPELS

Book of Lindisfarne . . .	British Museum (Nero D. iv.).
Book of Kells . . .	Trinity College, Dublin.
Book of Durrow . . .	<i>Ibid.</i>
Book of Armagh . . .	Royal Irish Academy, Dublin.
Book of St. Chad . . .	Lichfield.
Book of MacRegol . . .	Bodleian, Oxford.
Book of MacDurnan . . .	Lambeth.
Book of Deer . . .	Public Library, Cambridge.
Codex No. 51 . . .	St. Gall, Switzerland.
Golden Gospels . . .	Royal Library, Stockholm.
Gospels . . .	Imperial Library, St. Petersburg.
Gospels of St. Arnoul, Metz	Nuremberg. [burg.

PSALTERS

Vespasian A. i. . . .	British Museum.
Vitellius F. xi. . . .	<i>Ibid.</i>
Psalter of St. John's College	Cambridge.
Psalter of Ricemarchus . . .	Trinity College, Dublin.

Some of the above MSS. can be dated by means of entries giving the name of the scribe or other person, who can be identified by contemporary or nearly contemporary historical record. The oldest MS. with

illuminations in the Hiberno-Saxon style which can be thus dated is the Lindisfarne Book. It contains two entries written in an English hand of the tenth century, which show that the volume was written by Eadfrith, Bishop of Lindisfarne; that Æthilwold, Bishop of Lindisfarne, made the cover for it; that Billfrith, the anchorite, wrought the metalwork for it; and that Aldred, the priest, over-glossed it in English for the love of God and St. Cuthbert. Eadfrith held the see of Lindisfarne from A.D. 698 to 721, and was then succeeded by Æthilwold, who held the bishopric of the island until his death in A.D. 740. The Book of Lindisfarne, therefore, must have been written either during the last two years of the seventh century or the first twenty-one years of the eighth century. This may be looked upon as the starting-point of all Hiberno-Saxon art, and its origin may be fairly traced to Lindisfarne, where the Scotie and Anglo-Saxon schools were able to mingle, each reinvigorating the other to their mutual advantage.

The Book of Kells makes its first appearance in history in A.D. 1006, during which year it is recorded in the *Annals of the Four Masters* that the Great Gospels of Columkille was stolen. Although the name of the scribe who wrote and illuminated this book is unknown, it is probable, from the style of the decoration and lettering, that it belongs to about the same period as the Lindisfarne Book, but somewhat later, as the Book of Kells contains foliage amongst the ornament, and is altogether more elaborate.

The Book of Durrow was written by a scribe named Columba, who can hardly have been the celebrated Saint of that name, as his time is far too early for it. Since the spiral patterns in the Book of Durrow

approximate more nearly to the flamboyant designs of the Pagan-Celtic metalwork than those in any other MS., it cannot be dated later than the eighth century.

The Book of St. Chad should more properly be called the Book of St. Teilo, as it contains an entry stating that the volume was purchased by Gelhi, son of Arihtuid, from Cingal for his best horse, and dedicated to God and St. Teilo. Before it was at Lichfield it lay on the altar of Teilo, at Llandaff. This MS. has also a good claim to be of the eighth century.

The Book of Armagh and the Golden Gospels of Stockholm are of the ninth century. The former was written by Ferdornach, "a sage and choice scribe of Armagh," who died in A.D. 844. The Stockholm Gospels contains a deed of gift, which shows that the volume was bought by the Earl Ælfred and Wetburg his wife from a Viking, and presented by them to the Cathedral of Canterbury. The deed is signed by Ælfred, Wetburg, and their daughter Alhtryth, who have all been identified by the will of Ælfred, which is attested by Æltered, Archbishop of Canterbury, from A.D. 871-9. The Gospels of MacRegol also belongs to the ninth century, if the identification of the scribe who wrote it with "MacRiagoil nepos Magleni, Scriba et Episcopus Abbas Biror" can be relied upon. His death is recorded in the Irish Annals under the year A.D. 820.

The Gospels of MacDurnan is of the tenth century. It has an inscription on one of the blank pages of the MS. showing that the book was either written for, or was in the possession of, Maelbrigid MacDurnan, and that it was given by King Athelstan to the city of Canterbury. Maelbrigid MacDurnan was Abbot of Derry in the ninth century, and was afterwards

promoted to the see of Armagh in A.D. 927. He died in A.D. 927. Athelstan reigned from A.D. 925 to 941.

The Psalter of Ricemarchus is of the eleventh century. It contains a Latin poem, from which we gather that the book was written by Ricemarch Sulgenson, with the assistance of Ithael, "whose name makes learning golden," and that the initial letters were illuminated by John. Ricemarch, or Rhyddmarch, succeeded his father Sulgen in the see of St. Davids in A.D. 1089, and died in A.D. 1096.

The examples given afford a very good series arranged in chronological order, showing the modifications which the style underwent in the course of the four centuries between A.D. 650 and 1050. We are somewhat sceptical as to there having been any fine illuminated Hiberno-Saxon MSS. before A.D. 700; but assuming that there may have been some which are no longer in existence, the best period is from A.D. 650 to 850; then from A.D. 850 to 950 there is a middle period of rather inferior excellence; and, lastly, from A.D. 950 to 1050 a distinct period of decline which went on with increasing decadence for a century or two after the Norman Conquest.

The number of illuminated pages in the different MSS. varies considerably, sometimes because the volumes are imperfect, but also because they were less lavishly illustrated in the first instance. The illuminated pages in the copies of the Gospels are of the following kinds:—

- (1) Initial pages.
- (2) Ornamental or Cross pages.
- (3) Symbols of the Evangelists.
- (4) Portraits of the Evangelists.
- (5) Scenes from the Life of Christ.
- (6) Tables of Eusebian Canons.

As an instance of a very completely illustrated MS. of the Gospels we may take the Lindisfarne Book, which contains twenty-three full pages of illumination as specified below:—

Four portraits of the Evangelists with their Symbols, one for each Gospel.

Five ornamental pages, one before St. Jerome's Epistle and one before each Gospel.

Six *Initial pages*, namely—

“Novum opus,” commencing St. Jerome's Epistle.

“Liber generationis,” commencing St. Matthew's Gospel.

“ $\overline{\text{XPI}}$ autem generatio,” commencing the Genealogy of Christ in St. Matthew's Gospel.

“Initium Evangelii,” commencing St. Mark's Gospel.

“Quoniam quidem,” commencing St. Luke's Gospel.

“In principio erat,” commencing St. John's Gospel.

Eight pages of tables of Eusebian Canons.

The Book of Durrow has sixteen illuminated pages, namely, four of the Symbols of the Evangelists; six ornamental pages, one at the frontispiece, one before the Preface of St. Jerome, and one before each Gospel; and the usual six initial pages.

The Book of Kells is more profusely illustrated than any other Irish MS. in existence. Besides innumerable large and small initials, it contains three portraits of the Evangelists, three combined symbols of the Four Evangelists, three scenes from the Life of Christ—namely, the Virgin and Child, Christ seized by the Jews, and the Temptation of Christ, and eight pages of Eusebian Canons.

The St. Gall Gospels (Codex No. 51) has twelve full pages of illumination, namely, four portraits of the Evangelists, five initial pages, one ornamental cross-

page, and two scenes from the Life of Christ—the Crucifixion and Christ in Glory.

As an instance of the method of illustrating the Irish MSS. of the Psalter we may take the one in the library of St. John's College, Cambridge. This has six illuminated pages, namely—

- (1) "Beatus vir," commencing the 1st Psalm.
- (2) "Quid gloriaris" ,, ,, 51st ,,
- (3) "Dñe exaudi" ,, ,, 101st ,,
- (4) Miniature of the Crucifixion.
- (5) ,, David and Goliath.
- (6) ,, David and the Lion.

The Vit. F. xi. Psalter in the British Museum has two initial pages and two miniatures, namely, David and Goliath, and David playing the harp.

The Vesp. A. i. Psalter in the British Museum has only one miniature, namely, David playing the harp; but it has a great number of extremely beautiful initial letters ornamented with spiralwork of the best quality. Figure subjects (one of David and the Lion) are introduced in the initials of the 26th, 52nd, 68th, 97th, and 109th Psalms.

The details of the ornamental patterns in the MSS. will be dealt with when we come to consider the leading characteristics of the style; all that we need do now, therefore, is to point out the manner in which the patterns are distributed. The treatment of the miniatures of the Evangelists and of the scenes from the Life of Christ and the Life of David is very simple; the picture is enclosed within a rectangular frame divided into panels, each filled in with a separate piece of ornament complete in itself. Sometimes, as in the case of the miniatures of Christ seized by the Jews in the Book of Kells, and David playing the harp in the

Vesp. A. i. Psalter, the figures are placed beneath an arch supported by columns at each side. The architectural origin of the design is entirely concealed by converting the columns and the arch into pieces of flat ornament arranged in panels. The pages of Eusebian Canons are also treated architecturally, the tables being placed under arcading so disguised by the incrustations of ornament as to be almost unrecognisable. The initial pages of the Gospels are only partially surrounded by a rectangular frame, so as to allow the tops of the large capital letters to project beyond the frame into the margin. The incomplete portion of the frame on the right side of the page is covered into a zoomorph in a characteristically Celtic manner by adding the head of a monster at the top and a fish-like tail at the bottom. The frame and the larger initials within it are covered with panels of ornament. The pages of ornament are generally arranged in rectangular panels, so as to give the appearance of a cross; or sometimes, as in the Book of Durrow, there is a small equal-armed cross within a circle in the middle of the page, the remainder of which is entirely filled up with ornament. In many cases where the miniatures, etc., are surrounded by a rectangular frame the outer margins are extended and formed into ornamental knots at each of the four corners.

After the Celtic style of decorative art of the Christian period had been fully developed in the Irish and Hiberno-Saxon illuminated MSS. of the eighth century, it was afterwards applied to sculptured stonework in the ninth, tenth, and eleventh centuries. There are so few details of pre-Norman Celtic buildings¹

¹ The sculptured architectural details of the Round Towers and early churches in Ireland and Scotland consist chiefly of crosses or crucifixes over the doorways and terminal heads.


which afford examples of ornamental sculpture that they are hardly worth considering, so that we need only take cognisance of the sepulchral and other monuments. These are of the following different kinds:—

- (1) Recumbent cross-slabs.
- (2) Recumbent hog-backed and coped stones.
- (3) Erect cross-slabs.
- (4) Erect wheel-crosses.
- (5) Erect free-standing crosses.
- (6) Erect pillar crosses, with shafts of round or square cross-section.

The recumbent cross-slabs are confined almost exclusively to Ireland, although there are one or two in Cornwall, Wales, and Scotland. Much the largest collection is at Clonmacnois, King's Co., where there are not far short of 200 sepulchral cross-slabs with inscriptions in Irish minuscule letters, giving the name of the deceased and requesting a prayer for his or her soul. A considerable number of the names on the slabs have been identified on sufficiently satisfactory evidence, thus giving reliable dates for a series arranged in chronological order. Clonmacnois was founded by St. Ciaran in A.D. 554, but the greater part of the dated cross-slabs belong to the ninth, tenth, and eleventh centuries. The earliest of these inscribed cross-slabs which exhibits any decorative features is that of Tuathgal,¹ who has been identified with the seventh abbot of Clonmacnois. The death of abbot Tuathgal took place in A.D. 806. There are, therefore, no ornamental cross-slabs at Clonmacnois older than the beginning of the ninth century. The best ex-

¹ Petrie's *Christian Inscriptions in the Irish Language*, vol. i., pl. 12, No. 29.

amples of recumbent cross-slabs with Celtic ornament in Ireland to which reliable dates can be assigned are those of Suibine McMailæhumai¹ at Clonmacnois (A.D. 887), and St. Berechtir² at Tullylease, Co. Cork.



Cross-slab from Pen-Arthur, Pembrokeshire
Now in St. David's Cathedral. Scale $\frac{1}{4}$ linear

The latter is specially interesting as having upon it a combination of interlaced-work, key-patterns, and spiral ornament.

¹ *Ibid.*, vol. i., pl. 31, No. 82.

² *Ibid.*, vol. ii., pl. 30.

Outside the limits of Ireland there are slabs of the same type, but of unknown date, at Camborne,¹ Cornwall; Pen Arthur² (now in St. David's Cathedral), Pembrokeshire; and Baglan,³ Glamorganshire.

The recumbent hog-backed or coped stones are more likely to be of Anglian or Scandinavian origin than Celtic. They are most common in the north of England; there are one or two in Wales, and none in Ireland. As instances of coped stones with Celtic ornament we have those at Meigle,⁴ Perthshire; and Lanivet,⁵ Cornwall.

The erect cross-slabs are, with a few unimportant exceptions, peculiar to Scotland and the Isle of Man. They are probably older than the free-standing crosses, because the erect cross-slabs are not treated architecturally (as the high crosses of Ireland are), but resemble more nearly than anything else ornamental pages from the Celtic illuminated MSS. directly transferred to stone with hardly any modification whatever to suit the requirements of the new material to which the decoration was applied. A particularly good instance of this is afforded by the erect cross-slab at Nigg,⁶ Ross-shire. On one side of the monument is a cross with the ornament arranged in rectangular panels exactly as it is in the cross-pages of the Irish Gospels; and on the other a figure subject (David and the Lion) surrounded by a frame, also divided into panels, as in those of the miniatures in the Book of Kells.

¹ *Archæologia Cambrensis*, ser. 5, vol. vi., p. 357.


² Prof. J. O. Westwood's *Lapidarium Walliæ*, pl. 60.

³ *Ibid.*, pl. 14.

⁴ Dr. J. Stuart's *Sculptured Stones of Scotland*, vol. ii., pl. 131.

⁵ A. G. Langdon's *Old Cornish Crosses*, p. 412.

⁶ Dr. J. Stuart's *Sculptured Stones of Scotland*, vol. i., p. 28. See also casts in the South Kensington and Edinburgh Museums.



Erect Cross-Slab at St. Madoes, Perthshire

Scale $\frac{1}{2}$ linear

The following is a list of some of the best specimens of erect cross-slabs in Scotland :—

NORTHERN PICT-LAND

Papil (now at Edinburgh)	Shetland.
Ulbster (now at Thurso)	Caithness.
Farr	Sutherland.
Golspie	”
Hilton of Cadboll (now at Inver-		
gordon)	Ross-shire.
Nigg	”
Rosemarkie	”
Shandwick	”
Brodie	Elginshire.
Forres	”
Aboyne	Aberdeenshire.
Dyce	”
The Maiden Stone	”
Migvie	”

SOUTHERN PICT-LAND

Aberlemno	Forfarshire.
Cossins	”
Farnell	”
Glamis	”
Inchbrayock (now at Montrose)	”
Invergowrie	”
Monifieth (now at Edinburgh)	”
St. Vigean	”
Woodray (now at Abbotsford)	”
St. Madoes	Perthshire.
Meigle	”
Rossie Priory	”
Dunfallandy	”

DALRIADIC SCOTLAND

Ardchattan	Argyllshire.
------------	-----------	--------------



**ERECT CROSS-SLAB IN ABERLEMNO CHURCHYARD,
FORFARSHIRE**

John Patrick of Edinburgh, photo.



Front



Back

Cross at Penmon, Anglesey

Drawn by Harold Hughes

Scale $\frac{1}{4}$ linear

The erect cross-slabs of the Isle of Man show a mixture of Celtic and Scandinavian art, but there are a few which appear to be purely Celtic, as, for instance, those at Kirk Maughold¹ (on the village green) and at Kirk Bride.²

The erect free-standing cross seems to have been evolved from the erect cross-slab by removing one part of the background of the cross after another, until at last nothing but the cross itself was left. We see the first stage in the Pupil stone from Shetland, now in the Edinburgh Museum of Antiquities. Here the top of the slab is rounded to suit the curve of the circle, within which the head of the cross is enclosed. The wheel-cross comes next, in which the portion of the background of the cross on each side of the shaft is dispensed with, as in the specimens at Margam³ and Llantwit Major,⁴ both in Glamorganshire. Then the ends of the arms of the cross are allowed to project beyond the circular ring, as at Penmon,⁵ Anglesey. Lastly, the portions of the background of the cross between the quadrants of the ring and the arms are pierced right through the slab, thus giving us the "four-hole" cross of Cornwall⁶ and the typical High Cross of Ireland.⁷

We have used the term "wheel-cross" to describe the class of monuments with a round head and a shaft of less width than the diameter of the head rather because it is convenient than on account of its appro-

¹ J. G. Cumming's *Runic Remains of the Isle of Man*.

² *Ibid.*

³ Prof. J. O. Westwood's *Lapidarium Walliæ*, pl. 15.

⁴ *Ibid.*, pl. 5.

⁵ *Ibid.*, pl. 84.

⁶ A. G. Langdon's *Old Cornish Crosses*.

⁷ H. O'Neill's *Ancient Crosses of Ireland*.



Great Wheel-Cross of Conbelin at Margam Abbey, Glamorganshire
Drawn by Worthington G. Smith
Scale $\frac{1}{4}$ linear

priateness. Perhaps "disc-cross" would be more accurate, but in order to avoid confusion it may be as well to adhere to the term "wheel-cross," which has been adopted by previous writers on the subject.

The wheel-crosses are peculiar to Wales, Cornwall, and the Isle of Man, there being none either in Ireland or Scotland. The wheel-crosses of Wales and the Isle of Man have round heads of large diameter and very short shafts; those of Cornwall have heads of much smaller diameter with a taller shaft. The best examples of wheel-crosses are at Margam and Llantwit Major, Glamorganshire; and at Kirk Braddan and Lonan, Isle of Man.


The free-standing crosses, in which the outline of the stone corresponds with the outline of the cross, are the most highly developed type of Celtic sculptured monument of the Christian period, and are therefore presumably the latest, with the exception of those of the decadent period just before and after the Norman Conquest. The free-standing crosses show the influence of the architect rather than that of the monkish scribe who embellished the early Irish and Hiberno-Saxon illuminated MSS. The sculpture is less flat, and the mouldings round the panels of ornament are more elaborate than on the earlier erect cross-slabs.

The free-standing crosses also, instead of being monolithic, are constructed of two or more separate pieces of stone fixed together by means of mortice and tenon joints. In the larger of the High Crosses of Ireland the base forms one block, the shaft another, the head a third, and sometimes the top arm a fourth.

The High Crosses of Ireland are in most cases associated with a characteristic set of ecclesiastical



Front



Back

Cross at Neuadd Siarman, near Builth, Brecknockshire

Scale $\frac{1}{2}$ linear

structures consisting of a Round Tower and several small churches. This class of monument consequently belongs to the time when the artistic talents of the Celtic monks, which had been previously entirely absorbed in illuminating MSS., was directed into the new channel of architecture. The High Cross of Muiredach¹ at Monasterboice, Co. Louth, and that of King Fland² at Clonmacnois, King's Co., are proved by the inscriptions upon them to have been erected during the first quarter of the tenth century. There is such a general family likeness between most of the High Crosses of Ireland that they are probably all of about the same date.

There is a peculiarity in the design of some of the High Crosses of Ireland which should not pass unnoticed, namely, the semicircular projection in each of the four hollows between the arms.³ In a stone cross these projections have no use or meaning, but in the metal crosses of the same period projections of this kind serve to disguise the rivets by means of which the metal plates on each side of the cross are held together.⁴ From this it would appear that the art of the worker in metal to some extent influenced the sculptors by whom the stone crosses were made.

Some of the Cornish crosses have triangular projections in a similar position, giving an appearance not unlike the cusping in Gothic window tracery.


The free-standing crosses of Wales and Cornwall differ from those of Ireland in having heads of much

¹ Petrie's *Christian Inscriptions in the Irish Language*, vol. ii., p. 66.

² *Ibid.*, vol. i., p. 43.

³ As on the crosses at Monasterboice, Co. Louth, and Durrow, King's Co.

⁴ As on the Cross of Cong in the Dublin Museum, and on the pectoral cross of St. Cuthbert in the Library of Durham Cathedral.



Cross at Nevern, Pembrokeshire

Scale $\frac{1}{4}$ linear

smaller diameter in proportion to the height of the shaft, and bases are the exception rather than the rule. In the Welsh and Cornish crosses figure sculpture is made altogether subordinate to ornament, whilst in the Irish crosses exactly the reverse is the case. The fronts and backs of the Irish crosses, and sometimes the sides also, are entirely covered with panels of symbolical figure subjects forming a cycle, which does not occur in the illuminated MSS., although evidently borrowed from a Byzantine source. The subordination of ornament to figure subjects on the Irish crosses shows that they are further removed from the MSS. than the Welsh, Cornish, and Scottish crosses, and therefore of later date. The free-standing crosses of Scotland seem to belong to the Irish group.

The following list gives the best examples of free-standing crosses :—

IRELAND

Kells	Co. Meath.
Monasterboice	Co. Louth.
Termonfechin	Co. Louth.
Clonmacnois	King's Co.
Durrow	King's Co.
Castle Dermot	Co. Kildare.
Moone Abbey	Co. Kildare.
Kilkispeen	Co. Kilkenny.
Kilfenora	Co. Clare.
Drumcliff	Co. Sligo.

SCOTLAND

Iona	Argyllshire.
Kildalton	Islay.
Barrochan	Renfrewshire.
Dupplin	Perthshire.

WALES

Penmon	Anglesey.
Maen Achyfan	Flintshire.
Neuadd Siarman	Brecknockshire.
Llanbadarn Fawr	Cardiganshire.
Llantwit Major	Glamorganshire.
Margam	”
Carew	Pembrokeshire.
Nevern	”
Penally	”

The shafts of the erect free-standing crosses which have just been described are rectangular in section, but there are a few exceptional monuments with shafts of square section or of round section, or partly of square and partly of round section. As an instance of a cross of square section we have the one at Llandough, Glamorganshire. At Llantwit Major, in the same county, is a cylindrical pillar with a vertical groove down one side of it, the use of which has caused much futile speculation amongst antiquaries. The pillar of Eliseg at Valle Crucis, Denbighshire, is round at the bottom and square at the top, thus corresponding in shape to a well-known type of monument which is common in Mercia. These round pillar crosses usually occur in pairs.

There are a few unique monuments that cannot be classed with any of those already described, such as the ornamented stone coffin at Govan, Renfrewshire, and the altar tomb at St. Andrews, Fifeshire.

Descriptions and illustrations of nearly all the monuments mentioned will be found in Dr. J. Stuart's *Sculptured Stones of Scotland* (published by the Spalding Club of Aberdeen); Dr. J. Anderson and J. R. Allen's *Early Christian Monuments of Scotland*

(published by the Society of Antiquaries of Scotland); R. C. Graham's *Carved Stones of Islay*; H. O'Neill's *Sculptured Crosses of Ancient Ireland*; Dr. Petrie's *Christian Inscriptions in the Irish Language* (published by the R. Soc. Ant. of Ireland); Miss M. Stokes' *Early Christian Art in Ireland*; Prof. J. O. Westwood's *Lapidarium Walliæ*; A. G. Langdon's *Old Cornish Crosses*; J. G. Cumming's *Runic Remains of the Isle of Man*.

The Celtic metalwork of the Christian period may be arranged under the following heads:—

Bells.	Book shrines.
Crozier.	Relic shrines.
Chalices.	Plaques for book-covers.
Processional crosses.	Penannular brooches.
Bell shrines.	Hammer-headed pins.

v With a few exceptions all the existing specimens are now preserved in the Museum of the Royal Irish Academy in Dublin, the National Museum of Antiquities of Scotland in Edinburgh, and the British Museum in London.

Ecclesiastical bells are of two different kinds, namely, (1) *portable* bells, sufficiently light to be carried in the hand; and (2) *fixed* bells, whose weight renders a trussed framework of wood necessary for their support. Each kind of bell can be rung in two separate ways, namely, (1) by holding the bell stationary and striking it on the outside with a hammer; or (2) by providing the bell with a tongue, or clapper, suspended from the inside and swinging the bell backwards and forwards, so as to cause the clapper to strike against the interior and thus produce sound. The method of bell-ringing by means of a hammer is frequently illustrated in the

illuminated psalters of the thirteenth and fourteenth centuries, and is also to be seen on the sculptured capitals in the Abbey of St. George's de Boscherville,¹ in Normandy. The great bells of the Kremlin at Moscow, and in other Greek churches throughout Russia, are rung in this fashion. Portable bells with clappers have a handle at the top, by which they can be swung backwards and forwards in the hand, in the manner depicted upon the Bayeux Tapestry.² Fixed bells with clappers have loops at the top for suspension by iron bands to a horizontal wooden axle or rocking bar working in bearings supported on a trussed framework of timber, usually within a masonry tower. The required rocking motion is given by a lever and rope or a grooved wheel and rope.

The bells used in the Celtic Church seem to have belonged exclusively to the class of portable bells rung by hand. During the earlier period of Christianity in Ireland, when the monks lived together in small isolated communities, bells which were intended to carry sound to a great distance would be unnecessary, so that the absence of belfries in connection with the primitive dry-built stone oratories of the sixth and seventh centuries is easily explained. When, however, at a later period, the congregations became larger and more widely scattered, the lofty tower served a useful purpose in greatly increasing the area over which the sound of the bell could be heard.

The commencement of the building of belfries in Ireland coincides with the introduction of Lombardo-Byzantine architecture into that country, and the Irish round tower is obviously nothing more than a local

¹ Didron's *Annales Archéologiques*, vol. vi., p. 315.

² F. R. Fowke's *Bayeux Tapestry*, pl. 31.

variety of the Italian campanile. The Viking invasions at the same time gave an additional impetus to the erection of structures which could be used not only for ecclesiastical purposes, but also as watch-towers to detect the approach of the enemy, as bell-towers to alarm the neighbourhood, and as towers of defence to secure the lives and property of the congregation. The fact that the Irish round towers are called by the name of *cloicthech*, or bell-house, in the ancient annals is sufficient proof they were used as belfries, but it does not appear to be known whether the bells were rung by swinging in the hand or fixed to a framework and swung on pivots. At any rate, no Irish bells of this period (A.D. 800 to 1000) have survived except the portable hand-bells. If any mechanical appliance was employed for bell-ringing in the Irish round towers it was probably constructed by fixing an ordinary hand-bell to a horizontal axle-bar of wood or iron, working in two bearings, and swung backwards and forwards by means of a rocking lever with a rope attached to it, as is done in many village churches at the present day. The large, heavy metal bells made specially with a view to being fixed in a tower and rung by a grooved wheel and cord belong to a much later period, after the Norman Conquest, when the art of making castings in bronze of great size had been learnt.

The portable bell of the early Celtic Church is merely an ordinary cattle bell,¹ such as would, no doubt, be common in Pagan times, adapted to ecclesiastical purposes and slightly modified to suit the requirements of the monks. It differs hardly at all, except as regards size, from the common sheep-bell

¹ Probably the earliest representation of a cow-bell in Great Britain is on the pre-Norman cross at Fowlis Wester, near Crieff, Perthshire.

still to be found in many parts of England. Dr. Joseph Anderson tersely sums up the peculiarities of the Celtic ecclesiastical bell, as regards its material, manufacture, form, and size, in his *Scotland in Early Christian Times* (first series), p. 183, somewhat as follows:—

- (1) *Material*—iron coated with bronze.
- (2) *Manufacture*—hammered and riveted; coating of bronze put on by means of a process analogous to tinning.
- (3) *Form*—tall, narrow, tapering, foursided; ends flattened; sides bulged.
- (4) *Size*—portable; provided with handle so as to be easily swung by hand.

The original home of ecclesiastical bells of this type was in Ireland, where there are still the greatest number in existence, and thence they spread to Scotland, Wales, England, Brittany, France, and Switzerland.

The largest iron bell of this kind is preserved in the Church of Birnie, near Elgin, N.B. It is 1 foot 2 inches high, and 7 inches by 5 inches at the bottom, tapering to 4½ inches by 3 inches at the top. It is riveted down each of the narrow sides with four rivets, and the handle is fixed to the top by four much smaller rivets. As a rule, however, the height of such bells rarely exceeds 1 foot or is less than 8 inches.

The Celtic ecclesiastical bell of wrought-iron was afterwards copied in cast bronze. It is reasonable to suppose that the bronze bells are of later date than those of iron (1) because the rectangular shape is useless and meaningless in the case of a bronze bell, and results from copying an iron bell, in which the rectangular shape is necessitated by its method of construction; (2) because the bronze bells are of more refined shape

and better manufacture than those of iron ; and (3) because the bronze bells are in many cases ornamented.

Celtic ecclesiastical bells of cast bronze may be divided into the following classes :—

- (1) Bronze bells without ornament.
- (2) Bronze bells without ornament, but inscribed.
- (3) Bronze bells with ornamented handles.
- (4) Bronze bells with ornamented bodies.

Examples of Celtic quadrangular bells of cast bronze without ornament have been recorded at the following places :—

WALES—

Llanrhyddlad, Anglesey (*Archæologia Cambrensis*, 4th ser., vol. ii., p. 275).

Llangystenyn, Carnarvonshire ; now in the Powysland Museum at Welshpool (*Montgomeryshire Collections*, vol. xxv., p. 327).

SCOTLAND—

Eilean Finan, Loch Shiel, Argyllshire (Dr. J. Anderson's *Scotland in Early Christian Times*, 1st ser., p. 198).

Insh, near Kingussie, Inverness-shire (*Ibid.*, p. 195).

Little Dunkeld, Perthshire (*Proc. Soc. Ant. Scot.*, vol. xxiii., p. 119).

Forteviot, Perthshire (*Ibid.*, vol. xxvi., p. 434).

IRELAND—

Garton, Co. Donegal (Rev. H. T. Ellacombe's *Church Bells of Devon—Supplement*, p. 342).

Lower Badony, Co. Tyrone (*Ibid.*, p. 344).

Scattery Island, Co. Clare ; now in the British Museum (*Ibid.*, p. 344).

Kilbroney, Rostrevor, Co. Down (R. Welch, photo. No. 1,932 ; *Jour. R. Soc. Ant. of Ireland*, vol. xxxiii., p. 55).

Kilmainham (*Jour. R. Soc. Ant. of Ireland*, 5th ser., vol. x., p. 41).

IRELAND—

Cappagh, Co. Tyrone (*Jour. R. Soc. Ant. of Ireland*, vol. xxxiii., p. 52).

Drumragh, Co. Tyrone (*Ibid.*, vol. xxxiii., p. 54).

FRANCE—

Goulien, Finistère (*Ibid.*, 5th ser., vol. viii., p. 167).

As has already been pointed out, the bells of cast bronze are copies in another material of the wrought-iron bells, the quadrangular form of which had its origin in the method of construction out of a thin sheet of metal with riveted joints being still adhered to in the bronze bell, where joints were not required. The only difference in the shape of the iron and the bronze bells is that the latter have in most cases a flange, or an expansion and thickening of the metal round the mouth. The handles vary from those which are almost rectangular to those which are quite round. The bell still preserved in the church at Insh, near Kingussie, Inverness-shire, may be taken as a fair sample of the Celtic quadrangular bell of cast bronze without ornament. It is 10 inches high, and measures 9 inches by $7\frac{1}{4}$ inches at the mouth. The handle is oval and the mouth expanded. The remaining bells of the same class vary from 4 inches to 11 inches in height, with their other dimensions in proportion.

There are three Celtic quadrangular bells of cast bronze without ornament, but inscribed, at the following places:—

IRELAND—

Clogher, Co. Tyrone (H. T. Ellacombe's *Church Bells of Devon—Supplement*, p. 369).

Armagh; now in the Museum of the R.I.A. at Dublin (M. Stokes' *Early Christian Art in Ireland*, p. 65).

BRITTANY—

Stival (*Mémoires de l'Institut Impériale de France; Académie des Inscriptions et Belles-Lettres*, vol. xxiv., pt. ii., p. 387).

The bell of Clogher is inscribed, in one horizontal line, with Roman capital letters—

PATRICI

The bell of Armagh is inscribed, in three horizontal lines, with Hiberno-Saxon minuscules—

✠ oroit ar chu
mascach m̄
ailello

“✠ A prayer for Cumascach, son of Ailell.”

The bell of Stival is inscribed, in one vertical line, with Carlovingian minuscules—

pirtur ficifti
“Pirtur made this” (?).

Or, according to the Vicomte Hersart de la Villemarqué:

pir turfic is ti
“Sweet-sounding art thou.”

The Cumascach mentioned on the bell of Armagh was probably the steward of Armagh, who, according to the *Annals of the Four Masters*, died in A.D. 904, thus fixing the date of at least one of the bells of this class.

Celtic quadrangular bells of cast bronze with ornamented handles exist at the following places:—

WALES—

Llangwynodl, Carnarvonshire; now in the possession of W. C. Yale-Jones-Parry, Esq., of Madryn Castle, Pwllheli, Carnarvonshire (*Archæologia Cambrensis*, 1st ser., vol. iv., p. 167; and 4th ser., vol. ii., p. 274).

SCOTLAND—

Strathfillan (Bell of St. Fillan), Perthshire ; now in the National Museum at Edinburgh (Dr. J. Anderson's *Scotland in Early Christian Times*, 1st ser., p. 186).

IRELAND—

Lorrha (Bell of St. Ruadhan), Co. Tipperary ; now in the British Museum (H. T. Ellacombe's *Church Bells of Devon—Supplement*, p. 344).

FRANCE—

St. Pol de Léon (Bell of St. Meriadec) (Rohault de Fleury's *La Messe*, vol. vi., pl. CDXVIII. ; Ellacombe, p. 383).

The ornament on the handles is of two kinds—zoömorphic and phyllomorphic. The former consists of the head of a beast at each end of the loop handle where it joins the body of the bell, and the latter of a leaf in the same position. The bell of Llangwynodl¹ has a good typical example of a zoömorphic handle, and the bell of St. Pol de Léon is the only one with leaf terminations to the handle. The Llangwynodl bell is 5 inches high, and measures 6½ inches by 4 inches across the mouth ; and the St. Pol de Léon bell is 9½ inches high, and measures 6½ inches across the mouth. St. Fillan's bell is 1 foot high, and St. Ruadhan's bell only 2 inches or 3 inches high.

Celtic quadrangular bells of cast bronze with ornamented bodies exist at the following places :—

IRELAND—

Lough Lene Castle, Co. Westmeath ; now in the Museum of the R.I.A. at Dublin ; Bangor, Co. Down (*Ulster Journal of Archæology*, vol. i., p. 179 ; Ellacombe, p. 340). Cashel ; now at Adare Manor (Lady Dunraven's *Memorials of Adare Manor*, p. 152 ; Ellacombe, p. 340).

¹ We are indebted to Mr. W. Corbet Yale-Jones-Parry, of Madryn Castle, Pwllheli, the present owner of the Bell, for permission to reproduce the photograph.

By the courtesy of Mr. George Coffey, M.R.I.A., of the Museum of the Royal Irish Academy, we are able to illustrate the bell from Lough Lene Castle.

It is 1 foot $1\frac{1}{4}$ inches high, including the handle, and measures $8\frac{1}{8}$ inches by $7\frac{1}{4}$ inches across the mouth. The shape of the body of the bell resembles that of the iron quadrangular bells, but exhibits much greater refinement in the delicate and almost imperceptible curves of the sides. The handle is semicircular. The cross of the well-known Irish type, with a border of key pattern below, round the mouth of the bell, on one of the border faces; and a border of angular interlaced-work in a similar position on each of the narrower faces.

The bell of Bangor was found at the place of that name, in Co. Louth, and was subsequently in the possession of Dr. Stephenson, of Belfast. It now belongs to Colonel MacCance, of Knocknagoney House, Holywood, Co. Down.¹ It is 1 foot $2\frac{1}{2}$ inches high, and measures 9 inches by 8 inches across the mouth.

This bell is also ornamented with a cross and key patterns, like the one just described, the only difference being that the cross is not combined with a circular ring, and the design of the key pattern is not quite the same.

The bell of Cashel was found at the place of that name, in Co. Tipperary, in 1849, and is now preserved at Lord Dunraven's house at Adare Manor, Co. Limerick. It resembles the bell of Bangor almost exactly, except that there are four round dots in the

¹ Mr. R. Welch, of Belfast, tells me that it is kept in a fire-proof safe, and that over £300 was refused for it.



**BRONZE BELL WITH ENGRAVED ORNAMENT FROM LOUGH
LENE CASTLE, CO. WESTMEATH, IN THE MUSEUM
OF THE ROYAL IRISH ACADEMY**

hollows between the arms of the cross. The handle is broken off, and without this the bell is 1 foot high. Its dimensions across the mouth are $9\frac{1}{2}$ inches by $6\frac{1}{4}$ inches.

These three bells are so nearly alike as regards their size, shape, and ornamentation that they are probably all the same date, and may even have been the work of one artificer in metal. A peculiarity occurs in the key patterns on the bells from Lough Lene Castle and from Bangor which may perhaps help to fix the date. It will be noticed that the square spaces in the middle of the key patterns are filled in with an almond-shaped figure. This is also a feature of the key patterns in the Irish Gospels (Codex No. 51) at St. Gall, in Switzerland.¹

There is in the British Museum a Celtic quadrangular bell of iron with an ornamental bronze cap fixed to the top of it, but it is not clear whether the cap forms part of the original design or was added subsequently. This bell is called the Bell of Conall Gael, and came from Inishkeel, in the Barony of Boyle, Co. Donegal. It was enclosed within a metal shrine in the fifteenth century.

All the other Celtic ecclesiastical bells which have been enshrined are entirely of iron, a fact tending to show that the bronze bells are of later date than the iron ones, because the enshrined bells were those belonging as a general rule to the saint who founded the church. The bronze bells probably came into use long after most of the older churches had been founded.

¹ R. Purton Cooper's Appendix A to Rymer's *Fœdera*, p. 90 and pl. 7 (St. Mark miniature), and pl. 10 (initial page of St. John's Gospel).

It may be interesting to give a list of the bell-shrines still in existence :—

IRELAND—

Shrine of the Bell of St. Patrick's Will; now in the Museum of the R.I.A. at Dublin (H. O'Neill's *Fine Arts of Ancient Ireland*, p. 46).

Shrine of the Bell of St. Culan, called the *Barnaan Cuilaun*; now in the British Museum (*Transactions of the Royal Irish Academy*, vol. xiv., p. 31).

Shrine of the Bell of St. Mogue.

Shrine of the Bell of Maelbrigde (Miss M. Stokes' *Early Christian Art in Ireland*, p. 67).

Shrine of the Bell of St. Mura, from the Abbey of Fahan, Co. Donegal (*Ulster Journal of Archæology*, vol. i., p. 274).

Shrine of the Bell of Conall Gael, from Inishkeel, Co. Donegal; now in the British Museum (H. T. Ellacombe's *Church Bells of Devon—Supplement*, p. 365).

SCOTLAND—

Bell-shrine of Kilmichael Glassary, Argyllshire, dug up on Torrebhlaurn Farm in 1814; now in the National Museum at Edinburgh (Dr. J. Anderson's *Scotland in Early Christian Times*, 1st ser., p. 207).

Bell-shrine, preserved at Guthrie Castle, Forfarshire (*Ibid.*, p. 209).

The bells of the Celtic Church, whether they be of iron or bronze, whether devoid of lettering or inscribed, ornamented or plain, possess a far higher interest than that attaching to ordinary museum specimens, because most of them have an authentic history, going back in some cases to the time when Christianity was first introduced into this country. The bell, the book, and the crozier which belonged to the Celtic saints who founded churches, were always looked upon



THE SHRINE OF THE BELL OF ST. PATRICK'S WILL IN THE
MUSEUM OF THE ROYAL IRISH ACADEMY, DUBLIN

A.D. 1091 TO 1105

with the highest veneration, and were used for a variety of superstitious purposes, such as healing the sick, procuring victory in battle, and the solemnising of oaths. The relics of the saints of the fifth, sixth, and seventh centuries were enclosed in costly metal shrines, generally a few hundred years after the death of the saint, and an hereditary keeper was appointed to be responsible for the safety of the relics when borrowed for effecting cures and other purposes. The shrines and their contents were thus handed down from generation to generation, and in most cases sold by their last hereditary keepers to collectors of antiquities, from whom they were acquired by the national museums of England, Scotland, and Ireland. The relics still bear the names of the saints to whom they originally belonged; the names of their hereditary keepers are well known, and they have been obtained from the localities where the saint founded his church, and where the relics remained for centuries afterwards undisturbed. No class of antiquities, therefore, possesses a better record or a more satisfactory pedigree.

The Irish and Scottish bell-shrines which have been enumerated are cases of metal of the same shape as the bell they contain, having four sloping sides and an arched top. The sides are usually made of bronze plates ornamented with gold, silver, enamel, and settings of crystal and precious stones. Two features which are characteristic of the ornamental bronze bells are repeated in the shrines, namely, the zoö-morphic terminations of the handles and the cross on the body of the bell. In the two Scottish bell-shrines the Crucifixion takes the place of the Cross. The ornament on the bell-shrines is much further removed in style from that of the illuminated MSS. than is the

case with the sculptured stones. This is only what might be expected, considering the late date of the bell-shrines as compared with that of the crosses. On two of the bell-shrines Scandinavian influence may be clearly detected in the ornament upon them. Thus on the Shrine of the Bell of St. Patrick's Will the pear-shaped eyes of the beast's heads on each side of the arched top are placed with the point outwards in the Scandinavian fashion; and on the Shrine of the Bell of St. Mura the "tendril pattern," which is so common on the Rune-inscribed monuments of the Isle of Man, may be noticed.

The dates of three of the bell-shrines have been ascertained by means of the inscriptions upon them, namely, Maelbrigde's Bell-shrine, *circa* A.D. 954; the Shrine of the Bell of St. Patrick's Will, A.D. 1091 to 1105; and the Guthrie Bell-shrine, 14th century. Judging merely from the style of the ornament, the Shrine of the Bell of St. Culanus should be of the twelfth century, and the Shrines of the Bell of St. Mura and of Kilmichael Glassary perhaps as late as the beginning of the thirteenth century.

The metal croziers of the Celtic Church are in reality shrines enclosing the wooden pastoral staffs of the different saints, whose names most of them still bear. The chief peculiarity of the Celtic crozier is the shape of the head, which is like the hook of a modern walking-stick, but with a remarkable flattened end. The inside curve of the hook is nearly circular, but the outside curve is only partially semicircular, and suddenly changes to a nearly vertical straight line just before the end of the crook is reached. At the bottom of the crozier is a pointed ferrule, and the straight portion consists of two cylindrical tubes of



HEAD OF THE LISMORE CROZIER AT LISMORE CASTLE,
CO. WATERFORD
A.D. 1090 TO 1113

thin metal joined together in the middle by a bulbous collar. The upper tube is joined to the head at the top by a similar bulbous collar, and the lower tube is joined to the ferrule at the bottom by a third bulbous collar.

One of the most perfect of the Irish crozers is preserved at Lismore Castle,¹ Co. Waterford. It bears an inscription showing that it was made by Nectan, the artisan, for Niall, son of MacAeducain. Mac Mic Aeducain was Bishop of Lismore from A.D. 1090 to 1113. Another fine crozier in the British Museum² has an inscription asking a prayer for Maelfinnia and Condulig. The former was Bishop of Kells, and died in A.D. 967. Condulig was an ecclesiastic of the same monastery, and died in A.D. 1047.

The best examples of uninscribed croziers are the croziers of Clonmacnois³ and of St. Berach in the Museum of the Royal Irish Academy in Dublin, and a crozier now in the possession of the Roman Catholic Bishop of Killarney. Besides the complete croziers mentioned there are several heads and other portions of croziers in the Museum of the Royal Irish Academy, and in the Edinburgh Museum of Antiquities may be seen the head of the crozier of St. Fillan,⁴ which has an unusually interesting history.

The decoration of the Celtic croziers is concentrated on the head, the ferrule, and the collars round the straight portion of the staff. Most of the croziers have a zoöomorphic cresting⁵ on the outside curve of the head, sometimes consisting of a procession of

¹ Petrie's *Christian Inscriptions in the Irish Language*, vol. ii., p. 118; and H. O'Neill's *Fine Arts of Ancient Ireland*, p. 42.

² Petrie's *Christian Inscriptions in the Irish Language*, vol. ii., p. 116.

³ Miss M. Stokes' *Early Christian Art in Ireland*, p. 105.

⁴ Dr. J. Anderson's *Scotland in Early Christian Times*, 1st ser., p. 219.

⁵ As on the croziers of Lismore, Clonmacnois, and Dysert.

beasts one behind the other, and sometimes only having terminal beasts' heads at each end.¹ The flat portion of the crook of the crozier at the end is decorated in some cases with the head of the saint or bishop, and a crystal setting below.² Zoömorphism enters very largely into the ornamentation of the Celtic croziers, and the beasts with only two toes instead of three on the Crozier of Clonmacnois obviously betray their Scandinavian origin by this detail. The decoration of the heads of the croziers is treated in at least three different ways: (1) the head of the Lismore crozier is divided into rectangular panels with raised bosses of enamel at the intersections of the bands, which form the divisions between the panels; (2) the heads of the croziers of Dysert, Blathmac, and St. Fillan are divided into lozenge-shaped panels by a sort of raised lattice-work; and (3) the head of the crozier of Clonmacnois is not divided into panels, but the surface entirely covered with zoö-morphic strap-work.

The croziers are all of the eleventh century or later, and their decoration has little in common with that of the early illuminated MSS.

“Cumdachs,” or book-shrines, are peculiar to Ireland. Three MSS. still in existence are known, from historical evidence, to have had cumdachs, although they have been lost.

These are :—

The Book of Durrow enshrined	A.D. 877 to 914.
The Book of Armagh	„ A.D. 938.
The Book of Kells	„ before A.D. 1007.

¹ As on St. Fillan's crozier.

² As on St. Fillan's crozier,

The existing cumdachs are as follows :—

In the Museum of the Royal Irish Academy.

Cumdach of Molaise's Gospels	. A.D. 1001 to 1025.
„ „ the Stowe Missal	. A.D. 1023.
„ „ Columba's Psalter	. A.D. 1084.
„ „ St. Patrick's Gospels.	

In the Library of Trinity College, Dublin.

Cumdach of Dimma's Book	. A.D. 1150.
-------------------------	--------------

The cumdachs are simply rectangular boxes, sufficiently large to hold the MS., made either of wood or bronze and plated with silver. The decoration of the principal face of the cumdach is generally arranged in the form of a cross, the treatment being much the same as in the ornamental pages of the MSS. of the Gospels. The cross on the cumdach of Molaise's Gospels is formed of a flat silver plate with panels pierced right through the thickness of the metal, and filled in with interlaced patterns in filigree-work. The cross in the middle is surrounded by the Symbols of the Four Evangelists, with their names inscribed at the side of each. The centre of the cross and the ends of the four arms are ornamented with settings of crystal.

On one of the narrow faces of this cumdach are some very curious figures of two ecclesiastics, one holding a bell and the other a pastoral staff; and a harper, with an angel above his head, between them.

The cumdach of the Stowe Missal has upon the principal face a cross within a rectangular frame. The centre of the cross is ornamented with a crystal setting, and the recessed panels of the background are filled in with a peculiar kind of triangular and square chequer-work made of pierced metal plates.

✓ The cumdach of Dimma's Book has also on the principal face a cross surrounded by a rectangular frame, and ornamented with thirteen crystal settings. The four recessed panels of the background of the cross are filled in with zoöomorphic designs in the same style as those on the High Cross of Tuam,¹ Co. Galway, which is of about the same period, having been erected in A.D. 1123.

The relic-shrines of the Celtic Church are of two kinds, namely, (1) those made in the shape of the portion of the body of the saint enshrined; and (2) those made in the shape of a small oratory or house with a steep pitched roof having hipped ends. As an example of the first kind we have the Shrine of St. Lachtin's Arm.²

The most beautiful and perfect example of a reliquary in the form of a small oratory is the one now in the possession of Sir Archibald Grant, and preserved at Monymusk House,³ Aberdeenshire. It is a wooden box, hollowed out of the solid, and covered with plates of bronze and silver. It is decorated with enamel, settings of precious stones, and raised circular medallions and rectangular plaques of interlaced-work on a chased background of zoöomorphic designs. Another reliquary of the same kind was found in Lough Erne,⁴ between Enniskillen and Belleek, in 1891, and belongs to Mr. T. Plunkett, of Enniskillen. It is 7 inches long by $3\frac{1}{2}$ inches wide by $5\frac{1}{8}$ inches high, and is made of plates of bronze covering an inner box scooped out of two solid pieces of yew-wood. The decoration,

Now
manuscript.

¹ H. O'Neill's *Sculptured Crosses of Ancient Ireland*, pl. 12.

² *Vetusta Monumenta*, vol. vi., pl. 19.

³ Dr. J. Anderson's *Scotland in Early Christian Times*, 1st ser., p. 249.

⁴ *Journ. R. Soc. Ant. of Ireland*, 5th ser., vol. ii. (1892), p. 349.



CELTIC QUADRANGULAR BELL OF BRONZE WITH ZOÖMORPHIC HANDLES FROM LLANGWYNODL CHURCH, CARNARVONSHIRE; NOW IN THE POSSESSION OF W. CORBET YALE-JONES-PARRY, ESQ., OF MADRYN CASTLE, PŴLLELI

W. Morgan Evans, of Pwllheli, photo.



BRONZE RELIQUARY FROM LCWER LOUGH ERNE; NOW IN THE POSSESSION OF T. PLUNKETT, ESQ., OF ENNISKILLEN

7 INS. LONG BY 5·7-8 INS. HIGH BY 3½ INS. WIDE

R. Welch, of Belfast, photo.

which consists of interlaced-work, is concentrated upon the ridge-piece of the roof; upon a band concealing the joint between the eaves of the roof and the sides; upon six circular raised medallions, one on each of the longest sloping faces of the roof and two on each of the longest sides; and upon the hinges at each end of the box to which the bars for suspending the shrine round the neck of its hereditary keeper were attached. There is a third reliquary, like the two just described, from Norway, in the Copenhagen Museum.¹ It has raised circular medallions arranged in the same way as on the Lough Erne shrine, but they are decorated with spiral designs, and the background, instead of being plain, is covered with elaborate interlaced-work. An inscription in later Runes on this shrine reads "Ranvaig owns this casket." The Edinburgh Museum possesses a fourth shrine of the same class found in the Shannon² in a very dilapidated condition.

Dr. J. Anderson³ has pointed out the identity of the form of the Temple at Jerusalem, as represented in the Book of Kells, with the form of this particular class of reliquary.

The Breac Moedoc,⁴ or shrine of St. Mogue, from Drumlane, now in the Museum of the Royal Irish Academy at Dublin, resembles the reliquaries of the Monymusk type in shape except that the roof is gabled instead of being hipped, and the method of applying the decoration also is entirely different. It is $7\frac{1}{4}$ inches long by $8\frac{1}{8}$ inches wide by $3\frac{1}{2}$ inches wide, and is made of bronze, with decorations of bronze gilt, enamel,

¹ J. J. A. Worsaae's *Nordiske Oldsager i det Kongelige Museum i Kjøbenhavn*, p. 129, Fig. 524.

² Dr. J. Anderson's *Scotland in Early Christian Times*, 1st ser., p. 246.

³ *Ibid.*, p. 247.

⁴ *Archæologia*, vol. xliii., p. 131.

and glass. The front is divided into rectangular panels, each containing a group of figures of male and female saints numbering twenty-one altogether; and on one of the gabled ends is a bearded figure playing a harp on which a bird is perched. The back and bottom of the shrine are ornamented with cruciform patterns in pierced work, as on the shrines of the Bell of St. Patrick's Will, of the Stowe Missal, and of Dimma's Book.

The relic-shrine of St. Manchan¹ differs from all those previously described in being considerably larger, and in being shaped like the gabled roof of a house, but without any house; that is to say, it has two rectangular faces meeting in a horizontal ridge and two nearly vertical triangular ends. It was formerly in the keeping of the ancient Irish family of Mooney, of the Doon, but it is now preserved in the Roman Catholic Church of Boher, in the parish of Lemanaghan, near Clara, King's Co. The Shrine of St. Manchan is 1 foot 11 inches long by 1 foot 1 inch wide by 1 foot 7 inches high. The framework of the shrine is made of yew boards. The front and back are each ornamented with an equal-armed cross having large circular raised bosses in the centre, and on the ends of the four arms. The four spaces forming the background of each of the crosses are filled in with rows of small figures fixed to the bronze plate behind with rivets. The front, back, and two ends of the shrine are partially surrounded by a border of zoömorphie ornament. The bosses in relief of the crosses on the front and back, and the recessed triangular panels on the two ends are also elaborately decorated with zoömorphs. At each of the four corners

¹ *The Reliquary*, vol. xv. (1875), p. 193.

of the base is a circular ring, probably for carrying the shrine about. The clamps of the rings, the borders round the bottom of the shrine, and the narrow parts of the arms of the crosses have step-patterns in red and yellow enamel upon them. The whole of the bronze was originally gilt. The style of the ornament is so similar to that on the Cross of Cong that we shall not be far wrong if we attribute the shrine of St. Manchan to the same period, namely, the twelfth century.

There is only a single example of a processional cross belonging to the Celtic Church now in existence, namely, the Cross of Cong¹ in the Museum of the Royal Irish Academy at Dublin. It is 2 feet 6 inches high by 1 foot 6 $\frac{1}{4}$ inches across the arms by 1 $\frac{3}{4}$ inches thick. The cross is of oak covered with copper plates, and has a boss of rock-crystal in the centre, beneath which the portion of the true cross was enshrined. The outer margin of the cross is formed by a roll moulding of silver, with eighteen small enamelled knobs at intervals to emphasise the cuspings of the outline of the cross. The face of the cross within the margin is divided into two rows of panels by a narrow longitudinal band in the middle of the arms, with enamelled bosses of enamel in relief and circular silver discs alternately marking the points where the cross-bars branch off at right angles to the central stem, so as to divide the surface into panels. The eight panels surrounding the boss of rock-crystal in the centre of the cross are filled in with scrolls of gold filigree-work,

¹ *Proc. R.I.A.*, vol. ii., p. 113, and vol. iv., p. 572; Petrie's *Christian Inscriptions in the Irish Language*, vol. ii., p. 118; Miss M. Stokes' *Early Christian Art in Ireland*, p. 108; and *Journ. R. Soc. Ant. Ireland*, vol. xxxi. (1901), p. 40.

and the remaining thirty-eight panels on the arms and shaft are filled in with zoöomorphic designs in cast bronze gilt, riveted to the copper plates beneath. At the bottom of the cross is a beast's head with a bulbous projection between it and the socket to receive the staff. The bulbous portion is ornamented with small bosses of blue enamel and panels of zoöomorphic designs. The general effect of the whole is extremely rich, and shows great artistic feeling. The prevalence of the zoöomorphic element in the design and the arrangement of the panels reminds us of the croziers of the same period, more especially the one at Lismore Castle, Co. Waterford.

The inscriptions on the Cross of Cong, of which the first is in Latin (twice repeated) and the remaining four in Irish, may be thus rendered in English :—

- (1) "This Cross covers the Cross on which the Saviour of the World suffered."
- (2) "Pray for Murdoch O'Duffy, the Senior of Ireland."
- (3) "Pray for Turloch O'Connor, for the King of Ireland, for whom this shrine was made."
- (4) "Pray for Donnell M'Flannagan O'Duffy, for the Bishop of Connaught, for the successor of Coman and Ciaran, under whose superintendence this shrine was made."
- (5) "Pray for Maeljesu MacBratdan O'Echan, who made this shrine."

Murdoch O'Duffy, Archbishop of Connaught, died in A.D. 1150, and it is recorded in the *Annals of Innisfallen* that in the year 1123 a bit of the true cross came into Ireland and was enshrined by Turlogh O'Connor, thus fixing the date of the Cross of Cong some time in the first half of the twelfth century. The cross was

removed from Tuam to Cong either by Archbishop O'Duffy or King Roderic O'Conor, and was found there in 1839, when it was purchased by Prof. Mac Cullach and presented by him to the Museum of the Royal Irish Academy.

Chalices of earlier date than the Norman Conquest are of extreme rarity either in Great Britain or on the Continent. Perhaps the three most ancient specimens abroad are (1) the chalice, found with gold coins of Justinian (A.D. 508 to 527), at Gourdon,¹ Chalons-sur-Saône, and now in the National Library at Paris; (2) the chalice of Tassilo,² Duke of Bavaria (A.D. 757 to 781), at Kremsmünster in Lower Austria; and (3) the chalice of St. Gozlin³ of Toul (A.D. 922 to 962), now in the treasury of the Cathedral of Nancy. The first and last of these have two handles. The chalice of Tassilo, however, has no handles. It is profusely decorated with interlaced-work, zoöomorphic designs, and figure subjects, and has round the foot the following inscription in capital letters, not unlike those used in the Hiberno-Saxon MSS:—

“ + TASSILO DVX FORTIS LVITPIRC VIRGA REGALIS.”

The lady referred to was Luitberga, wife of Duke Tassilo, and daughter of Desiderius, the last king of the Lombards. The chalice is 10 inches high and is made of copper ornamented with gold, silver, and niello. The figures are placed in oval medallions round the bowl and the base. The principal figure is that of Christ giving the benediction, and the remainder appear to be those of saints. The style of the

¹ De Caumont's *Abécédaire d'Archéologie Architecture Religieuse*, p. 117.

² Dr. R. Munro's *Bosnia-Herzegovina and Dalmatia*, p. 292.

³ De Caumont, *loc. cit.*, p. 118.

decoration resembles that of the Irish metalwork to a certain extent, and the chalice of Tassilo may very possibly have been made abroad under the direction of some Irish monk.

Only one metal chalice of undoubted Irish work has been preserved until the present time, namely, the Ardagh Chalice¹ in the Museum of the Royal Irish Academy at Dublin. It was found in 1868 in a rath in the townland of Reerasta, in the parish of Ardagh, Co. Limerick. The chalice belongs to the two-handled type, and has a hemispherical bowl, a very short cylindrical stem, and a conical base with a flat rim round the bottom. It is 7 inches high by $9\frac{1}{2}$ inches in diameter at the top, and $6\frac{1}{2}$ inches in diameter at the bottom, the bowl being 4 inches deep and of sufficient capacity to hold three pints of liquid. The chalice is composed of gold (1 oz. 2 dwts.), silver (20 ozs. 13 dwts.), bronze (9 ozs.), lead, enamel, glass, amber, and mica. No less than 354 different pieces, including 20 rivets, are used in the construction of the vessel.

The exterior of the bowl of the Ardagh chalice is inscribed with the names of the Twelve Apostles in Hiberno-Saxon capitals, finely engraved on the silver. The forms of the letters correspond with those used in the Books of Kells, Dimma, St. Chad, Durham, and MacRegol.

The raised decoration of the chalice, which is made in separate pieces and fixed on with rivets, is concentrated on the following parts:—

- (1) A horizontal band just below the rim and running through the handles.

¹ Petrie's *Christian Inscriptions in the Irish Language*, vol. ii., p. 123; *Trans. R.I.A.*, vol. xxiv., p. 433; Miss M. Stokes' *Early Christian Art in Ireland*, p. 83.



BRONZE FIBULA WITH PLAITWORK AND LATE-CELTIC
ORNAMENT FROM THE ARDAKILLEN CRANNOG, NEAR
STROKESTOWN, CO. ROSCOMMON ; NOW IN THE MUSEUM
OF THE ROYAL IRISH ACADEMY, DUBLIN



DETAIL OF ORNAMENT ON THE UNDER-SIDE OF THE FOOT
OF THE ARDAGH CHALICE IN THE MUSEUM OF THE
ROYAL IRISH ACADEMY, DUBLIN

- (2) The two handles.
- (3) Two circular medallions on the lower side of the bowl midway between the handles.
- (4) The stem.
- (5) The flat rim at the bottom of the base.
- (6) The under side of the flat rim round the base.
- (7) The circular medallion in the centre of the under side of the conical base.

The ornament consists of interlaced-work, step-patterns, key-patterns, spiralwork, zoömorphic designs, and scrollwork, arranged in panels after the usual Celtic fashion. The step patterns are confined to the plaques and bosses of enamel, and the other patterns are executed in delicate gold filigree-work on a repoussé background of gold. On the under side of the flat rim round the base panels of most beautifully plaited silver wire are introduced. Amber is used on the handles for the borders round the raised bosses of enamel, and there is a narrow ring of the same material between the concentric rings of ornament in the middle of the under side of the base. The heads of the rivets by which the circular medallions on the sides of the bowl are fixed are concealed by two small bosses of blue glass and two of amber. The heads of the rivets for securing the two handles in place are disguised in a similar manner. The stem and supports of the chalice are of bronze gilt, highly ornamented. They are attached to the bowl by a bronze-gilt ball, with a strong square tang, and most ingeniously fastened by an iron bolt which secures all together. A plate of lead is inserted between the upper and under sides of the flat rim round the base to give weight and stability. The flat rim round the base is ornamented with gold and bronze-gilt plaques of open-

work on a background of mica, in order to show up the beauty of the patterns. The flat rim round the base has on its under side, between the panels of ornament, rectangular tablets of blue glass, underneath which are decorated pieces of wrought-silver, which give a brilliant appearance in a strong light. In the centre of the under side of the base is a circular setting of rock-crystal. The rim of the bowl of the chalice is of brass.

Enough has been said of the elaborate nature of the construction and ornamentation of the Ardagh Chalice to show that it is a masterpiece of Celtic art metalwork of the best period. The style of the lettering of the inscription upon it and the general character of the decorative features indicate that it belongs to the same school as the Book of Kells, the Durham Book, St. Chad's Gospels, and the Tara Brooch, and cannot consequently be of much later date than the eighth century. It will be noticed that in the decoration of the Ardagh Chalice spiral patterns of the best quality are present, and that the zoömorphs are kept under proper restraint so as not to swamp the whole design. Both these points are an indication of early date.

There are at least three examples known of bronze plaques with representations upon them of the Crucifixion treated in the archaic Irish fashion. The most interesting of these was found at Athlone,¹ and is now in the Museum of the Irish Academy in Dublin. The Saviour is shown wearing a tunic, the surface of which is almost entirely covered with spirals, key-patterns, and interlaced-work. Another smaller and less ornamental plaque with the Crucifixion may be seen in the

¹ Dr. J. Stuart's *Sculptured Stones of Scotland*, vol. ii., pl. 10.

same museum;¹ and a third, belonging to Mr. M. J. Arketell, has been illustrated by Prof. J. O. Westwood in his *Miniatures and Ornaments of the Anglo-Saxon and Irish MSS.*²

Leaving Celtic ecclesiastical metalwork, we come to personal ornaments, which, although exhibiting the same style of decoration, were not necessarily intended to be worn by persons taking part in the ceremonies of the Church. These personal ornaments consist of pins, brooches, and buckles. We have previously given a list of the hammer-headed pins, which may either be Pagan or Christian. Another peculiarly Celtic type of pin consisted of three parts, namely, (1) a long pin; (2) a kite-shaped pendant; and (3) a short bar hinged at one end to the top of the pin, and at the other to the rounded top of the pendant. A remarkably fine pin of this description was found about 1883 at Clonmacnois,³ King's Co., and is now in the possession of the Rev. Timothy Lee, of Limerick. The pin is $7\frac{1}{2}$ inches long, the coupling-bar $\frac{3}{4}$ inch long, and the kite-shaped pendant $2\frac{1}{2}$ inches long by $1\frac{1}{4}$ inches wide by $\frac{1}{8}$ inch thick. The whole is of silver, decorated with gold filigree, enamel, niello, and settings of claret-coloured glass or precious stone. The coupling-bar has on one side a lozenge-shaped panel of filigree-work, and on the other an interlaced pattern in niello. The front of the pendant is ornamented with a cross having a large rectangular setting of glass in the centre, three smaller rectangular settings at the ends of the top and two side arms, and a small triangular setting at the bottom of the shaft. The background of the cross consists of four panels

¹ *Miniatures*, pl. 51. Fig. 7.

² Pl. 51, Fig. 8.


³ *Journ. R. Soc. Ant. Ireland*, ser. 5, vol. i. (1890-1), p. 318.

of interlaced filigree-work, three of which are missing. The point of the kite-shaped pendant terminates in a beast's head. On the back of the pendant there is a cross of similar shape to that on the front, but with an ornamental border of spiralwork round it, and the whole design executed in niello. At the pointed end at the bottom is fixed a small ring through which passes a silver plaited chain of Trichinopoly-work, like the one attached to the Tara Brooch. There is another pin of similar shape ornamented with zöomorphic designs in the Museum of the Royal Irish Academy,¹ in Dublin.

Dr. Hans Hildebrand, in his excellent South Kensington handbook of *The Industrial Arts of Scandinavia* (p. 21), remarks that "every work of human art, higher as well as lower, has its shape determined by two agents: the end which it is to serve, and the taste of the people and the time of which it is a fruit." In other words, there is a utilitarian as well as an ornamental side to almost every object fashioned by man to satisfy his wants. The form of an object must depend primarily upon the practical use to which it is intended to be put, and the decorative features generally follow afterwards in due course. The function of the decorative features, however, should be to add grace and beauty to the original form of the object, but not to attempt to disguise the utilitarian purpose it fulfils.

No relics of antiquity are more deserving of study than personal ornaments, and of all personal ornaments perhaps the brooch is the most important as affording an insight into the character of the people by whom it was worn. Their ingenuity can be measured by the perfection of the mechanism of the working

¹ R.I.A. photo, A 165.



Pin-brooch from Clonmacnois, King's Co.

Now in the possession of the Rev. Timothy Lee, of Limerick

Drawn by R. Cochrane, F.S.A.

parts, their culture by the refinement of the ornament, and their skill as craftsmen by the finish of the workmanship. Much, again, is to be learnt of the habits of the people by investigating the different methods of wearing the brooch. Thus it is that almost every age and every country possesses its typical form of brooch.

Looked at from its practical side, a brooch is a contrivance for fastening together temporarily any two points on a garment. It is obviously a higher development of the pin. Going back to first principles, the pin may have been suggested by the natural spikes, or thorns, found in the vegetable world. It would not require much intelligence to see that a small knob added to the blunt end of the pin would facilitate its removal from the fabric when it was required to be withdrawn, and would also prevent the pin going further than was desirable through the fabric. The problem which was solved by the invention of the brooch, however, was one of much greater complexity, namely, how to secure the pin in position so as to prevent it from slipping out of the fabric in the direction of the head. This might have been effected either by fixing a removable knob, or stop of some kind, on the pointed end after it had been inserted in the fabric, or by connecting the head with the point temporarily, so as to form a complete ring for the time being. In the brooch the latter alternative is chosen. The pin must necessarily be straight, so as to pierce the fabric with the least amount of resistance, and the temporary connection between the head and the point has to be approximately semicircular, the whole forming a ring shaped like a bow, the pin corresponding to the string and the body of the brooch to the bow.

In order to be able to remove the brooch from the



**SILVER PENANNULAR BROOCH FROM IRELAND;
NOW IN THE BRITISH MUSEUM**

SCALE $\frac{1}{2}$ LINEAR

fabric at pleasure, some contrivance must be hit upon by which a gap, or break, can be made in the ring, and be closed up again whenever it is desired to do so. The opening is attained by placing a hinge where the head of a pin joins the body of the brooch, and the closing by having a groove-shaped catch at the opposite extremity. A spring is also required to prevent the pin coming unfastened accidentally from the catch. These different contrivances constitute the essential parts of a brooch, which, divested of its ornamental appendages, is represented by the ordinary "safety-pin" of the present day.

If the rigid bow-like connection between the head and point of the pin be doubled we get an annular brooch, and if the central portion of the ring be filled in we get the discoidal brooch. In these cases the ring or disc is placed parallel to the plane of the fabric instead of at right angles to it.

The somewhat dry disquisition just inflicted upon the unsuspecting reader is necessary in order to place him in a position to fully understand the mechanism of the typical Celtic brooch, the leading characteristics of which are that the ring has a break in its continuity (whence the name "penannular"), and that the length of the pin considerably exceeds the diameter of the ring. The object of the break in the continuity of the ring is that it enables the spring-catch to be dispensed with, the method of fixing the brooch in the dress being as follows: First, the long pin is inserted in the fabric at two points close together, in such a manner that the apex goes right through it and appears again above the surface; the pin is then forced through the break, and the ring is given a turn through a right angle in the plane of the fabric, thus fixing the brooch

by the friction produced by the drag of the weight of the garment on the pin.

We are now brought face to face with the question as to how the Celtic penannular brooch was worn. This can not only be conjecturally determined by an examination of the specimens to be found in museums, but fortunately can be settled beyond a shadow of a doubt in two ways, each of which confirms the other. First, there are at least two contemporary representations of persons actually wearing a penannular brooch (one on a cross at Monasterboice, Co. Louth, and the other on a cross at Kells, Co. Meath, in Ireland); and this ancient form of fibula has survived, and is in use at the present time in Algeria and elsewhere.

The example at Monasterboice¹ is on the bottom panel of the side of the shaft of the cross of Muiredach (or Murdoch), which was erected in A.D. 924. The scene represented on the panel has been conjectured by the late Prof. J. O. Westwood, from its similarity to a miniature in the Book of Kells at Trinity College, Dublin, to be intended for Christ seized by the Jews. If this be so, the central figure is our Lord, and on each side is a soldier armed with a drawn sword. The sculpture is in good preservation, considering its great age, and the details of the costume, which are very elaborate, can be made out fairly well. Our Lord wears a sort of cloak with a penannular brooch fixed on His right shoulder. The split in the ring of the brooch faces downwards, and the pin is inclined upwards at an angle of about 30 degrees to the horizontal, the point being outwards. Probably the heavy head of the pin is placed downwards because its weight would always tend to bring it to this position, as the

¹ *Illustrated Archaeologist* for 1893, p. 164.



**BISKRA WOMAN WEARING A PAIR OF PENANNULAR BROOCHES,
THE ENDS OF THE PINS POINTING UPWARDS**

one of most stable equilibrium, but it may also have been to avoid injury from the point of the long pin.

The second example is on the bottom panel of the side of the broken cross-shaft in Kells¹ churchyard. The exact date of this monument is unknown, but it is probably of the ninth or tenth century. The subject on the panel is the Baptism of Christ, with the sources of the two imaginary rivers, Jor and Dan, which, when united, were supposed to contribute their waters to the Jordan, indicated conventionally in a most remarkable manner. John the Baptist pours the water over the head of Christ with a sort of ladle. Above is the Holy Dove, and on the left are two figures wearing penannular brooches exactly in the same manner as on the Monasterboice cross, with the pin pointing upwards. In the case of the figure furthest to the left, the end of the long pin is inserted a second time into the fabric of the dress, beyond the ring.

The method of wearing the penannular brooch at the present day in Algeria is clearly indicated on the reproduction of a photograph² here given. The only difference in the way of wearing the brooch in Algeria and in ancient Ireland is, that in the former case they are worn in pairs instead of singly, and there is a connecting chain with a small pendant scent-box hung from the middle. The size of the box is exaggerated out of all proportion by being placed nearer the camera than the rest of the figure.

In Great Britain the penannular brooches appear to have been worn singly, as they are never found in

¹ *Illustrated Archæologist* for 1893, p. 165.

² Obtained from Albert Hauteccœur, 2, Boulevard des Capucines, Paris.

pairs; thus offering a contrast to the Scandinavian bowl-shaped brooches, which are always found in pairs, and were connected by a chain, as in the case of the Algerian brooches.

It would be interesting to know how the penannular form of brooch was first introduced into this country, for it seems hardly conceivable that it could have been invented here, or else it would not be found in Algeria, which never had any connection with Great Britain, it being extremely unlikely that so peculiar a type of brooch was evolved independently in the two countries.

The most probable suggestion is that the Algerians and the ancient Irish got it from a common source, namely, the East, and that its introduction into our own islands dates from the time when the traffic in silver bullion from the East commenced. The existence of a trade route which was made use of by the dealers in silver bullion is made clear by the number of finds of Mahomedan silver coins associated with ingots, rings, and ornaments of silver, made both in Scandinavia and in Great Britain. Dr. Hans Hildebrand, in his *Industrial Arts of Scandinavia* (p. 81), informs us that "considerable stores of such coins, most of them of the Samanid dynasty, have been found in Sweden. It is satisfactorily proved by Russian finds, that these coins were brought from states near the Caspian Sea, through Russia to the shores of the Baltic Sea, and thence to the commerce established by the inhabitants of Gotland over to that island. From Gotland, and probably also by direct intercourse with Russia, the Mahomedan coins were spread over Scandinavia, being of course more common in the eastern provinces of Sweden than in the western and in Norway." No



DETAIL OF ORNAMENT ON THE TARA BROOCH



DETAIL OF ORNAMENT
ON THE TARA BROOCH



DETAIL OF ORNAMENT
ON THE TARA BROOCH

less than 20,000 Mahomedan silver coins have already been discovered in Sweden, mostly dating between A.D. 880 and 955, the latest belonging to the year A.D. 1010.

Penannular brooches have been found in association with Mahomedan coins of the ninth and tenth centuries, at Skaill, in Orkney; at Storr, in Skye; and at Cuerdale, near Preston, in Lancashire.

Although the general form of the penannular brooch is probably of Eastern origin, the decorative features vary according to the race of people who adopted it. Thus the examples from Algeria have Mahomedan ornament; those from Gotland, Scandinavian patterns; whilst those from Ireland and Scotland are thoroughly Celtic in design. With the decoration of the foreign specimens we are not now concerned, but a few words with regard to the various types found in Great Britain will form a fitting conclusion to this article.

The finest collections of penannular brooches are to be seen in the British Museum, the National Museum of Antiquities of Scotland, in Edinburgh, and in the Museum of the Royal Irish Academy in Dublin. A few good specimens are in private hands, and there is a splendid one from Orton Scar,¹ in Westmoreland, in the Museum of the Society of Antiquaries at Burlington House.

The portions of the brooch, the forms of which are altered so as to adapt them better to the reception of ornament, are the head of the pin and the two terminations of the ring, where the break occurs. The two chief ways of altering the shapes of these parts are (1) by making them spherical, and (2) by expanding into a wide flat surface; the object in both cases being

¹ *Reliquary* for 1903, p. 203.

to increase the area available for decoration. Sometimes, also, the ring and the long end of the pin are flattened and widened for a similar purpose.

As an example of a penannular brooch with bulbous terminations to the ring and head of the pin, we have one from Co. Kildare in Ireland (R.I.A. photo, B 172). The knobs are covered with a prickly ornament produced by incised lines drawn prickly diagonally in two directions, crossing each other, giving the whole the appearance of the head of a thistle. Several brooches of this kind have been obtained from different localities in Ireland, and there was one along with the three brooches of the type with flattened and expanded ends found with the Ardagh Chalice—a hoard of objects of purely Irish types—but their ornamentation appears to be more Scandinavian than Celtic. One of the best specimens from Skaill, in Orkney, now in the Edinburgh Museum, has a pin 1 foot 3 inches long, and the bulbous ends covered with zoomorphic designs similar to those on the Manx crosses, and on an iron axe-head inlaid with silver from the Mammen How,¹ Denmark.

We next come to brooches with discoidal terminations, of a date not later than the beginning of the ninth century, as the simplest example of which may be taken one from Croy, in Inverness-shire (*Scotland in Early Christian Times*, 2nd ser., p. 23). Another, found near Perth (*ibid.*, p. 21), has three raised heads on each disc; whilst one from Rogart, in Sutherland-shire (*ibid.*, p. 7), has four raised heads outside the circumference of the disc, so that the terminations are altered into the shape of a quartrefoil.

Lastly, we have brooches with flat expanded ends to

¹ Dr. J. Anderson's *Scotland in Pagan Times: Iron Age*, p. 97.



DETAIL OF ORNAMENT ON THE TARA BROOCH
IN THE DUBLIN MUSEUM



DETAIL OF ORNAMENT ON THE TARA BROOCH
IN THE DUBLIN MUSEUM

the ring, of which kind three specimens in the Museum of the Royal Irish Academy at Dublin are illustrated, in order to show the way of ornamenting the expansions with one, four, and five raised bosses, having zoö-morphic designs on the background (R.I.A. photos, B 163 and B 164). The area of the head of the pin available for decoration is increased by making it into a cylindrical tube.

In the final stage of the development of the penannular brooch in Ireland it ceased to be penannular, if we may be permitted to use such an Irish expression. The break in the ring was entirely filled up, although its position can still be traced by the method of arranging the pattern, which survived in its old form long after the split had disappeared. The celebrated Tara Brooch, in the Museum of the Royal Irish Academy (R.I.A. photo, A 161), affords a striking example of this. The doing away of the break in the ring must have entirely defeated the original purpose the brooch was intended to serve, and it would, therefore, appear that these highly decorated brooches were made rather for ceremonial use, than to be of any practical value as dress-fasteners.

It may be pointed out that all the characteristic modifications of the form of the penannular brooch made by the Celtic artist arose from his desire to provide more space for the ornamental patterns, which were the very salt of his existence.

Dr. Joseph Anderson contributes the following note apropos of the long pin :—

“ In the *Brehon Laws*, vol. iii., p. 291, men are exempted from liability to fine for injury from the pin of their brooch (in a crush? or at a fair?) if they have the brooch on their shoulder so as not to project beyond it. Women also are

exempt if they have their brooch similarly on their bosom." Vol. iv., p. 323, "a precious brooch worth an ounce [of silver?] is enumerated among the customary insignia of a chief."

The Tara Brooch¹ was found in 1850 by some children whilst playing on the strand near Drogheda, Co. Meath. It was offered by the mother of the children to a dealer in metals in Drogheda, but he refused to purchase it, after which she took it to a watchmaker in the town, who gave her a trifle for it. The watchmaker cleaned it up, and subsequently sold it to Messrs. Waterhouse, of Dame Street, Dublin. The Tara Brooch is now in the Museum of the Royal Irish Academy. The body of the brooch is made of an alloy of copper and tin called white bronze, and the decorations with which it is encrusted consist of gold filigree in small recessed panels, niello, enamel, and settings of amber and glass. The ornament includes interlaced-work, spirals, step-patterns, scrollwork, zöomorphs, and anthropomorphs. The spiralwork is of the best kind, such as is only found in MSS. like the Book of Kells. The designs on the back of the brooch appear to be chased or cut into the solid metal of the body, and not composed of plaques fixed on with rivets. Attention should be particularly directed to the rows of birds, each biting the leg of the one in front of it, on the back of the brooch. Similar designs occur in the Lindisfarne Gospels² and on a cross-shaft from Aberlady,³ now at Carlowrie Castle, near Kirk-

¹ H. O'Neill's *Fine Arts of Ancient Ireland*, p. 49.

² *Publication of the Palæographical Soc.*, and G. F. Warner's *Illuminated Manuscripts in the British Museum*, 3rd series.

³ Allen and Anderson's *Early Christian Monuments of Scotland*, p. 428.



DETAIL OF ORNAMENT ON THE TARA BROOCH IN THE
MUSEUM OF THE ROYAL IRISH ACADEMY, DUBLIN

liston, Linlithgowshire; clearly showing Northumbrian influence, as bird-motived ornament of this kind is in no way characteristic of pure Irish work.

There are several beautiful penannular brooches in the National Museum of Antiquities of Scotland, at Edinburgh, most of which are described and illustrated in Dr. J. Anderson's *Scotland in Early Christian Times* series. The finest of these is the Hunterston Brooch,¹ which has a Runic inscription upon it and is decorated with interlaced-work, zoömorphs, and spiralwork almost equal to that on the Tara Brooch. The Cadboll Brooch² from Rogart, Sutherlandshire, and a brooch from Perth³ are also very beautiful examples.

The best examples of early Irish ornamental leather-work are the satchel of the Book of Armagh⁴ in the Library of Trinity College, Dublin, and the satchel of St. Moedog's reliquary⁵ in the Museum of the Royal Irish Academy. The patterns on the former consist of interlaced-work and zoömorphs, and those on the latter of interlaced-work only. There are also specimens of leather shoes in the Museum of the Royal Irish Academy with Celtic ornament upon them.⁶

There are very few objects of wood or bone now in existence which exhibit Celtic ornament of the Christian period.

¹ Dr. J. Anderson's *Scotland in Early Christian Times*, 2nd ser., p. 2.

² *Ibid.*, p. 7.

³ *Ibid.*, p. 21.

⁴ Rev. J. P. Mahaffy's *Book of Trinity College*.

⁵ *Archæologia*, vol. xliii., p. 131.

⁶ Sir W. Wilde's *Catal. Mus. R.I.A.*, p. 284.

CHAPTER VII

CELTIC ART OF THE CHRISTIAN PERIOD

TECHNICAL PROCESSES AND MATERIALS EMPLOYED DURING THE CHRISTIAN CELTIC PERIOD IN GREAT BRITAIN

ECCLESIASTICAL and other MSS. written on sheets of vellum and bound up in the form of a book were introduced into this country with Christianity. The materials and tools used by the Celtic scribes and illuminators probably did not differ to any great extent from those used throughout Europe during the Middle Ages. The parchment of the Irish MSS. is, however, generally much thicker¹ than that of the Carlovingian and other foreign MSS. The letters in the Irish MSS. of the best period, such as the Book of Kells, are composed partly of extremely fine lines, drawn with a firm hand, which gradually expand in width to form the other parts of the letters. These could hardly have been made with a reed or a brush, so that it is probable that the pens of the Irish scribes were made from the quills of swans, geese, crows, and other birds. The black ink used in the Irish MSS. is remarkable for its blackness and durability; and Bede, the historian, speaks highly in praise of the colours prepared in Ireland, and especially of

¹ Sir E. M. Thompson's *Greek and Latin Palaeography*, p. 38.

the brilliancy and permanence of the red made from whelks.¹ Some colours, such as yellow, are put on thin and transparent ; whilst others, such as red, have a thick body made of titurated earth or other skilfully prepared material, mixed with some strong binding material of the nature of gum or varnish.²

The material employed for the highly ornamented sculptured monuments of the Christian Celtic period was generally that most readily procurable on the spot, but a preference was always shown for a freestone, which could be easily worked. The greater proportion of the best crosses are carved in a fine-grained sandstone. In Cornwall granite was most generally used, although Polyphant stone was also used. In the Isle of Man nearly all the crosses are of slate. Hard, volcanic rocks were avoided where possible on account of the difficulty of working. There are, however, crosses of trap-rock at Carew, Pembrokeshire, and Moel Siarman, Brecknockshire.

On some of the crosses the marks of the tool with which they were carved can still be clearly seen, as on the Cross of Iltyd at Llantwit Major, and the cross-base at Llangevelach, both in Glamorganshire. As far as it is possible to judge from the tool-marks, either a pick or a pointed chisel must have been employed by the early Christian Celtic stone-carvers. Similar tool-marks have been observed on the cup-and-ring sculptures of the Bronze Age.

In the churchyard at Kells, Co. Meath, there is an unfinished cross which is of great interest as showing the exact methods used in the construction and decoration of this class of monument. The stone was first

¹ Bede's *Eccl. Hist.*, bk. i., chap. 1.

² Dr. Ferdinand Keller in the *Ulster Journal of Archaeology*, vol. viii.

squared and the design roughly set out upon it. Draughts were then cut across the faces, leaving certain portions standing out in high relief, upon which the figure subjects were afterwards sculptured. The unfinished cross at Kells was formerly lying on the ground, but it has recently been erected on its original base, which is also unfinished.

When the crosses are constructed of two or more pieces they are fitted together by means of mortice and tenon joints. Sometimes the quadrants of the circular ring connecting the arms were made in separate pieces, as in the case of the large broken cross at Iona.¹

The metals in use during the Christian Celtic period were gold, silver, copper, lead, bronze, brass, and other alloys. These were cast and wrought and ornamented by means of enamelling, niello, plating, gilding, repoussé-work, chasing, engraving, piercing, inlaying, filigree-work, Trichinopoly chainwork, and settings of precious stones, amber, and glass. The different pieces of the metal objects were fixed together by rivets, and if soldering and brazing were known, they were certainly not employed to any great extent. Even when the specimens can be removed from their show-cases in museums and examined carefully by an expert it is not always possible to be certain of the exact technical processes by which the various decorative effects have been produced, and unless the objects can be dissected many of the constructive features must necessarily be a matter for conjecture. The Ardagh Chalice and the Tara Brooch illustrate nearly all the materials, technical processes, and methods of construction used at this period.

¹ *Proc. Soc. Ant. Scot.*, vol. xxxv., p. 90.

Three different kinds of enamel are used in the decoration of the Ardagh Chalice, namely, (1) a peculiar variety of *cloisonné* in which the compartments, or *cloisons*, are all cut out of a single piece of metal and the open framework thus formed is pressed into the surface of the enamel when soft until it rises up and fills each compartment; (2) a combination of *cloisonné* and *champlevé* enamel in which the compartments are all cut out of a single piece of metal, some being pierced right through and the remainder only sunk partially through the thickness of the metal; the framework is pressed into the enamel when soft, thus filling up the open compartments, as in the first kind just described, and the remaining dug-out compartments are filled with fusible enamel as in *champlevé*; and (3) a species of *champlevé* enamel, in which the surface of a piece of glass was engraved with a design in *intaglio* and the hollows filled up with an enamel of a different colour. The Celtic enamels of the Christian period usually occur in the form of small round bosses, of which there are good instances on the Ardagh Chalice, the Ardagh Brooch, the Tara Brooch, the Lismore Crozier, and the Cross of Cong.

The use of bands of silver with borders of niello is well illustrated by the head of a crozier¹ formerly belonging to the late Dr. W. Frazer, M.R.I.A., of Dublin. Portions of the silver have been stripped, showing how the surface of the metal into which it was inlaid was roughened with a pointed tool to make the inlay adhere better. Niello is a black composition made of silver, lead, sulphur, and copper, which is reduced to powder and placed in cavities or lines cut for its reception in the surface of the metal,

¹ *Proc. R.I.A.*, 3rd ser., vol. i., p. 207.

and afterwards incorporated with it by being passed through the furnace. Niello probably found its way to Ireland from the East. It was used by the Byzantines as early as the beginning of the ninth century.¹

A peculiar kind of decoration which is specially characteristic of the early Irish ecclesiastical metal-work consists of plates perforated with triangles, squares, and crosses, so as to form a geometrical pattern. The plates are usually of bronze covered with silver, and the contrast between the bright surface of the white silver and the pierced portions through which the dark bronze below can be seen gives the general appearance of chequerwork. There are good instances of this class of decoration on the Shrine of the Bell of St. Patrick's Will, and the Cumdachs of Dimma's Book, the Stowe Missal, and the Shrine of St. Mogue. Cruciform pierced work of a similar kind also occurs on an ivory of the tenth century representing the raising of the widow of Nain's son, in the British Museum;² on an ivory of the tenth century, representing Christ in the Temple, in the Royal Library at Berlin;³ and on the chair of the image of St. Faith, in the treasury of Conques⁴ (Aveyron). The wards of ecclesiastical keys are often made to form cruciform patterns, as in the case of those of Netley Abbey, St. Serrais Maestricht, and Liège.⁵ The cruciform patterns on the west face of

¹ J. H. Pollen's *Gold and Silver*, p. 53.

² J. O. Westwood's *Catal. of Fictile Ivories in S. K. Mus.*

³ *Ibid.*

⁴ *Annales de la Société Archéologique de Bruxelles*, vol. xv. (1901), p. 434.

⁵ Le Chanoine Rensens' *Éléments d'Archéologie Chrétienne*, 2nd ed. (Aix, 1885), vol. i., pp. 241 and 262.

the cross at Dysert O'Dea,¹ Co. Clare, seem to be copied from metalwork.

Filigree-work of gold wire is used to make the panels of interlaced-work, scrollwork, and zoöomorphic designs with which some of the best specimens of Christian Celtic metalwork are decorated, such as the Ardagh Chalice, the Tara Brooch, the Hunterston Brooch, and the Clonmacnois Pin. The filigree-work is often covered with minute granulations, which add greatly to the richness of the effect produced by their texture.

We have already referred to the Trichinopoly chainwork of silver wire used in the Ardagh Chalice, the Tara Brooch, and the Clonmacnois Pin. This kind of chainwork can be traced back to the Pagan Celtic period, as chains of similar character were found with the Late-Celtic gold collar at Limavady, Co. Londonderry, and with the pair of silver-gilt Kelto-Roman fibulæ from Chorley, Lancashire, now in the British Museum.

Settings of coral and enamel were, as we have seen, employed for the decoration of the Late-Celtic metalwork, but in the Christian Celtic period numerous other substances were also employed, such as glass, rock crystal, amber, and other precious stones. In some cases the settings of stones and glass were rectangular with a flat top and bevelled edges, but they were more generally round, oval, or almond-shaped and "tallow-cut," *i.e.* polished without facets.

The process used for producing the patterns on the leather satchels and shoes previously mentioned was probably of the same nature as that by which the *cuir bouilli* cases of later times were decorated.

¹ *Jour. R. Soc. Ant. Ireland*, ser. 5, vol. ix., p. 251.

Objects of wood, bone, ivory, and pottery and textile fabrics of the Christian Celtic period are so rare that there is really nothing to be said about the technical processes involved in their manufacture.

THE ORIGIN AND DEVELOPMENT OF EARLY CHRISTIAN
ART IN GREAT BRITAIN

Attention has been recently directed to the problem of how decorative art was evolved, in the first instance, by the primitive races of mankind in remote ages. Mr. Henry Balfour, Mr. C. H. Read, and Dr. Colley March have shown us how much light may be thrown on this difficult question by a critical examination of the various forms of ornament used by the savage—or, rather, the uncultured—peoples existing at the present day in countries where they have had only limited opportunities of coming in contact with modern civilisation.

There is, however, at least as difficult a problem nearer our own doors awaiting solution, namely, that of the origin and development of early Christian decorative art in the British Isles. This problem is not one of a wholly uncultured race left to itself to work out its own ideas, as suggested by external natural objects or otherwise, but it is a problem of a race already in a state of semi-culture being brought suddenly face to face with a higher civilisation, through the introduction of a new religion, and afterwards influencing, or being influenced by, other conquering races—also in a state of semi-culture—whom they converted by missionary enterprise. That is to say, the Celts of Ireland, Scotland, the Isle of Man, Wales,

and Cornwall became acquainted with Italo-Byzantine art when they were first Christianised, about the middle of the fifth century. In the seventh century they came in contact with the Anglo-Saxons, and in the ninth with the Norsemen and Danes. It is the object of the present inquiry to determine in what measure the Christian art of this country before the Norman Conquest was affected by the absorption of these new racial elements.

The style of art we are now dealing with was formerly, quite wrongly, called Runic, because some of the monuments on which characteristic forms of ornament occur bear Runic inscriptions. Later authorities have called the style Hiberno-Saxon, Kelto-Northumbrian, Celtic, and Irish, but this is simply begging the whole question. The term we have chosen, namely, early Christian, is scientifically correct, and does not commit us to the assumption of any unproved facts.

Early Christian art in this country is essentially decorative, and to a lesser extent symbolic. The figure subjects are obviously barbarous copies of Byzantine originals, for no matter how they are disguised by bad drawing or incrustated with ornament, the conventional grouping and accessories still remain to prove their origin. The miniature of the Temptation of Christ in the Book of Kells is perhaps the most remarkable instance of a Byzantine design Celticised, if one may use the expression. Comparing this with a miniature in the Psalter of Misselinda (A.D. 1066) in the British Museum (Add. 19,352), we find all the essential features of the scene the same, even to the black Devil; but in the Book of Kells the Temple with its Byzantine cupolas has been converted into an

Irish stone-roofed oratory, shaped like a metal shrine of the period, and covered with ornament; the Devil, too, has been decorated with spiral curves after the Celtic fashion.

The miniatures of the Evangelists, with their symbols, which form the frontispieces of the Irish Gospels, are also taken from a Byzantine source and similarly disguised, although not so effectually as to conceal their derivation. The Irish illuminator put as much local colour into his copy as a Chinaman or a Japanese would, but in a different way, if told to make a replica of an English picture.

In distilling the original Byzantine idea through the alembic of the mind of the Irish scribe it has absorbed so much of his individuality that it assumes an archaic and semi-barbarous appearance which is very misleading at first sight. We hope to be able to show that some of the elements of the ornament may be traced to a Byzantine source, and that the only obstacle in the way of our at once recognising whence the Irish designer received his inspiration is his marvellous power of adaptation and skill in evolving fresh combinations of simple elements. The ancient Irish artists appear in some respects to have resembled the Japanese in the rapidity with which they absorbed new ideas and turned them to good account in their decorative designs.

The materials available for the study of early Christian art in Britain consist of illuminated MSS., ecclesiastical and other metalwork, sculptured monuments, and a few miscellaneous objects. I propose now to direct attention chiefly to the sculptured monuments, because they afford a much more certain means than any other of determining the charac-

teristics of the various local styles throughout the country.

If a monument is found in a particular district, it may generally be assumed that it was the art product of the district, unless there is some special reason for thinking otherwise. The number of MSS. and examples of metalwork is comparatively much smaller than the number of monuments, and it is only in a few exceptional cases that a MS. can be traced to the monastic establishment where it was written. In Scotland, for example, although richer than any other part of Great Britain in sculptured monuments, the Book of Deer is the only pre-Norman MS. known to have been written there. Wales, again, can only claim the Psalter of Ricemarchus.

I am of opinion that if we are ever to arrive at any definite conclusions with regard to the evolution of early Christian art in Great Britain, it must be by means of a careful examination and comparison of the minute details of the ornament. The science of palæography is entirely founded on the observation of every small variation in the form of each letter, and if the same trouble was taken with ornament equally valuable results would be obtained.

We will now proceed to analyse the decorative features of the monuments, and endeavour to find an origin for the component elements which go to make up the style. I must assume the reader to possess a certain amount of acquaintance with the art of the early Christian period, and to know what is meant by most of the technical terms, but I shall give examples of the various classes of patterns in case anyone should be unfamiliar with their appearance.

Broadly speaking, early Christian ornament in Great

Britain is made up of the following elements, generally arranged in separate panels :—

- | | | |
|------------------------------|---|--|
| (1) Interlaced-work. | } | Geometrical. |
| (2) Step-patterns. | | |
| (3) Key-patterns. | | |
| (4) Spirals. | | |
| (5) Zöomorphic Designs. | } | Suggested by Animal,
Human, and Vege-
table Forms. |
| (6) Anthropomorphic Designs. | | |
| (7) Phylломorphic Designs. | | |

Now the question is, what are the possible or probable sources whence each of these different kinds of patterns was derived?

First of all, there are the native and imported styles of decorative art existing in Great Britain previous to the introduction of Christianity (*circa* A.D. 450), comprising the art of the ages of Stone, Bronze, and Iron, and Romano-British art. Next, the external influences which came into play after A.D. 450, and before A.D. 1066, were Italo-Byzantine, Anglo-Saxon, Frankish, and Scandinavian.

Early Christian art in Great Britain was produced, in the first instance, by grafting the Italo-Byzantine style upon the native style of the Iron Age (sometimes called Late-Celtic), and was subsequently modified by Anglo-Saxon and Scandinavian influence.

Of the forms of decoration used in the Stone Age in this country we know hardly anything, and therefore they will not come within the scope of our investigations. The ornamental patterns of the Bronze Age, as far as we are acquainted with them from a study of the sepulchral urns, implements, personal ornaments, and sculptured cists and chambered tumuli, are of a very simple description, consisting chiefly of chevrons, concentric circles, and rudely drawn spirals. The latter

may have been the forerunners of the beautifully designed volutes of the Iron Age, the nearest approach to perfection being on the sculptured slab at the entrance to the New Grange tumulus, Co. Meath, and on the slabs forming the sides of a chambered cairn at Clover Hill, Co. Sligo.

When we come down to the Iron Age we find a very beautiful and refined system of decoration applied to bronze objects, such as hand-mirrors, shields, helmets, sword-sheaths, and horse-trappings, the leading *motif* of which is the divergent, or trumpet-shaped spiral. This style of decoration has received the name Late-Celtic in this country, and La Tène on the Continent.

No one can fail to be struck with the similarity between the Late-Celtic spiral ornament and that found in the early Irish MSS., the patterns in some cases being absolutely identical. It is thus possible to trace this particular element in the decorative art of the early Christian period to a native Pagan source.

Late-Celtic objects have been found in all parts of the United Kingdom, but probably the style of decoration only survived into Christian times in Ireland, although there is really no reason why it should not have done so elsewhere—in the north of Scotland, for instance, which was quite as much cut off from civilisation as Ireland during the Saxon conquests. The closest resemblance between the spiral decoration of the Pagan period and that of the Christian period is to be found on the discoidal ornaments with patterns in *champlevé* enamel, forming the attachments of the handles of certain bronze bowls, several examples of which have been discovered from time to time in different parts of England.¹

¹ *Archæologia*, vol. lvi., p. 43.

I believe that the only element in early Christian decorative art in this country that can be traced to a native Pagan source is the divergent spiral. It has been suggested that the Irish and Saxon designers derived some of their ideas from the Roman pavements, but I can see nothing in the decoration of the MSS. on monuments of the pre-Norman period that can be fairly attributed to a Romano-British origin.

We have now to consider the external influences which came into play after the introduction of Christianity (*circa* A.D. 450). First amongst these was the influence of Italy, and thus more indirectly that of Byzantium. It is to this source that it is possible to trace the interlaced-work and scrolls of foliage which occur so frequently on the early sculptured monuments in Great Britain. We can refer to no better text-book whilst dealing with this portion of our investigation than *L'Architettura in Italia*, by Professor Raffaele Cattaneo (Venezia, 1888), who, by a careful study of the subject, has been able to divide early Italian ecclesiastical architecture into the following styles and corresponding periods:—

- | | | | |
|-----------------------|---|---|------------------------|
| (1) Latino-Barbaro | . | . | A.D. 300 to A.D. 600. |
| (2) Bizantino-Barbaro | . | . | A.D. 600 to A.D. 800. |
| (3) Italo-Bizantino | . | . | A.D. 800 to A.D. 1000. |

As an example of the first period we have the Ciborium in the Church of San Clemente at Rome (A.D. 514-23), decorated with plaitwork and foliage, both evidently of Classical origin. Belonging to the second period we have the Ciborium of San Giorgio di Valpolicella¹ (A.D. 712), decorated with broken plait-


¹ Also the jambs of the doorway of the chapel of S. Zeno in the church of S. Prassede, Rome (A.D. 772-95).



CIRCULAR KNOTWORK ON
SLAB IN CHURCH OF
STA. SABINA, ROME




CIRCULAR KNOTWORK ON
SLAB IN CHURCH OF
STA. SABINA, ROME



DOORWAY OF THE CHAPEL OF S. ZENO IN THE CHURCH OF
S. PRASSEDE AT ROME, SHOWING BROKEN PLAITWORK
ON JAMBS

(A.D. 772 TO 795)

work, and the Baptistery of Cividale (A.D. 737), with fully developed knotwork. And belonging to the third period the Ciborium of Sant' Apollinare in Classe, near Ravenna (A.D. 806-16), with interlaced-work and



Pierced Marble Screen at Ravenna

foliage, and a slab over the altar of San Giacomo, at Venice (A.D. 829), with circular knotwork.¹


A careful examination of these specimens shows that

¹ Slabs of circular knotwork are also to be seen in the church of Sta. Sabina, Rome.


the plait was the first kind of interlaced-work employed for decorative purposes, and that it was of Classical origin. The plait as a decorative motive must have been well known to the inhabitants of this country during the Roman occupation and immediately after, from the numerous examples which occur on Roman pavements, as at Lydney Park, Gloucestershire, and elsewhere.

Knotwork was gradually evolved from the plait by introducing breaks at regular intervals during the Bizantino-Barbaro period (A.D. 600 to 800); and subsequent to this we find still more complicated forms of interlaced patterns were introduced, which I propose to call circular knotwork and triangular knotwork. The evidence gathered from dated examples of interlaced-work in Italy tends to show that there was a gradual advance in the elaboration of the patterns as time went on. Consequently the style could not have been borrowed *en bloc* by Ireland from Italy, or *vice versâ*, at one time; but interlaced ornament must have been a prevalent form of decoration throughout the whole of the West of Europe, and the style advanced in all the different countries simultaneously, there being always a constant communication between Rome and the centres of religious activity abroad. Some races, like those in Great Britain, who appear to have had a special gift for inventing new patterns and combining them with a sense of artistic fitness, may have made more rapid strides than their neighbours and have influenced the development of the style in consequence, but that is all that can be said.

Two special peculiarities of the Italian interlaced-work, as compared with that in Great Britain, are the ornamenting of the interlaced bands with two incised




VINE SCROLLS, S. APOLLINARE NUOVO, RAVENNA



KEY PATTERN, S. APOLLINARE NUOVO, RAVENNA

lines instead of one, and the twisting together two bands at frequent intervals, thus—



The latter feature, which is clearly Classical, occurs frequently in circular knotwork in this country, showing that circular knotwork is of Italian origin.

The reason why interlaced-work is characteristic of early Christian decoration almost throughout the whole of Europe, whilst spirals, key-patterns, foliage, etc., are confined to particular limited areas, I believe to be partly because the number of distinct patterns that can be produced from interlaced-work is far greater than those which can be got from any other class of ornament.

It is hardly necessary, perhaps, to enlarge much upon the subject of the foliage of the early Christian period in Great Britain. The scrolls with conventionalised bunches of grapes are no doubt descendants of the Classical vine; the involved birds, beasts, etc., being a later addition¹ of the Bizantino-Barbaro, or Italo-Bizantino periods. Foliage is unknown in the Pagan Saxon, Scandinavian, or Late-Celtic art, and the only other source it could have been derived from is Italian art.

We lastly have to consider the parts played in the development of early Christian art in Great Britain by the Anglo-Saxon and the Scandinavian invaders. There does not seem to be much evidence to show that

¹ Or a substitution of later forms for the Cupids, etc., of the Classical style.

the Saxons were ever gifted with any great capacity for ornamental design, although their workmanship often reached a high pitch of excellence. In looking through the plates of the most recent work on *The Industrial Arts of the Anglo-Saxons*, by the Baron J. de Baye, one is struck with the extremely limited range of imagination displayed in the design of the patterns. Interlaced-work (but of a debased kind) occurs on some of the sword-hilts and buckles, the latter evidently bearing a remarkable affinity to the Merovingian buckles. A radiated fibula found at Searby, in Lincolnshire, exhibits a diagonal key-pattern similar to that found in the Irish MSS. Far the most beautiful specimens of Saxon jewellery, however, are the circular brooches with *cloisonné* ornament. The disc-shaped surface of these brooches is broken up into little compartments, which are filled in with thin slabs of coloured glass, garnets, etc. The narrow bands of gold which separate the compartments from each other are zigzagged at right angles, or stepped, and it is quite possible that the idea of the stepped patterns within circles, which occur in the decoration of the Irish MSS. and on the circular enamelled bosses on the Irish ecclesiastical metalwork, may have been taken from the circular *cloisonné* Saxon brooch. It is only fair, however, to mention that circular ornaments of *cloisonné* enamel, with an approximation to a stepped-pattern, are used in the decoration of the magnificent Late-Celtic shield found in the Thames at Battersea, and now in the British Museum.

It has been suggested that Irish interlaced-work was derived from the rude interlaced patterns on the Saxon and Merovingian buckles, but this appears to me most unlikely.

M. Paul du Chaillu, in his *Viking Age*, has endeavoured to show that the Anglo-Saxons derived their art such as it is from Northern rather than from Central or from Western Europe; but his views will not receive favour at the hands of the scientific archæologist who relies on hard facts to make good his contentions. The forms and ornamental details of the buckles and other objects found with Saxon burials in the south of England undoubtedly show more affinity with Merovingian grave-goods than with anything emanating from Norway, Sweden, or Denmark.

Although no trace of Scandinavian influence can be detected in the ornamental patterns of the Anglo-Saxons—at all events, in the period preceding the Viking conquests in the ninth and tenth centuries—I am not quite so sure that one of the elements of early Christian decorative art in Great Britain may not possibly be of Northern origin, namely, the zoömorphic element. I put forward this suggestion with the greatest diffidence, and merely as a tentative theory until something better can be found to take its place.

Zoömorphism is not a marked characteristic of Pagan Saxon decorative art, and therefore, in order to account for the predominance of so-called dragonesque designs in the early Irish illuminated MSS., we must fall back on one of the following alternatives: (1) that these patterns are of native origin, and were invented by the Irish; (2) that like the spirals, they are of Late-Celtic origin; and (3) that they are of Italo-Byzantine derivation.

General Pitt-Rivers and Mr. Henry Balfour have given us an insight of the manner in which animal forms, by repeated copying, may degenerate into mere ornament; and at one time I thought that early Chris-

tian zoömorphism might have been the result of a process of a reverse nature. It is possible to "see snakes" when looking at a piece of interlaced-work without necessarily suffering from excess of alcoholism. Thus zoömorphic designs might have been evolved from interlaced-work by making the bands terminate in heads and tails, the limbs following in due course later on. Such may have been the process by which the Irish illuminator arrived at his zoömorphism, unless it can be shown that he got it in some other way.

Animal forms are comparatively rare in Late-Celtic art, and they are not interlaced, so that it is almost useless to seek for the original inspiring idea in this direction.

Birds, beasts, reptiles, and other creatures—often used symbolically—are frequently seen in Byzantine art, both in the decorative features of churches and in the borders of the MSS. If it was thence that the early Christian zoömorphs in this country took their origin, I fancy the interlacements must have been arrived at either by placing the creatures in pairs symmetrically facing each other, or by contorting their bodies into unnatural attitudes. In the case of beasts arranged in pairs, the first step towards interlacement is to raise their paws and then to make them cross. The beasts may also be placed with their necks crossed; their tails may gradually curl round until they pass over the body, and may be looped or knotted to fill in a blank space; and in endless other ways the most complicated forms of zoömorphic interlaced-work may be evolved from simple beginnings.

Dr. Hans Hildebrand, in his *Industrial Arts of Scandinavia* (p. 50), explains in a most ingenious manner how the lion *couchant*, which so often appears

in Roman art, forms the basis of the earlier kinds of zoömorphie ornament in Scandinavia. The question is, did the Irish evolve their zoömorphs independently in a similar way from a Classical or Byzantine lion, or did they get the idea from the Scandinavians after they had so transformed the Roman lion *couchant* that all resemblance to the original had disappeared? The difficulty in settling this point is the absence of accurately dated specimens of Scandinavian art workmanship. The panels of zoömorphie ornament on some of the fibulæ of the Later Iron Age, illustrated in Dr. Hans Hildebrand's work already referred to (pp. 58-65), bear a very considerable general resemblance to the panels of interlaced beasts in the Irish MSS., although the details are worked out differently. The whole question turns on the exact date of the Gotland brooches. If they can be proved to be earlier than the time when zoömorphism first appears in the Irish MSS., and if it is possible that the communication between Ireland and Gotland can be accounted for by the trade in silver objects and bullion existing between this country and the East, then there is something to be said for the Scandinavian origin of zoömorphism in Ireland. I believe, however, that from the evidence of the coins found with hoards of silver objects, this trade did not begin until about A.D. 800.

Attention must here be called to two points which are common to the zoömorphie and anthropomorphic designs of Scandinavia and of Great Britain, namely, (1) the introduction of spiral curves to represent conventionally the folds of the skin where a limb joins the body; and (2) the introduction of figures of men grasping birds and beasts, or arranged swastica-wise grasping each other's limbs. Here, again, it is not

easy to decide whether these features were invented independently, or whether they were borrowed by the Irish from Scandinavia, or by the Scandinavians from Ireland.

Whatever may be thought of the possibility of the existence of Scandinavian influence on Christian art in this country in its earlier phases, there is plenty of evidence of the development of an Anglo-Scandinavian style in particular districts where the Norse element was strong, as in the Isle of Man, and the adjoining coasts of Cumberland, Lancashire, and North Wales, and in Orkney and Shetland.

The specially Scandinavian characteristics of the sculptured monuments in the districts specified are as follows :—

(1) There is a predominance of patterns formed of chains of rings.

(2) The bands of the interlaced-work have a tendency to bifurcate and break off into scroll-like terminations.

(3) The beasts in the zoöomorphic designs have two toes, instead of three ; the bodies are covered with scales ; the attitude is peculiar, the head being bent back and a crest issuing from it with fin-like appendages in places ; and the junction of the limbs with the body is conventionally indicated by spirals.

(4) Amongst the figure-subjects scenes from the mythic-heroic Eddaic poems, such as Sigurd Fafni's bane, Thor fishing for the Midgard-worm, Weyland Smith, etc.

Even in Norman times Scandinavian influence is exhibited in the details of the tympana at Hoveringham, and Southwell Minster, Notts, and St. Nicholas, Ipswich.

The only element in early Christian decorative art the origin of which we have not succeeded in running

to earth in the preceding investigation is the key-pattern. I venture to think that this may have been suggested by the Greek or Roman fret, and that the essentially Celtic character imparted to it was the placing of the guiding lines in a diagonal direction with regard to the margin, instead of parallel to it. I believe the reason for this to be that exactly the same setting-out diagram was used both for the interlaced-work and the key-pattern. It is often possible to trace the origin of key-patterns to the necessities of the methods of weaving textile fabrics; but with regard to the ones we are now considering I am inclined to think that their beginnings are due to the geometrical conditions imposed by the arrangement of the setting-out lines.

In conclusion, I wish to emphasise the fact that the beauty and individuality of the ornamental designs found in early Christian art in Great Britain are due chiefly to the great taste with which the different elements are combined and the exquisite finish lavished upon them. I cannot see that it in the least detracts from the praise due to the originators of the style if it can be shown that the ideas underlying many of the patterns were suggested by a pre-existing native style or adapted from a foreign one. Interlaced-work, key-patterns, spirals, and zoömorphs are to be found separately in the decorative art of many races and many periods, but nowhere and at no time have these different elements been used in combination with such consummate skill, as in the early Christian period in Great Britain and Ireland.

CHAPTER VIII

CELTIC ART OF THE CHRISTIAN PERIOD

THE LEADING CHARACTERISTICS OF CELTIC ART OF THE CHRISTIAN PERIOD IN GREAT BRITAIN, AND THE GENERAL NATURE OF ITS DECORATIVE AND SYMBOLIC ELEMENTS

THE leading characteristics of Celtic art of the Christian period are as follows :—

- (1) The prominence given to the margin or frame within which the whole design is enclosed.
- (2) The arrangement of the design within the margin in panels, each containing a complete piece of ornament.
- (3) The use of setting-out lines for the ornament, placed diagonally with regard to the margin.
- (4) The use of interlaced-work, step-patterns, key-patterns, spirals, and zoömorphs in combination.
- (5) The geometrical perfection of all the ornament.
- (6) The superiority of the decorative designs to the figure-drawing.

There are in the world two distinct schools of decorative art, one which entirely ignores the shape of the surface to be ornamented, and the other which allows the contour of the margin to influence the whole design. Japanese art belongs to the first of these, and Celtic art to the second. In the Irish illuminated

MSS. the rectangular shape of the page determines the setting out of the design, which is universally enclosed within a rectangular margin composed of lines of various thicknesses, or within an ornamental panelled frame. The only exception is in the case of the initial pages of the Four Gospels, where the margin is incomplete, so as to allow the extremities of the letters to project more nearly to the edge of the page. This prominence given to the margin often greatly influences the designs within it, more especially the key-patterns with diagonal setting-out lines. In sculptured stonework either roll-mouldings or flat bands form the margin, and in metalwork the margins are raised and the panels sunk.

The panels within the margin are generally rectangular, but sometimes they are circular, annular, segmental, triangular, etc. The ornament in adjoining panels is seldom of a similar kind, and the patterns are often arranged on the principle of chequerwork, so that if there is a panel of interlaced-work at the left-hand upper corner of the page of a MS., and a panel of key-pattern at the left-hand lower corner, the order will be reversed on the opposite side of the page, and the key-pattern will be at the right-hand upper corner and the interlaced-work at the right-hand lower corner.

The diagonal setting-out lines are chiefly confined to the key-patterns, and, as we shall see subsequently, are the origin of the peculiar form of Celtic key-pattern which was developed from the Greek fret.

The various motives that have been specified—namely, interlaced-work, step-patterns, key-patterns, spirals, and zoömorphs—are not always found in combination, except in the MSS., sculptured stones, and

metalwork of the best period. The step-patterns are, as a rule, only found in the early MSS. and on the enamelled settings of metalwork. Foliage is a distinctly non-Celtic element, and wherever it occurs it is a proof of Anglian influence from Northumbria. As the decadence of Celtic art set in the spirals disappeared first, and then the key-patterns, leaving only interlaced-work and zoömorphs, which survived even after the Norman conquest. Key-patterns survived in a debased form in the architectural details of the churches of the twelfth century in Ireland, but not in Scotland or Wales.

By the geometrical perfection of the Celtic ornament is meant that there are hardly ever any mistakes in the setting-out and complete execution of the designs. Thus in the interlaced-work every cord laps under and over with unfailling regularity (never over two or under two), and all the cords are joined up so as not to leave any loose ends. All the details of the spiral-work are executed with the minutest care, and there is never a broken line or pseudo-spiral. In the zoöomorphic designs the beasts are all provided with the proper number of limbs and are complete in every respect down to the smallest detail.

The inferiority of the figure drawing in Christian Celtic art to the ornament will be dealt with subsequently in its proper place.

We will now proceed to examine in detail the different motives made use of in the Celtic art of the Christian period in Great Britain.

INTERLACED-WORK

The interlaced ornament used in Celtic art may be divided into the following classes :—

- (1) Regular plaitwork, without any breaks.
- (2) Broken plaitwork, with breaks made in an irregular way.
- (3) Knotwork.
- (4) Circular knotwork.
- (5) Triangular knotwork.
- (6) Ringwork or chainwork.

Interlaced-work is the predominant motive of the Celtic style of the Christian period. It lasted longer in time than any other motive, and its geographical distribution extends over a larger area. It is very seldom that one motive is used by itself for the decoration of a stone monument, metal object, or page of a MS.; but where this is the case the motive chosen is invariably interlaced-work, and not a key-pattern, spiral, or zoömorph. As instances of sculptured monuments decorated entirely with interlaced-work we have the cross at Neuadd Siarman, Brecknockshire, and the cross-shaft at St. Neot, Cornwall.

The evolution of knotwork from plaitwork cannot better be studied anywhere than in the decoration of the Welsh crosses. Let us now endeavour to trace the various stages in the process by which the higher forms of Celtic interlaced work were arrived at.

In Egyptian, Greek, and Roman decorative art the only kind of interlaced-work is the plait, without any modification whatever; and the man who discovered how to devise new patterns from a simple plait by making what I term *breaks* laid the foundation of all the wonderfully complicated and truly bewildering

forms of interlaced ornament found in such a masterpiece of the art of illumination as the Book of Kells in the library of Trinity College, Dublin. Although we do not know *who* made this discovery of how to make breaks in a plait, we know pretty nearly *when* it was made. In the decoration of the mosaic pavements in Great Britain belonging to the period of the Roman occupation, no instance, as far as I can ascertain, exists of the introduction of a break in a plait; nor is there any break in the plaitwork on the marble screen and the capitals of the columns of the ciborium, in the Church of San Clemente at Rome (which are dated by R. Cattaneo¹ between A.D. 514 and 523). In the eighth century, however, there are several examples with well-authenticated dates of the use of true knotwork (as distinguished from plaitwork) in the decoration of churches in Italy; namely, on the ciborium of San Giorgio at Valpolicella² (A.D. 712); on the Baptistery of Calistus at Cividale³ (A.D. 737); and on the jambs of the doorway of the Chapel of San Zeno in the Church of San Prassede at Rome⁴ (A.D. 772-795).


It would appear, then, that the transition from plaitwork to knotwork took place between the Lombard conquest of Italy under Alboin in A.D. 563, and the extinction of the Lombard monarchy by Charlemagne in A.D. 774; possibly during the reigns of Luitprand (A.D. 712-736) and Rachis (A.D. 744): for the name of the former king is mentioned in the inscriptions on the Baptistery at Cividale and the ciborium of San Giorgio at Valpolicella, and the latter on the altar at Cividale.

¹ *L'Architettura in Italia*, pp. 29 and 31.


² *Ibid.*, p. 80.

³ *Ibid.*, p. 87.

⁴ *Archæologia*, vol. xl., p. 191.




PLAITWORK ON CIBORIUM IN THE CHURCH OF
SAN CLEMENTE, ROME
(SIXTH CENTURY)




PLAITWORK ON ROMANO-BRITISH PAVEMENT AT LYDNEY PARK,
GLOUCESTERSHIRE

I now propose to explain how plaitwork is set out, and the method of making breaks in it. When it is required to fill in a rectangular panel with a plait the four sides of the panel are divided up into equal parts (except at the ends, where half a division is left), and the points thus found are joined, so as to form a network of diagonal lines. The plait is then drawn over these lines, in the manner shown on the accompanying diagram. The setting-out lines ought really to be double so as to define the width of the band composing the plait, but they are drawn single on the diagram in order to simplify the explanation.



Regular plaitwork without any break

If now we desire to make a break in the plait any two of the cords are cut asunder at the point where they cross each other, leaving four loose ends A, B, C, D. To make a break the loose ends are joined together in pairs. This can be done in two ways only: (1) A can be joined to C and D to B, forming a vertical




Method of making breaks in plaitwork


break ; or (2) A can be joined to D and C to B, forming a horizontal break. The decorative effect of the plait is thus entirely altered by running two of the meshes

between the cords into one. By continuing the process all the knots most commonly used in Celtic decorative art may be derived from a simple plait.

Let us proceed to trace the process of the evolution of knotwork out of plaitwork by actual instances taken from the Welsh crosses. We have, to start with, good examples of plaits of four, six, and ten cords¹ without any breaks at Nevern, Pembrokeshire; and Llantwit



Regular plaitwork, with one vertical break and one horizontal break




Six-cord plait, with horizontal breaks at regular intervals²

Major, and Margam, Glamorganshire. Next, plaits with a single break only are to be seen at Carew, Pembrokeshire, and Llantwit Major, Glamorganshire; then plaits with several breaks, made quite regardless of symmetry or order, at Golden Grove, Carmarthen-shire; and, lastly, breaks made at regular intervals,

¹ Plaits of an uneven number of cords are seldom used, because they produce lopsided patterns.

² This occurs on the second panel of the cross at Llanbadarn Fawr.




**Cross-shaft at Golden Grove, with panels
of irregular broken plaitwork**
Scale $\frac{1}{4}$ linear



**Cross-shaft at Llantwit Major
(No. 5), Glamorganshire.**
**Eight-cord plait, with cruciform
breaks**
Scale $\frac{1}{4}$ linear


at Neuadd Siarman, Brecknockshire. When the breaks are made symmetrically at regular intervals, and brought sufficiently near together, the plait ceases to be the



Eight-cord plaits, with cruciform breaks


most prominent feature in the design, and in its place we get a pattern composed entirely of what (for want of a better name) are called knots. On

some of the Welsh crosses (as at Carew and Nevern, Pembrokeshire), however, the breaks are made with sufficient regularity and proximity to produce knots,




Eight-cord plaits, with cruciform breaks

and yet the knots themselves are not symmetrically placed. The result is a class of interlaced-work, intermediate between plaitwork with irregular breaks and



Six-cord plait, with cruciform
breaks
(Occurring at Llanbadarn
Fawr)



Ten-cord plait, with cruciform
breaks
(Occurring at St. Neudd
(Siarman))



Knots derived from a three-cord plait

knotwork. The same kind of thing is to be seen on the crosses at Coppleston, Devonshire ; and St. Neot, Cornwall.

If two horizontal breaks and two vertical breaks are made next to each other in a plait, a space in the shape of a cross is produced. A large number of the interlaced patterns used in Celtic decorative art are derived from a plait by making cruciform breaks at regular intervals. There are examples of this in Wales, at Neuadd Siarman, Brecknockshire ; Llanbadarn Fawr, Cardiganshire ; and Llantwit Major, Glamorganshire. It is not unlikely that symbolism had something to do with the frequent use of the cruciform break.

There are eight elementary knots which form the basis of nearly all the interlaced patterns in Celtic decorative art, with the exception of those already described. Two of the elementary knots are derived from a three-cord plait, and the remaining six from a four-cord plait.



Knot No. 1



Knot No. 2

Knot No. 1 is derived from a three-cord plait by making horizontal breaks on one side of the plait only, and **No. 2** by making horizontal breaks alternately on one side and the other.

Knot No. 3 is derived from a four-cord plait by making horizontal breaks in the middle of the plait.

Knot No. 4 is derived from No. 3 by making a horizontal break at A; and **No. 5** from No. 4 by making a vertical break at B and C.

Knot No. 6 is derived from a four-cord plait by making horizontal breaks in the middle of the plait, in the same way as in the case of knot No. 3, but closer together.



Knot No. 4



Knot No. 3



Knot No. 5



Knot No. 7



Knot No. 6




Knot No. 8

Knot No. 7 is derived from No. 6 by making a vertical break at B; and **No. 8** from No. 6 by making vertical breaks at B and C.

If a series of knots repeated in a single row can be derived from a plait of n bands, a series of the same knots repeated in a double row can be derived from a plait of $2n$ bands. Thus a pattern composed of knot

No. 1 arranged in a double row would be derived from a plait of six cords.

Knots like Nos. 3 and 4, which are longer than they are broad, can be placed either horizontally or vertically. Thus No. 3 placed with its longer axis vertical can be derived from a four-cord plait, but if placed horizontally it would be derived from a six-cord plait.




Method of deriving Knots Nos. 3 and 6 from a four-cord plait


Knot No. 2 does not occur on the Welsh crosses, and No. 1 only in a double row, as at Neuadd Siarman, Brecknockshire. This pattern is derived from a six-cord plait by making horizontal breaks in the two edges of the plait, and vertical breaks in the middle, the stages being shown on the annexed diagram.

Knot No. 3, in a single row placed with its longer axis vertical, occurs at Llandough, Glamorganshire, and, in a single row placed the other way, at Margam, Glamorganshire.


Examples of the two knots, Nos. 4 and 5, which are




Knots Nos. 4, 5, 7, and 8, derived from a four-cord plait



Knot No. 1, derived from either a three-cord or a six-cord plait



Knots 3 and 4, derived from a six-cord plait



Evolution of Knot No. 1 from a six-cord plait

derived from No. 3, are to be seen at Baglan, Glamorganshire, and Penally, Pembrokeshire.


Knot No. 6, in a single row, occurs at Llantwit Major, Glamorganshire, and its second derivative, No. 8, at Llantwit Major, and also at Neuadd Siarman, Brecknockshire. Its first derivative, No. 7, is only used in a double row on the Welsh crosses, as at Silian and Maes Mynach, Cardiganshire, and at Penally, Pembrokeshire, where the knots have an extra spiral twist. The direction of the twist of the spirally bent cord is the same in both the right-hand and left-hand vertical row of knots, although the positions of the knots are different. The more usual arrangement is to make the cords twist in opposite directions, as on the annexed diagram, in which the evolution of the pattern is shown. (Page 271.)

The clearest proof that the spiral knot No. 7 was developed from plaitwork in the manner explained is that on stones at Llangenydd, Glamorganshire; Whithorn, Wigtonshire; Abercorn, Linlithgowshire; and Aycliffe, Co. Durham; the successive stages of development can be easily traced.

I have coined the term *circular knotwork* to describe a particular class of interlaced-work, in which the circular curves made by the cords give the pattern its distinctive appearance. The best example of circular knotwork in any of the Hiberno-Saxon MSS. occurs on one of the ornamental cross-pages of the Book of Durrow.¹ Circular knotwork is not used in the decoration of the Irish ecclesiastical metalwork, probably because it is only suitable for application to larger

¹ J. R. Allen and J. Anderson's *Early Christian Monuments of Scotland*, p. lxxviii.; J. A. Bruun's *Illuminated Manuscripts of the Middle Ages*, pt. 1, "Celtic MSS.," p. 8.


surfaces than are to be found on comparatively small metal objects. Circular knotwork is characteristic of



Evolution of Knot No. 7 from an eight-cord plait

the Irish and Scottish sculptured monuments of the best period ; it is unknown in Cornwall and the Isle of Man and there is only one instance of its occurrence in

Wales. Very good examples of circular knotwork may be seen on sculptured monuments in Ireland¹ at Kells, Co. Meath; Monasterboice and Termonfechin, Co. Louth; Boho, Co. Fermanagh; Kilfenora, Co. Clare; and Drumcliff, Co. Sligo; and in Scotland² at Collieston, Sutherland (now in the Dunrobin Museum); Tarbet (now at Invergordon Castle), Brodie, Elginshire; Nigg, Ross-shire; Aberlemno, Monifieth (now



Evolution of Knot No. 7 from an eight-cord plait

in the Edinburgh Museum), and Eassie, Forfarshire; and Rossie Priory and St. Madoes, Perthshire.

The most common kinds of circular knotwork appear to have been evolved in the following manner. It has already been shown how knot No. 3 can be derived from a four-cord plait by making a series of horizontal breaks at regular intervals, leaving two crossing-points of the cords between each break; and how knot No. 4

¹ H. O'Neill's *Crosses of Ancient Ireland*.

² Allen and Anderson's *Early Christian Monuments of Scotland*.

can again be derived from knot No. 3 by making a horizontal break at the point A.



Knot No. 3




Knot No. 4

Now if a pair of knots like No. 4 be placed opposite each other thus—




and repeated in a vertical row, we get the pattern shown below.




T

By making pointed ends to the loops forming the knots and "sweetening" the curves of the bands between each knot the appearance of the whole is changed, and its development from the plait disguised. Almost all geometrical ornament is capable of conveying several different impressions to the mind according to the way it is observed by the eye for the time being, and the intellectual pleasure which a pattern gives is most probably dependent on the infinite variety of



Sections of pattern shown on p. 273

these kaleidoscopic changes. Taking this pattern for example, if the attention is concentrated upon the portions of the pattern between each of the points where the bands cross in the centre, it will seem as if



Knotwork from Ramsbury, Wilts, and Nigg, Ross-shire

the whole was formed of repetitions of knot No. 4; but if the attention be now directed towards the portions lying between the middle points of each of the





**ERECT CROSS-SLAB FROM COLLIEBURN, SUTHERLAND,
NOW IN THE DUNROBIN MUSEUM**

Photograph supplied by the Rev. J. M. Joss, LL.D., Honorary Curator


knots, the pattern will appear to consist entirely of circular curves with two diameters crossing each other diagonally.

When the circular knot thus obtained is repeated in a double row we get a comparatively simple pattern, in which the circular curves assume much greater prominence.

More complicated forms of circular knots can be derived from the elementary circular knot by combining it with a circular ring, either a larger one enclosing the four loops in the middle entirely, or a smaller one interlaced through the loops thus :—



Further variations can again be produced from these by severing the bands in places, and joining parts of the loops to the rings on the same principle that breaks can be made in a plait.



The connection between the different knots will at once become clear if they are drawn on separate pieces of tracing paper and placed one over the other.

Another kind of circular knotwork is formed by enclosing the simpler sort of knots derived directly from plaitwork within a circular band, which crosses over in one or two places and turns inwards to form the enclosed knots.



Circular knotwork from Tarbet, Ross-shire

The illustrations of the different kinds of circular knotwork from actual examples show the process of development.



Circular knotwork from Monasterboice, Co. Louth



DETAIL OF ORNAMENT ON ERECT CROSS-SLAB AT NIGG,
ROSS-SHIRE

*From photographs of the cast in the Science and Art Museum, Edinburgh,
supplied by Mr. Valance, Curator*

By the term *triangular knotwork* is meant interlaced patterns, the setting-out lines of which form triangles only or triangles and lozenges. The patterns are made by distorting the simple knots derived from plaitwork, so as to adapt them to the triangular shape. This species of knotwork is very seldom seen except in a few of the Hiberno-Saxon MSS. and on some of the sculptured stones of Ireland and Scotland. The best




Triangular knotwork from Ulbster, Caithness

examples are at Kilfenora, Co. Clare; Ulbster (now at Thurso Castle), Sutherlandshire; and Dunfallandy, Perthshire.

Under the head of ringwork and chainwork are included all patterns composed of circular, oval, and looped rings interlaced symmetrically round a centre, or arranged so as to form a long chain. Patterns of this kind are not found in the best Celtic work, and when they occur it is generally an indication either of Scandinavian influence or of the style being debased.

A certain number of modifications of the interlaced-work already described are produced by adapting the patterns so that they will fit into circular or annular spaces. Instances of this may be seen on the erect



Triangular knotwork from Dunfallandy, Perthshire

cross-slabs at Hilton of Cadboll (now at Invergordon Castle) and Nigg, Ross-shire; Glamis, Forfarshire; and Rossie Priory, Perthshire; and on the Lough Erne and Monymusk Reliquaries.

STEP-PATTERNS

A step-pattern is one which is formed of straight lines bent backwards and forwards at right angles so as to resemble a flight of steps. The lines are often

arranged symmetrically round a centre, so as to make cruciform and swastika designs, and the different parts are also generally shaded alternately black and white on the principle of chequerwork. Step-patterns hardly ever occur in Christian Celtic art except on the enamelled bosses of metalwork and in a few of the illuminated MSS., such as the Lindisfarne Gospels, the St. Gall Gospels (Codex No. 51), the Gospels of MacRegol, the Book of Kells, and the Book of Durrow. The step-patterns in the MSS. so nearly resemble those on the enamelled bosses on the Ardagh Chalice, the Tara Brooch, and the Cross of Cong, that there can be but little doubt the illuminators copied their designs from the enamels. In the Pagan Celtic enamels the ornament is nearly always curvilinear; but in the Christian Celtic enamels it is rectilinear, the arrangement of the *cloisons* being very similar to that on the Anglo-Saxon disc brooches incusted with small slabs of garnet, glass, etc. Instances have already been given in a previous chapter of the use of step-patterns by the Pagan Celts on the engraved woodwork from the Glastonbury Marsh Village (p. 161). The only instances I have met with of step-patterns on the sculptured stones of the early Christian period in this country are at Bradford-on-Avon, Wilts; and Dysert O'Dea, Co. Clare.

KEY-PATTERNS


The term *key-pattern* is used to describe a particular kind of rectilinear ornament which bears a certain amount of resemblance to the perforations in a key to allow it to pass the wards of a lock. The best-known key-pattern is the Greek fret. This is composed of what may be appropriately called straight-line spirals;



1



2



3



4

Key-patterns

- (1) Aberlady, Haddingtonshire
- (3) St. Andrews, Fifeshire

- (2) Abercorn, Linlithgowshire
- (4) Collieburn, Sutherlandshire



that is to say, straight lines (or, to speak more accurately, narrow straight bars) bent round into a series of right angles in the same direction. The space between the lines (or narrow bars) is generally about the same width as that of the line itself.

The key-patterns used in Christian Celtic art may be classified as follows :—

(1) *Square key-patterns*, in which the lines run horizontally and vertically parallel to the margins.

(2) *Diagonal key-patterns*, in which the lines run vertically parallel to the right and left margins, and diagonally in two directions at an angle of 45° to the margins.

(3) *Diaper key-patterns*, in which the lines run horizontally and vertically parallel to the margins, and diagonally in two directions at an angle of 45° to the margins.

The essential difference between the key-patterns used by the Egyptians, Greeks, and Romans and those used by the Christian Celts consists in the introduction of diagonal lines by the latter. Square key-patterns (*i.e.* those of the Greek fret type) were very seldom used in Christian Celtic art. There is, however, a very good example on one of the crosses at Penmon, Anglesey. The first step in the evolution of the Celtic key-pattern was to turn the Greek fret round through an angle of 45° so as to make the lines run diagonally with regard to the margins instead of parallel to them. Key-patterns in this stage of development are to be seen in the Lindisfarne Gospels, the St. Gall Gospels (Codex No. 51), and an Anglian cross-shaft from Aberlady, Haddingtonshire, now at Carlowrie Castle, near Kirkliston, Midlothian. It will be observed, however, that the result of changing a square key-pattern into a diagonal one is to leave a series of unornamented



1



2



3



4

Key-patterns

- (1) Rosemarkie, Ross-shire
(3) Gattonside, Roxburghshire

- (2) Farr, Sutherlandshire
(4) Nigg, Ross-shire

triangles all round the edge (p. 280). When these triangles are filled in by bending the ends of the diagonal lines round through an angle of 45° , so as to run parallel to the margins, we get such a characteristically Celtic key-pattern as the one on the great cross-shaft at St. Andrews, Fifeshire. Lastly, when the opposite ends of the diagonal lines in the middle of the panel are bent round in a similar manner, the most typical of all the Celtic key-patterns is arrived at, of which there is a very good example on the erect cross-slab at Farr, Sutherlandshire.


The filling in of the sharp corners made by the lines inclined to each other at an angle of 45° , with small black triangles (if in a MS.) or with sunk triangles (if on a sculptured stone) gives a decorative finish to the pattern, and still further adds to its distinctively Celtic character.

Next to interlaced-work the key-pattern is the



Shaft of Cross of Eudon, at Golden Grove, Carmarthenshire

most common motive made use of in the decorative art of the Christian Celtic period. It occurs in nearly all the Hiberno-Saxon illuminated MSS. and on a large proportion of the sculptured monuments in Ireland, Scotland, and Wales. Key-patterns and interlaced-




Detail of ornament on erect cross-slab at Rosemarkie, Ross-shire

work in combination, but without any other decorative motive, may be seen on the Welsh crosses at Carew and Nevern, Pembrokeshire; Golden Grove, Carmarthenshire; and Llantwit Major and Margam, Glamorganshire. On the metalwork of the period key-patterns seldom occur, except on the bronze bells, on a strap-buckle from Islandbridge, near Dublin, and on the Crucifixion plaque of repoussé bronze from Athlone, now in the Dublin Museum.

SPIRAL ORNAMENT


The spiral is the only decorative motive used in Christian Celtic art that can be proved to have been borrowed from the Pagan Celtic art of the preceding period. Although spiral ornament appears to be so complicated when it is completed, the geometrical process of setting it out is simplicity itself. All that it is necessary to do is to fill in the surface to be decorated



Methods of connecting spirals

with circles of any size, leaving about the same distance between each; then connect the circle with **S**- or **C**-shaped curves; and, lastly, fill in the circles with spirals working from the tangent points, where the **S** or **C** curves touch the circles, inwards to the centre. As the size of the circles is a matter of no importance, a surface of irregular shape may be covered with spiral ornament just as easily as one of symmetrical shape. In the flamboyant ornament of the Pagan Celtic period we have the same **S**- and **C**-shaped curves, but the circles were occupied either by a disc of enamel (as on

the bronze shield from the Thames), or by raised conchoids (as on the gold necklet from Limavady, Co. Londonderry). In the spiral ornament of the Christian Celtic period closely coiled spirals like those of the Bronze Age were substituted for the discs of enamel or raised conchoids. The background of the spirals, however, retained several of the prominent features of the repoussé metalwork, the effect of the light shining



Tree key-pattern, Meigle, Perthshire

on the raised trumpet-shaped expansions of the **S** and **C** curves being imitated in black and white or coloured by almond-like dots. In the later and less refined spiral ornament of the Christian period this background disappears altogether, and the spirals are made all the same size and placed close together.

As the spiral was the earliest decorative motive in Christian Celtic art, so it was also the first to disappear, and its disappearance marks the decadence of the style. We have in a previous chapter traced the spiral motive

from the Pagan metalwork through the enamelled disc ornaments of the bronze bowls of the Transition period to the illuminated MSS. of Christian times.



Spiral ornament, with key-pattern border, from the Book of Kells

Spiral ornament in its best form is to be found in the following MSS. :—

The Lindisfarne Gospels . . .	A.D. 720.
The Book of Kells . . .	8th century.
The Gospels of St. Chad . . .	” ”
The Book of Durrow . . .	” ”
The Book of Armagh . . .	A.D. 750-808.
The Gospels of Willibrod . . .	A.D. 739.
The Gospels of St. Gall . . .	8th or 9th century.
The Gospels of MacRegol . . .	A.D. 820.
The Gospels of Stockholm . . .	A.D. 871.
The Vespasian A. i. Psalter . . .	8th century.

In metalwork spiral ornament is less common than in the MSS., there being good examples on the Ardagh

Chalice, the Tara Brooch, the Hunterston Brooch, the Monymusk Reliquary, and the Athlone Crucifixion Plaque.

Spiral ornament of the best kind is found on the sculptured stone monuments only in Ireland and Scotland.¹ In Wales, Cornwall, and the Isle of Man spiral ornament is extremely rare, and when it does occur it is of debased character. Typical examples of spiral ornament may be seen on the sculptured



Method of connecting spirals

monuments in Ireland at Kells, Co. Meath; Monasterboice, Co. Louth; Clonmacnois, King's Co.; and Kilkispeen, Co. Kilkenny; and in Scotland at Nigg, Shandwick, Hilton of Cadboll (now at Invergordon Castle), all in Ross-shire; the Maiden Stone, Aberdeenshire; St. Vigean, Forfarshire; Meigle and Dunfallandy, Perthshire; and Ardchattan, Argyllshire.

Judging from the evidence afforded by the dated specimens, the best kind of spiral ornament seems to have disappeared entirely from Christian Celtic art after the first quarter of the tenth century.

ZÖOMORPHIC DESIGNS

Animal forms are used in Celtic art of the Christian period in three different ways, namely, (1) pictorially,

¹ Chiefly in the Pictish districts of the north-east of Scotland.



FOUR MEN PLACED STRASTIKA FASHION
ON RECUMBENT MONUMENT AT MEIGLE,
PERTHSHIRE
SCALE $\frac{1}{2}$ LINEAR



SPIRAL ORNAMENT ON FRAGMENT OF SCULPTURED STONE
FROM TARBET, ROSS-SHIRE; NOW IN THE
EDINBURGH MUSEUM

(2) symbolically, and (3) decoratively. As cases of the first kind of treatment we have the hunting scenes,¹ battle scenes,² men driving in chariots³ drawn by horses, groups of animals,⁴ etc., on the erect cross-slabs of Scotland and on the bases of some of the Irish and Welsh crosses. Although these subjects may have some symbolism behind them, yet all the living creatures represented are treated realistically, and not conventionally. As cases of the second kind of treatment we have the Symbols of the Four Evangelists, which, although consisting of the figures of a man, a lion, a bull, and an eagle, are generally highly conventionalised. Lastly, we have the decorative use of animal forms, where the zoölogical species of the creatures represented becomes of so little importance that it is altogether ignored. The creatures can certainly be divided into beasts, birds, fishes, and reptiles; but the artist has taken such liberties with the shapes of their bodies, limbs, heads, tails, and other details, that he would be a bold man who would say of any one of the beasts whether it was intended for a lion, a tiger, a dog, a wolf, or a bear. The quadruped most in favour with the Christian Celtic artist may, as has been already suggested, have been degraded by successive copying from the Classical lion. Anyway, it has a head something like that of a dog, with pointed ears, an attenuated body, four legs terminating in paws with claws, and a long tail. The head

¹ As on the erect cross-slab at Hilton of Cadboll (now at Invergordon Castle), Ross-shire.

² As on the erect cross-slab at Aberlemno, Forfarshire.

³ As on the base of the cross in the churchyard of Kells, Co. Meath.

⁴ As on the erect cross-slabs at Shandwick, Ross-shire; and St. Vigean, Forfarshire; and on the base of the cross at Castledermot, Co. Kildare.

and the paws are never misrepresented for decorative purposes, but the body, limbs, ears, and tail may be extended to any given length or bent in any desired direction. The beasts and other creatures are generally shown in profile, and only rarely in plan.

In the simplest kind of zoöomorphic ornament a single beast is used to fill a panel, the different attitudes being as follows :—

- (1) With the head looking forwards.
- (2) With the head bent backwards.
- (3) With the head bent backwards, biting the middle of the body.
- (4) With the head bent backwards, biting the end of the tail.
- (5) With the tail curled up over the back.
- (6) With the tail curled up under the belly.

If the beasts are in pairs, they may be placed in the following positions :—

- (1) Symmetrically facing towards each other, or face to face.
- (2) Symmetrically facing away from each other.
- (3) In a horizontal row one in front of the other.
- (4) In a vertical row one below the other.

When there are three or four beasts, besides being arranged in rows, they may be placed after the fashion of the triskele or the swastika round a centre.

Interlaced zoöomorphic ornament can be made with a single beast by extending the length of its tail and ear, and forming them into knots at intervals, crossing over the body and limbs where necessary. Sometimes the tail alone is knotted. In this sort of ornament the shape of the beast is seen distinctly and the knots occupy the background. A more complicated design

can be made from a single beast by twisting its body and limbs into knots as well as the ears and tail.

The panels of zoömorphie ornament in Christian Celtic art are, however, usually composed of two or more beasts placed symmetrically with regard to each other and having their bodies and limbs crossed over and interlaced. The ears and tails may also be extended and formed into knots in combination with the bodies and limbs. The designs thus produced will be seen to consist apparently of two sets of bands crossing each other diagonally, the wide bands being the bodies of the beasts and the narrow bands, the limbs, tails, and ears. The bands are nearly straight, or if bent at all only gently curved.

When the beasts are not placed in opposite symmetrical positions, but in horizontal rows one in front of the other, or in vertical rows one below the other, the bodies are often bent round spirally in one direction or twisted into S-shaped spirals in two directions. A favourite device with the Celtic artist was to make the beasts bite their own bodies, limbs, or tails, or the body, limbs, or tail of the beast immediately in front of it.

The zoömorphie designs composed of birds were arranged on the same principles as those composed of beasts.

Reptiles or serpentine creatures with bodies of nearly the same width throughout were converted into interlaced zoömorphie ornament by twisting, plaiting, looping, or knotting the bodies together. This class of ornament is, in fact, the ordinary interlaced patterns derived from the plait, with heads added at one end and tails at the other.

A very ingenious zoömorphie design is made by filling in a long narrow panel with the body of a

serpentine creature undulating from side to side. The head of the creature is at the top of the panel, and the body remains about the same width until it reaches the bottom of the panel, where its width is greatly reduced and its direction reversed. On its return journey it makes a series of Stafford knots, which fill in the spaces between the undulations of the body and the sides of the panel, and the end of the tail is finally received into the mouth of the reptile.¹

There are two kinds of zoöomorphic designs which are peculiar to the MSS. of the period, namely, initial letters made in the form of a bird or beast, and the incomplete frames round the initial pages of the Gospels terminating in a beast's head at one end and a fish-like tail at the other. The only thing of a similar kind which occurs on the sculptured monuments is the zoöomorphic margin round some of the erect cross-slabs of the east of Scotland.² The margin is formed by two beasts, the heads of which appear at the top facing each other and the tails at the bottom.

Zoömorphs are found throughout the whole range of Christian Celtic art; they form an important feature in the decoration of nearly all the Hiberno-Saxon illuminated MSS.; they are particularly characteristic of the Irish ecclesiastical metalwork; and they are of frequent occurrence on the sculptured monuments of Ireland and Scotland. On the crosses of Wales and Cornwall zoömorphs are comparatively rare. Some of

¹ Instances of this occur at Lanherne and Sancreed, Cornwall.

² At Cossins and Monifieth, Forfarshire; and Meigle, Dunfallandy; and St. Madoes, Perthshire. The arched top of the frame round the miniature of Christ seized by the Jews, in the Book of Kells, is treated in exactly the same way as the pedimented tops of the erect cross-slabs. In the second table of Eusebian Canons, in the Book of Kells, the head and arms of Christ are placed between the two beasts' heads.



DETAIL OF ORNAMENT ON ERECT CROSS-SLAB AT NIGG,
ROSS-SHIRE

the best instances of zoöomorphic designs in the MSS. are to be seen in the cross-pages of the Book of Durrow, the Gospels of Lindisfarne, the Book of Kells, the Gospels of St. Chad, and the St. Gall Gospels (Codex No. 51); in metalwork on the Ardagh Chalice, the Tara Brooch, the Hunterston Brooch, the Shrine of the Bell of St. Patrick's Will, the Cross of Cong, and the Shrine of St. Manchan; and on sculptured monuments at Termonfechin, Co. Louth; Kells, Co. Meath; Tihilly, King's Co.; Dysert O'Dea, Co. Clare; Nigg, Ross-shire; Aberlemno and Invergowie, Forfarshire; St. Madoes, Perthshire; Penally, Pembrokeshire; and Sancreed and Lanherne, Cornwall.

Sometimes key-patterns and spirals are converted into zoöomorphic designs by the addition of animals' heads, as at Penmon, Anglesey; and Termonfechin, Co. Louth. The centres of spirals are also often made zoöomorphic, as in the Gospels of Lindisfarne, on the cross at Kilklispeen, Co. Kilkenny, and on an erect cross-slab at St. Vigeans, Forfarshire.

Probably the most wonderful *tour de force* in the way of zoöomorphic sculpture is a pair of panels on the erect cross-slab at Nigg, Ross-shire. Each panel is ornamented with a series of raised bosses arranged symmetrically. The whole of the convex surfaces of the bosses is covered with intricate knotwork, and the background is composed of serpents, the tails of which coil spirally round the bases of the bosses, and in each case enter the circumference at three points to form the interlaced-work on the boss. After innumerable crossings under and over, the tails again diverge at three other points round the base of the boss, and finally terminate in small spirals in different parts of the background.

ANTHROPOMORPHIC DESIGNS

Under the above heading are classed all designs in which the complete figure of a man, or portions of a man are used for purposes of decoration. Human heads occur in metalwork in the decoration of the Tara Brooch¹ and in sculptured stonework on the cross of Muiredach, at Monasterboice, Co. Louth, and on a cross-head from the crannog at Drumgay Loch.

The most remarkable instances of the decorative use of the complete figures of men in the illuminated MSS. are to be found in the Book of Kells. The figures are generally arranged in pairs facing each other, in groups of three triskele fashion, and in nearly all cases the attitudes are extremely uncomfortable with the knees drawn up close against the stomach. The limbs of the different figures are crossed over and interlaced, as in zoöomorphic ornament, and the hands are shown grasping either the limbs, hair, or beard of one of the other figures. Sometimes the human figures are combined with figures of birds or beasts.

We have already referred to the incomplete frames of the initial pages of the Gospels with zoöomorphic terminations. In the "Nativitas \overline{XPI} " initial page in the Book of Kells the incomplete frame terminates in a human head at one end and two legs at the other. Another initial page in the same MS.—that of St. Mark's Gospel—has a zoöomorphic frame, but the beast's head is holding a man between its jaws, whilst the man is tugging at the beast's tongue with his hand.

Groups of four human figures arranged swastika fashion, interlaced and each grasping the limbs, wrists,

¹ A pin brooch ornamented with a human head, from Woodford River, Co. Cavan, is illustrated in Sir W. Wilde's *Catal. of the Mus. R.I.A.*, p. 565.

hair, or beard of one of the other figures, occur on crosses in Ireland at Kilkispeen, Co. Kilkenny; Monasterboice, Co. Louth; and Kells, Co. Meath; and in Scotland on a recumbent monument at Meigle, Perthshire. A human figure interlaced with a bird occurs in two instances on sculptured stones in Scotland, namely, at Monifieth, Forfarshire (now in the Edinburgh Museum of Antiquities); and at Meigle, Perthshire.

FOLIAGE

Leaf and plant motive decoration is entirely foreign to the spirit of purely Celtic Christian art, and whenever it occurs it is generally to be traced to Northumbrian influence. The Book of Kells and the Stockholm Gospels are the only Hiberno-Saxon illuminated MSS. in which any trace of foliage can be detected. There are panels of foliage on the Irish crosses at Kells, Co. Meath; Monasterboice, Co. Louth; and Clonmacnois, King's Co. In Wales there is an instance of foliage on the crosses at Penally, Pembrokeshire. In Scotland the only sculptured monuments with foliage upon them (excluding, of course, those in the Northumbrian districts of the south) are the erect cross-slabs at Hilton of Cadboll and Tarbet, Ross-shire (both now at Invergordon Castle); St. Vigean, Forfarshire; and Crieff, Perthshire; on crosses at Camuston, Forfarshire; Dupplin, Perthshire; and on a cross-shaft at St. Andrews, Fifeshire.

The foliage may in all cases be traced back to the Classical vine, the well-known symbol of Christ. It is often much degraded by successive copying, and although the forms of the leaves are often altered beyond recognition the bunches of grapes can always be made out.

SYMBOLICAL FIGURE-SUBJECTS

We have already mentioned most of the figure-subjects to be found in the Hiberno-Saxon illuminated MSS., and on the Irish ecclesiastical metalwork. It remains therefore only now to take the sculptured monuments into consideration.

It was in Ireland alone that a recognised cycle of scriptural figure-subjects was adopted for the decoration of the crosses and that in nearly all cases the ornament was relegated to a subordinate position. In Scotland and Wales, on the contrary, Scripture scenes are seldom represented on the sculptured monuments; in Cornwall the only figure-subject which occurs on the crosses is the Crucifixion; and in the Isle of Man the figure-subjects are mostly taken from the Pagan Norse mythology.

The following table shows the Scriptural subjects on the sculptured monuments of Ireland, Scotland, Wales, and Cornwall, and the frequency with which they occur:—

	Ireland.	Scotland.	Wales.	Cornwall.
<i>Old Testament—</i>				
Adam and Eve . . .	15	2	—	—
Noah in the Ark . . .	2	1	—	—
Sacrifice of Isaac . . .	9	1	—	—
Three Children in Furnace .	4	—	—	—
Daniel in Den of Lions .	8	9	—	—
David and Harp . . .	6	2	—	—
David and Lion . . .	6	2	—	—
David and Goliath . . .	3	—	—	—
Jonah and Whale . . .	—	3	—	—
Ascent of Elijah . . .	—	1	—	—

	Ireland.	Scotland.	Wales.	Cornwall.
<i>New Testament—</i>				
Virgin and Child	—	5	—	—
Adoration of Magi	2	1	—	—
Flight into Egypt	1	—	—	—
Baptism of Christ	2	—	—	—
Miracle of Loaves and Fishes	4	1	—	—
Raising of Lazarus	—	1	—	—
Crucifixion	16	5	3	40
Christ in Glory	5	1	—	—
Last Judgment	1	—	—	—
Annunciation	—	—	1	—
Christ seized by the Jews . .	2	—	1	—
Twelve Apostles	1	—	—	—
Agnus Dei	2	—	—	—
Dextera Dei	2	—	—	—

In addition to the above there are the following, which are sacred or ecclesiastical, but not, strictly speaking, Scriptural :—

	Ireland.	Scotland.	Wales.	Cornwall.
Symbols of Four Evangelists . .	—	4	—	—
Cherubim	—	—	1	—
Angels	—	22	—	—
Saints	—	—	—	—
Oranti	—	1	3	—

It appears, then, that the Scriptural subjects of most frequent occurrence in Ireland are the Crucifixion, Adam and Eve, the Sacrifice of Isaac, Daniel in the Lions' Den, and the scenes from the Life of David; and in Scotland, the Crucifixion, Daniel in the Lions' Den, the Virgin and Child, and the symbols of the four Evangelists.

The subjects common to both Ireland and Scotland are Adam and Eve, Noah (?), Sacrifice of Isaac, Daniel in the Lions' Den, David and the Harp, David and the Lion, Adoration of the Magi, Flight into Egypt, Miracle of Loaves and Fishes, Crucifixion, Christ in Glory, Agnus Dei, Angels.

The subjects which occur in Ireland, but not in Scotland, are the Three Children in the Furnace, David and Goliath, Baptism of Christ, Resurrection, Last Judgment, Dextera Dei, Twelve Apostles. And those which occur in Scotland, but not in Ireland, are Ascent of Elijah, Raising of Lazarus, Jonah and the Whale, Annunciation, Salutation, Miracle of Healing the Blind, Christ and Mary Magdalene, Lazarus.

Of the subjects on the early sculptured stones of Ireland and Scotland the following belong to the cycle of subjects found on the paintings in the Catacombs and the Sculptured Sarcophagi (A.D. 50 to 450):—

Adam and Eve.	Daniel in the Lions' Den.
Noah.	Jonah and the Whale.
Sacrifice of Isaac.	Adoration of Magi.
Three Children in the Furnace.	Miracle of Loaves and Fishes.
Ascent of Elijah.	Miracle of Healing the Blind.

The following subjects belong to the Lombardo-Byzantine period (A.D. 700–1100):—

David.	Christ in Glory.
Baptism of Christ.	Last Judgment.
Crucifixion.	Agnus Dei.
Resurrection.	Dextera Dei.
Flight into Egypt.	Twelve Apostles.
Virgin and Child (apart from Magi).	Symbols of the Four Evangelists.
Christ and Mary Magdalene.	Angels.

Thus the early Sculptured Stones and the Hiberno-Saxon MSS. of Great Britain, and the Carolingian Ivories afford a connecting link between the older symbolism of the primitive Christianity of the Catacomb period and the more strictly ecclesiastical art of mediæval times.

Quite apart from the fact that King David was a type of Christ, and that his pictures formed the illustrations of the Psalter, it is not surprising that he should have been an object of popular worship amongst the warlike and musical Celts, to one side of whose character his heroic deeds in rending the jaws of the lion and slaying the giant Goliath, would appeal as strongly as his talent as a harper would to the other.

A small MS. Irish Psalter in the British Museum (Vit. F. i.)¹ contains two very curious miniatures, one of David Playing the Harp and the other of David and Goliath.² The former is interesting, because I think it helps to explain the meaning of a figure sitting on the back of a beast and playing a harp,³ sculptured on one of the panels of the cross at Clonmacnoise. As I hold, this is intended for David; and my reason for supposing this is, because the throne on which David is seated in the miniature in the Psalter is conventionally treated as a beast.

I am not quite sure whether the boat with men in it, on the stone at Cossins, is intended for Noah's Ark or not, but a boat of just the same kind is represented on

¹ Westwood's *Miniatures*, pl. 5.

² In the miniature of David and Goliath in the Psalter David holds a sling in one hand and a beast-headed club in the other. The resemblance between this club and the beast's-head symbol, which occurs on the Norrie's Law silver ornaments and on several of the early incised slabs in Scotland, may be only accidental, but it is worth noting as a possible clue to the scriptural interpretation of the symbol.

³ O'Neil, pl. 24A.

a carved wooden pillar at Olaf's Church,¹ Nesland, where it is associated with other Scriptural subjects, amongst others the creation of Eve, Samson and Delilah, and David and Goliath. In this case there can be little doubt but that the boat is intended for Noah's Ark, so that probably the boat at Cossins has the same meaning.

The angels are cherubim, with four wings, and spirals where the wings join on to the body, representations of which are to be seen on the stones at Eassie, Glamis, and elsewhere in Scotland. They do not occur on any of the sculptured crosses in Ireland; but there are instances of angels or the symbols of the four evangelists treated in the same fashion in the St. Gall Gospels, Codex No. 51,² and on the Book Shrine of St. Molaise's Gospels,³ in the Museum of the Royal Irish Academy in Dublin, and also on a bronze plaque⁴ of the Crucifixion, in the same collection. I have recently discovered a very curious instance of an angel of this kind, with three wings on a cross-slab, with interlaced-work, in St. David's Cathedral, given in Westwood's *Lapidarium Walliæ* (pl. 63, fig. 4), but the wings and spirals only shown, and the head of the angel omitted.

The pair of ecclesiastics, sometimes standing, sometimes enthroned, sometimes kneeling, with a bird holding a circular disc in its mouth between them, is a subject common to the early sculptured stones of both Scotland⁵ and Ireland,⁶ but the exact meaning of it

¹ L. H. S. Dietrichsen, *De Norske Stavkirker*, p. 362.

² C. Purton Cooper's "Appendix A to Report on Rymer's Fœdera," pl. 5.

³ *Archæologia*, vol. xliii., p. 131.

⁴ Westwood's *Miniatures*, pl. 51.

⁵ As at Nigg and St. Vigean. Dr. J. Anderson regards the Nigg example as being intended for St. Paul and St. Anthony.

⁶ As at Kells, Moone Abbey, Clonca.

has yet to be ascertained if we are not to take the instance on the Ruthwell cross as an authoritative explanation of the whole.

As I have already pointed out in my Rhind Lectures on *Christian Symbolism*, there is a nearer affinity between the subjects chosen to decorate the bases of the Irish crosses and the representations of hunting scenes, horsemen, chariots, etc., on the upright cross-slabs of the north-east of Scotland, than the more strictly Scriptural scenes on the shafts of the Irish crosses. The best examples illustrating this are to be seen on the bases of the crosses at Kells (Figs. 5 and 6), Monasterboice, Clonmacnois, Castle Dermot (Fig. 7), and Kilklispeen.

The chariot on the Meigle slab, now lost, may be compared with the chariots to be seen on the shaft of the cross at Killamery, and on the bases of the crosses at Monasterboice, Kilklispeen, and in Kells churchyard; on the base of the cross in the street at Kells we have the eagle and fish, as on the "Drosten" stone at St. Vigean,¹ and as in the Book of Armagh; and on the base of this same cross, and on the cross of Muredach at Monasterboice, centaurs occur, in some respects like those on the slabs at Aberlemno, Meigle, and Glamis.

On the base of the Kilklispeen cross is portrayed a procession of ecclesiastics taking part in a most remarkable ceremony. On the south side of the base is to be seen a priest carrying a processional cross, and followed by a man leading a horse, on the back of which is laid the headless trunk of a man, with

¹ Another remarkable instance of the eagle and fish has recently been found on a stone with an Ogam inscription, at Latheron, near Keiss, Caithness.

two birds of prey, or carrion crows, perched on the top.

On the north side of the base are two ecclesiastics on horseback, followed by two more in a chariot drawn by a pair of horses.

On the east side are several beasts, birds, and a man.

On the west side is a central figure, perhaps a bishop, with three ecclesiastics holding croziers on each side of him.

These scenes can hardly be Scriptural; and if they are not taken from the life of some saint, it is difficult to see what explanation remains to be suggested, except that an event of local importance is here commemorated. The bases of the pillar-cross at Llandough and of the great wheel-cross at Margam, both in Glamorganshire, are the only ones with figures of horsemen upon them in Wales.

The symbolism of the shafts of the Irish crosses is so strictly biblical that secular subjects may have been placed on the bases by way of contrast, to indicate the actual world or earth on which the cross stood representing the spiritual world. The eagle and fish may personify the ocean, and the centaur the desert, for which we have the authority of the bestiaries and the legendary life of St. Anthony.

The points of similarity between the ornamental patterns on the stones of Ireland and Scotland raise questions of too much intricacy to be dealt with here; but it may be remarked that figure-sculpture forms the chief feature of the Irish crosses—geometrical, zoö-morphic, and foliageous designs being only as a rule applied to the decoration of the smaller panels on the sides of the shafts and to the rings connecting the

arms. The upright cross-slabs of Scotland, more particularly those in Ross-shire, approach much more nearly in style—and therefore probably in age—to the illuminated pages of the Hiberno-Saxon MSS. of the best period, than do any of the Irish crosses.

In conclusion, I consider the so-called Celtic style to be a local variety of the Lombardo-Byzantine style, from which the figure-subjects, the interlaced-work, the scrolls of foliage, and many of the strange real and fabulous creatures were apparently borrowed. The Lombardo-Byzantine style was introduced into this country after the Saxons had become Christians; and being grafted upon the Pagan art of the Late-Celtic period, was developed in different ways in different parts of Great Britain. However, it in no way detracts from the artistic capacity of the Celt that he should have adapted certain decorative motives belonging to a foreign style instead of evolving them out of his own inner consciousness. Although his materials may not all have been of native origin, they were so skilfully made use of in combination with native designs, and developed with such exquisite taste, that the result was to produce an entirely original style, the like of which the world had never seen before.

INDEX

Abercorn, cross-shaft, 269
 Abergele, horse-trappings, 95
 Aberiemno, erect cross-slab, 184
 Abernethy, 82
 Abingdon, pottery, 124
 Aboyne, armlet, 113
 — erect cross-slab, 184
 Achnabreac, spirals at, 50
 Ægean, spiral ornament in the, 54
 Æsica, 82
 — fibula, 152
 Alfriston, horse-trappings, 94
 — enamelled harness-ring, 134
 Algeria, penannular brooch, 225
 Allington, pottery, 124
 Alstonfield, Iron Age burial at, 68
 Amber settings, 237
 Amerden, sword-sheath, 91
 Ammendola, sarcophagus of, 6
 Andrews, St., sarcophagus, 193
 Angels, 300
 Animals, figures of, 146
 Antennæ, swords with, 86
 Anthony, St., 302
 Anthropomorphic designs, Late-Celtic, 144
 Anthropomorphs in Celtic Christian art, 294
 Apollinare in Classe, Sant', Ravenna, 244
 Archdall, Castle, spirals at, 51
 Ardagh, chalice, 216, 235
 Ardakillen Crannog, 81
 — fibula, 170
 Ardchattan, erect cross-slab, 184
 Ardoch, 82
 — horse-trappings, 95
 Aristotle, 2
 Armagh, bell, 199
 — Book of, 175
 — shrine of Book of, 208

Armlets, enamelled, 134
 — Late-Celtic, 113
 — of glass, Late-Celtic, 141
 Arria and Paetus, 5
 Arras, armlet, 114
 — horse-trappings, 94
 — Iron Age burials at, 63
 — mirror, 115
 Aryans, 1
 Aspatria, sculptured cist, 55
 Assynt, jet necklace from, 42
 Aston Clinton, pottery, 124
 Athenry, dagger-sheath, 92
 Athlone, Crucifixion, 218
 Auchendolly, horse-trappings, 95
 Auchenbadie, armlet, 113
 Avebury, fibula, 106
 Axe-head of bronze with spirals, 52
 — sculptures, 55
 Aycliffe, cross-shaft, 269
 Aylesford, bucket, 116, 145
 — fibula, 106
 — Iron Age cemetery at, 70
 — pottery, 122
 — tankard, 116
 Ayton Moor, cup-marks at, 57
 Backworth, pair of fibulæ, 103
 — saucepan, 117
 Badony, Lower, bell, 198
 Baglan, cross-slab, 182
 Bakerhill, sculptured cist, 55
 Balcalk, jet necklace from, 42
 Ballinderry Crannog, 81
 — comb, 128
 Balmaclellan, Late-Celtic finds at, 77
 — mirror, 115
 Balls, stone, of Bronze Age, 50
 Ballycostello, horse-trappings, 95
 Ballynaminton, horse-trappings, 95

- Bandaging patterns, 38
 Bangor, bell, 201
 Bapchild, horse-trappings, 94
 Bargany House, sword-sheath, 91
 Barlaston, bowl, 58, 166
 Barlaston, Iron Age burial at, 68
 Barrington, enamelled bowl, 135
 Barrochan, cross, 192
 Bartlow Hills, enamelled vessel, 138
 Basketry, Late-Celtic, 143
 Battersea, shield, 92
 — sword-sheath, 91
 Beaded torques, 159
 Beads, Late-Celtic, 125 141
 Belhelvie, armllet, 113
 Bells, Celtic, 194
 Bell-shrines, 204
 Bently Grange, enamelled bowl, 134
 — Iron Age burial at, 67
 Berkshire, triskele pendant, 121
 Bernaldby Moor, sculptured cist, 55
 Berru, helmet from, 12
 Beverley, Iron Age burials at, 65
 Bibracte, enamels from, 138
 Bigbury Camp, 82
 Birdlip, bowl, 116
 — fibula, 106
 — Iron Age burials at, 69
 — mirror, 115
 Birnie, bell, 198
 Birrenswark, 82
 Birrenswark, horse-trappings, 95
 Biskra, penannular brooch, 225
 Black Hedon, cup-marks at, 57
 Blackshaw, spirals at, 50
 Blathmac, crozier, 208
 Boars' tusks from Arras, 64
 Bones, engraved, 150
 Bonework, Late-Celtic, 127
 Bonville, fibula, 106
 Book-shrines, 208
 Bowl, Barlaston, 166
 — Chesterton, 167
 — enamelled, Möklebust, 160
 Bowls, Late-Celtic, 116
 — with enamelled handles, 134
 Boxmoor, sword-sheath, 91
 Braddan, Kirk, wheel-cross, 188
 Braintree, pottery, 124
 Braughing, enamelled vessel, 137
 Brazing, 132
 Breac Moedoc, 211
 Breaks in plait, 259
 Bride, Kirk, cross, 186
 Bridle-bit, enamelled, Rise, 133
 — — Birrenswark, 133
 Brighton, pottery, 125
 Brodie, erect cross-slab, 184
 Brighter, Limavady, find of gold ornaments, 109
 Brooch, penannular, 223
 Bronze Age burials, 23
 — — Celtic art in, 22
 — — Celts, 15
 — — chronology of, 19
 — — patterns which survived into the Iron Age, 60
 Brough, 82
 Brough, fibula, 107, 154
 Brythons, 17
 Buckets, 145
 — Late-Celtic, 116
 Burghead, 82
 Burials of Iron Age, 65
 Bunrannoch, armllet, 113
 Byzantine art, 239, 244
 Caburn, Mount, Late-Celtic oppidum at, 74
 Caistor, enamelled bowl, 135
 Calderstones, spirals at, 50
 Camborne, cross-slab, 182
 Came Down, cup-marks at, 57
 Camerot Muir, spirals at, 50
 Canterbury, châtelaine, 115
 — horse-trappings, 94
 Capel Garmon, fire-dogs, 118, 141
 Cappagh, bell, 199
 Carew, cross, 193
 Carham, sword-sheath, 91
 Carlingwark Loch, tankard, 116
 Carlswark Cavern, armllet, 114
 Carlton, inlaid object, 139
 Carnbân, sculptured cist, 55
 Carn Brê, 16
 Carnwath, sculptured cist, 55
 Cashel, bell, 201
 Castell Nadolig, 82
 Casting metal, Iron Age, 130
 Castle Dermot, 192
 Castle Newe, armllet, 113
 — — weem at, 82
 — — enamelled armllets, 134
 Castlethorpe, armllet, 114
 Catterdale, sword-sheath, 91
 Cauldrons of bronze, 86
 Caves inhabited by Brit-Welsh, 75, 81

- Celtæ, 4
 Celtic tribes in Britain, 17
 Celt in classical sculpture, 5
 Celts of bronze, 41
 Centaur, 302
 Certosa situlæ, 145
 Chad, St., Book of, 175
 Chains, 237
 — of gold and silver, Late-Celtic, 139
 Chalice, Celtic, 215
 Chalk drums from Folkton, 56
 Champlévé enamel, 136
 Characteristics of Celtic Christian style, 254
 — Late-Celtic style, 143
 Chariots, 301
 — wheels, 98
 — wheels from Arras, 64
 Châtelaines, Late-Celtic, 115
 Chedworth, Chi-Rho Monogram, 162
 Chequerwork, Late-Celtic, 160
 Cherubim, 300
 Chesterford, Great, Kimmeridge shale vessel, 128
 Chesters, Great, fibula, 107
 Chesterton, bowl, 167
 — enamelled bowl, 135
 Chevron patterns, 28
 — — Late-Celtic, 160
 Chi-Rho Monogram, 163
 Chorley, chains, 140
 — pair of fibulæ, 102
 Christianity in Britain, 162
 Chronology of Bronze Age, 19
 Circles, concentric, in Bronze Age, 55
 Circular knotwork, 273
 Cirencester, fibula, 107
 Cists of Bronze Age with sculpture, 55
 Cividale, Baptistery of Calistus, 258
 Cloughton Moor, cup-marks at, 57
 Clemente, San, Rome, 244, 258
 Clogher, fibula, 105
 — bell, 199
 Cloisonné enamel, 136
 Clonmacnois, 190
 — cross-slabs, 180
 — crozier, 207
 — gold collar, 111
 — pin, chains, 140
 — pin, 219
 Clooncunra, horse-trappings, 95
 Clova, horse-trappings, 95
 Clyde Crannog, comb, 128
 Coins, ancient British, 77
 — with Late-Celtic finds, 88
 Cookham, dagger-sheath, 92
 Colchester, Kimmeridge shale vessel, 128
 Commios, coins of, 78
 Corfe Castle, Kimmeridge shale vessel, 128
 Cowlam, fibula, 106
 Cochno, wheel symbol at, 59
 Coffey, George, theory on spiral ornament, 53
 Coffins, stone, 193
 Coilsfield, spirals at, 50
 — sculptured cist, 55
 Coinage, Celtic, 14
 Collar, Late-Celtic, 153
 Collars, Late-Celtic, 109
 Colours used by Celtic scribes, 233
 Columba's Psalter, shrine of, 209
 Compass-work in Late-Celtic art, 150
 Cong, cross, 213
 Coped stones, 182
 Copenhagen, reliquary, 211
 Coral settings, 237
 Cossins, erect cross-slab, 184
 Courcelles-et-Montagne, 13
 Cowlam, armet, 114
 — Iron Age burials at, 65
 Craigie Wood, sculptured cist, 55
 Craigywarren, pin, 108
 Crannogs, 81
 Craven Arms, châtelaine, 115
 Crawfordjohn, silver chains, 170
 Cremation in Bronze Age, 23
 Crichtie, horse-trappings, 95
 Cricklade, fibula, 106
 Crosby Ravensworth, spoons, 120
 Cross, Celtic, evolution of, 186
 — processional, 213
 Cross-slabs, 181
 Crossthwaite, enamelled bowl, 134
 Croy, penannular brooch, 228
 Croziers, Celtic, 206
 Cruciform breaks in plait, 262
 — patterns, 236
 Crucifixion plaques, 218
 Crystal settings, 237
 Cuerdale, penannular brooch, 227
 Culan, St., bell-shrine, 204

- Culbin Sands, armlet, 113
 Cumdachs, 208
 Cup-and-ring sculpture at Ilkley, 59
 — — Wooler, 59
 — — Kirkcudbright, 59
 — — Lochgilphead, 59
 — — Kilmartin, 59
 Cup-marked stones, 57

 Danes' Graves, horse-trappings, 94
 — — Iron Age burials, 65
 — — pin, 107
 Dartmoor, 16
 Datchet, fibula, 106, 139
 Dates of Late-Celtic finds, 85
 Decorative motives in Bronze Age,
 23
 Delphi sacked by the Gauls, 4
 Denmark, spiral ornament in, 51
 Deepdale Cave, 76, 81
 — looped wire armlets, 139
 Diagonal lines, use of, 60
 — setting-out lines, 255
 Dimma's Book, shrine of, 209
 Discs of repoussé bronze, Late-
 Celtic, 121
 Dogmael's, St., 18
 Dogs, fire-, 141
 — — Late-Celtic, 118
 Dorchester, sword-sheath, 91
 Dornoch Links, cup-marks at, 57
 Dots, rows of, in decoration, 39
 — use of, 60
 Dowalton Crannog, 81
 — horse-trappings, 95
 Dowkerbottom Cave, fibula, 107
 Dowth, spirals at, 50
 Drinking-cup urns, 25
 Drumcliff, cross, 192
 Drumragh, bell, 199
 Dunfallandy, erect cross-slab, 184,
 277
 Dunkeld, Little, bell, 198
 Dupplin, cross, 192
 Durrow, cross, 192
 — Book of, 169, 174
 — shrine of Book of, 208
 Dyce, erect cross-slab, 184
 Dysert, crozier, 208

 Eagle and fish, 301
 Ecclesiastics, 301
 Eday, spirals at, 50
 Egypt, spiral ornament in, 54

 Eilean Finan, bell, 198
 Eliseg's Pillar, Valle Crucis, 193
 Elkstone, cup-marks at, 57
 Elveden, pottery, 124
 — tankard, 116
 Embleton, sword-sheath, 91
 Embsay, collar, 111
 Emlagh, horse-trappings, 95
 Enamelling, Iron Age, 133
 — process of, 135
 Enamels of Christian Celtic period,
 235
 Engraved patterns, Iron Age, 132
 Eppillos, coins of, 78
 Essex, pottery, 122
 Evolution of Celtic cross, 186

 Farley Heath, 82
 — fibula, 107
 Farnell, cross-slab, 184
 Farr, erect cross-slab, 184
 Fens, the, horse-trappings, 94
 Fibula, evolution of, 99
 — from Æsica, 152
 Fibulæ, enamelled, 134
 — disc-shaped, 154
 — worn in pairs with chain, 104
 Figure drawing in Celtic Christian
 art, 256
 Figure-subjects in Celtic Christian
 art, 296
 Filigree-work, 237
 Finds, Late-Celtic, dates of, 85
 — — geographical distribution of,
 79
 — — with coins, 88
 — of Iron Age, nature of, 61
 Fire-dogs, 141
 — Late-Celtic, 118
 Firth, spirals at, 50
 Flamboyant ornament, Late-Celtic,
 150
 Flasby, sword-sheath, 91
 Flutes, Late-Celtic, 118
 Foliage in Celtic Christian art, 247,
 294
 — in Late-Celtic art, 148
 Folkton, chalk drums from, 56
 Food-vessel urns, 25
 Ford West Field, sculptured cist, 55
 Forres, erect cross-slab, 184
 Forteviot, bell, 198
 Frampton, Chi-Rho Monogram,
 163

- Galati, 4
 Gall, St., Gospels of, 177
 Galli, 4
 Garton, bell, 198
 Gaulcross, pin, 108
 Gauls, Cisalpine, 13
 Geographical distribution of Late-Celtic finds, 79
 Ghegan Rock, comb, 128
 Giacomo, San, Venice, 245
 Gilton, mirror, 115
 Giorgio, San, di Valpolicella, 244, 258
 Gladiator, the Dying, 5
 Glamis, erect cross-slab, 184
 Glass, Late-Celtic, 125, 141
 — settings, 237
 Glastonbury Lake-Dwellings, 72, 81
 — Lake Village, pottery, 142
 — — — woodwork, 147, 161
 — Marsh Village, pottery, 125
 — — — woodwork, 126
 — — — bowl, 117
 Glencolumbkille, spirals at, 51
 Glencotho, sword-sheath, 91
 Glenfahan, Ogam stone, 165
 Gobnet, St., stone of, 165
 Goidelic Celts, 15
 Goidels, 17
 Golden Grove, cross, 261
 — — cross-shaft, 282
 Golspie, erect cross-slab, 184
 Gorge-Meillet, helmet from, 12
 Gospels, 173
 Goulien, bell, 199
 Gourdon, chalice, 215
 Govan, sarcophagus, 193
 Grækwyl, 13
 Grange of Conan, weem at, 82
 — — armlet, 113
 Greenloan, cup-marks at, 57
 Greenwich, enamelled bowl, 135
 Grimspound, 16
 Grimthorpe, Iron Age burial at, 65
 — sword-sheath, 91
 Guthrie Castle, bell-shrine, 204
- Hagbourne Hill, horse-trappings, 95
 — — Late-Celtic finds at, 76
 Hällristningar, 60
 Hallstatt, cemetery of, 7
 — situlæ, 145
 — type, objects of, found in Great Britain, 86
- Hambledown Hill, 82
 Ham Hill, 82
 Hamdon Hill, horse-trappings, 95
 — — Late-Celtic finds at, 76
 Hammer-headed pins, 108
 Hammersmith, fibula, 106
 Hand-grasping figures, 294
 Harness-mountings, 98
 — enamelled, 134
 Harness-rings, enamelled, 134
 — Late-Celtic, 96
 Harry, broch of, 82
 Houghton - le - Skerne, sword-sheath, 91
 Hay Hill, fire-dogs, 118
 Head ornaments for horses, 98
 Hecataeus, 2
 Helen's, St., Chi-Rho Monogram, 163
 Helmet from Berru, 12
 — from Gorge-Meillet, 12
 Helmets, Late-Celtic, 93
 Henshole, horse-trappings, 95
 Herodotus, 2
 Hexagon patterns, 36
 High Crosses, 188
 Highfield Pits, pottery, 125
 Hilton of Cadboll, erect cross-slab, 184
 Hinksey, N., dagger-sheath, 92
 Hitchin, pottery, 124
 Hod Hill, 82
 — — fibula, 106
 — — sword-sheath, 91
 Hollows Tower, spirals at, 50
 Hook-and-disc ornaments, Late-Celtic, 121
 Horns with terminal knobs, 148
 Horse's head ornaments, 98
 Horse-trappings from Arras, 64
 — Late-Celtic, 94
 Hounslow, figures of animals, 146
 Hunsbury, fibula, 106
 — Late-Celtic oppidum at, 73
 — pottery, 125
 — sword-sheath, 132
 — sword-sheath, 91, 97
 — triskele pendant, 121
 Hunterston, brooch, 231
 Hyndford Crannog, 81
 — — collar, 112
- Iberians, 15
 Icklingham, sword-sheath, 91

- Ilkley, cup-and-ring sculpture, 59
 — rock-sculptures at, 57
 Incense-cup urns, 25
 Inchbrayock, erect cross-slab, 184
 Ingoe, cup-marks at, 57
 Inhumation in Bronze Age, 23
 Inishkeel, bell, 203
 Ink used by Celtic scribes, 232
 Iona, cross, 192
 Insh, bell, 198
 Interlaced-work, 246
 — evolution of, 257
 Invergowrie, erect cross-slab, 184
 Ireland, spoons, 121
 Italo-Greek objects found at Aylesford, 71
 Iron Age finds, 61

 Jet necklaces, 42
 Jezerine, chains, 140
 Just, St., Chi-Rho Monogram, 163

 Kells, Book of, 174
 Kells, cross, 192, 224, 233
 — crozier, 207
 — shrine of Book of, 208
 Kelko Cave, 76, 81
 Kent's Cavern, 76, 81
 — — pottery, 125
 Keshkerrigan, bowl, 117
 Keston, 16
 Kettleburn, broch of, 82
 Key-patterns, 278
 Kilbroney, bell, 198
 Kilburn, cup-marks at, 57
 Kildalton, cross, 192
 Kildare, Co., penannular brooch, 228
 Kilfenora, cross, 192
 Kilkeeran, horse-trappings, 95
 Kilklispeen, cross, 192
 Killarney, crozier, 207
 — gold lunula from, 40
 Killeen Cormac, Ogam stone, 165
 Killing Hill, spirals at, 51
 Kilmainham, bell, 198
 Kilmartin, cup-and-ring sculpture, 59
 — sculptured cist, 55
 Kilmichael Glassary, bell-shrine, 204
 Kilnsea, fibula, 107
 Kimmeridge shale objects, Late-Celtic, 128
 Kingsholm, pottery, 125
 Kingsholm, triskele pendant, 121
 King's Mountain, spirals at, 50
 Kingston Down, enamelled bowl, 135
 Kirkby Thore, fibula, 107
 Kirkcudbright, cup-and-ring sculpture, 59
 Kirkhead Cave, 75, 81
 Kirkly Thore, 82
 Kirkmadrine, Chi-Rho Monogram, 163
 Kirk Whelpington, cup-marks at, 57
 Kirriemuir, horse-trappings, 95
 Kit's Coty House, pottery, 124
 Knobs on horns of beasts, 148
 Knockmany, spirals at, 51
 Knot, spiral, 270
 Knots used in Celtic art, 265
 Knotwork, circular, 273
 — triangular, 276

 Lactin's, St., Arm, shrine of, 210
 Lagore Crannog, 81
 — — beads, 125
 — — comb, 128
 — pin, 108
 Lake-dwellings, 81
 Lake-dwellings at Glastonbury, 72
 Lanivet, coped stone, 182
 Lashing patterns, 38
 Late-Celtic finds, dates of, 85
 — — geographical distribution of, 79
 — — with coins, 88
 — style, 143
 La Tène, oppidum of, 9
 Latheron, eagle and fish, 301
 Lattice-work patterns, 34
 Leather-work, 237
 Leicester, horse-trappings, 94
 Lilburn Hill, spirals at, 50
 Limavady, gold chains, 139
 Limavady, gold collar, 109, 153
 Lincoln, sword-sheath, 91
 Lindisfarne Book, 177
 Linlithgowshire, enamelled patera, 137
 Lismore, crozier, 207
 Lisnacrogghera Crannog, 81
 — — sword-sheath, 148
 — sword-sheath, 91
 Llanbadarn Fawr, cross, 193
 Llanbedr, spirals at, 50
 Llanfair, spoons, 121

- Llandough, cross, 193
 Llandyssyl, collar, 111
 Llangenydd, cross-shaft, 270
 Llangystenyn, bell, 198
 Llangwynodl, bell, 200
 Llanrhyddlad, bell, 198
 Llantwit Major, cross, 186, 261
 Lochar Moss, bowl, 116
 — — collar, 111
 Lochgilphead, cup-and-ring sculpture, 59
 Lochlee Crannog, 81
 — — woodwork, 127
 — horse-trappings, 95
 Lonan, Kirk, wheel-cross, 188
 London, enamelled harness-ring, 134
 — fibula, 106
 — horse-trappings, 94
 — spoons, 120
 — sword-sheath, 91
 Looped wirework, 139
 Lorrha, bell, 201
 Loughcrew, spirals at, 50
 Lough Erne, reliquary, 210
 Lough Lene Castle, bell, 201
 Loughnashade, trumpet, 118
 Lough Ravel Crannog, beads, 125
 Lozenge patterns, 32
 — — Late-Celtic, 160
 Lullinstone, enamelled bowl, 135
 Lunulæ, gold, 41
 Lumphanan, stone ball from, 50

 MacDurnan, Gospels, 175
 MacRegol, Gospels of, 175
 Madoes, St., erect cross-slab, 183
 Maen Achwyfan, cross, 193
 Maes Mynach, cross-shaft, 270
 Magny Lambert, 12
 Maiden Castle, 82
 Maiden Stone, erect cross-slab, 184
 Maltbeck, enamelled vessel, 138
 Malton, fibula, 107
 Malton, New, 82
 Marlborough, bucket, 116
 Mancha, La, spirals at, 50
 Manchan, St., shrine of, 212
 Manuscripts, illuminated, 173
 Margam, cross, 186
 Marlborough bucket, 144
 Marne, La, cemeteries of, 11
 Materials for study of Celtic art in Bronze Age, 22

 Materials for study of Celtic art in Iron Age, 90
 Materials for study of Celtic Christian art, 172
 Materials used by Celtic sculptors, 233
 Maughanby, cup-marks at, 57
 — spirals at, 50
 Maughold, Kirk, cross, 186
 Meigle, coped stone, 182
 — erect cross-slab, 184
 Melfort, jet necklace from, 42
 Metallurgy, Iron Age, 130
 Metals used by Christian Celts, 234
 Metal-work, Christian Celtic, 194
 Methods employed by Celtic sculptors, 233
 Methods employed by Celtic metalworkers, 234
 Mevagh, wheel and symbol at, 50
 Middleby, horse-trappings, 95
 Middleton Common, Iron Age burial at, 67
 Middleton Moor, enamelled bowl, 134
 — — jet necklace from, 42
 Migvie, erect cross-slab, 184
 Mirrors, Late-Celtic, 115
 Mirror, Trelan Bahow, 131
 Mogue, St., bell-shrine, 204
 Möklebust, enamelled bowl, 160
 Molaise's Gospels, shrine of, 209
 Monasterboice, cross, 190, 224
 Monifieth, erect cross-slab, 184
 Monogram, Chi-Rho, 163
 Moone Abbey, cross, 192
 Mont Beuvray, enamels from, 138
 — — pottery, 141
 Monuments, sculptured, of Christian period, 180
 Monymusk, reliquary, 210
 Moresby, pin, 108
 Moreton Hall, sword-sheath, 91
 Morwick, spirals at, 50
 Motives, decorative, in Bronze Age, 23
 Motives used in Christian Celtic art, 242
 Mount Batten, Iron Age cemetery at, 70
 Mount Bures, fire-dogs, 118
 Mount Caburn, pottery, 125
 Mountings for harness, 98

- Mowroad, collar, 111
 Mura, St., bell-shrine, 204
 Mycenæan art, 57
- Nancy, chalice, 215
 Navan Rath, fibula, 106
 Necklaces of jet, 42
 Needham Market, enamelled bowl, 135
 Neolithic dwellings, 16
 Neuadd Siarman, cross, 190
 Nevern, cross, 191
 Newcastle, chains, 140
 Newgrange tumulus, 43
 Newry, armlet, 113
 Niello, 235
 Nigg, erect cross-slab, 182
 Norrie's Law, leaf-shaped plates, 170
 — — pin, 108
 Northfield, Late-Celtic village, 82
 Norton, enamelled fibula, 134
 — enamelled harness-rings, 134
 — horse-trappings, 94
- Ogam-inscribed stones, 165
 Okstrow, broch of, 82
 — tankard, 116
 Old Parks, tumulus, 56
 Orange, Triumphal Arch of, 5
 Orchomenos, spiral ornament at, 54
 Origin of early Christian art, 238
 Ornovasso, chains, 140
 Orton Scar, penannular brooch, 227
 Over-Haddon, enamelled bowl, 134
 Oxford, enamelled bowl, 135
- Pails, Late-Celtic, 116
 P and Q Celts, 18
 Panels, ornament arranged in, 255
 Papil, erect cross-slab, 184
 Parisi, 12
 Patera, enamelled, 137
 Patrick's Will, St., bell-shrine, 204
 Patrick's, St., Gospels, shrine of, 209
 Penally, cross, 193
 Penannular brooch, 223
 Pen Arthur, cross-slab, 181
 Penbryn, spoons, 121
 Penmachno, Chi-Rho Monogram, 163
 Penmon, cross, 185
- Pens used by Celtic scribes, 232
 Pentre Poeth, Ogam stone, 165
 Perdeswell, collar, 111
 Perfection of details of Celtic ornament, 256
 Perforated metal plates, 236
 Pergamos, 5
 Perth, penannular brooch, 231
 Philostratus, 133
 Pins, Celtic, 219
 — hammer-headed, 108
 — Late-Celtic, 107
 Pitalpin, armlet, 113
 Pitkelloney, armlet, 113
 — enamelled armlets, 134
 Plait, cruciform breaks in, 262
 — horizontal and vertical breaks in, 259
 Plaques with Crucifixion, 218
 Plato, 2
 Plaitwork, 259
 Plunton Castle, armlet, 113
 Polden Hill, enamelled harness-ring, 134
 — — fibula, 106
 — — horse-trappings, 95
 Pol de Léon, St., bell, 201
 Polybius, 3
 Poole's Cave, 76, 81
 Port-Blanc, dolmen, 39
 Portland, Isle of, collar, 111
 Pottery, Late Celtic, 121, 142
 — painted, Mont Beuvray, 141
 — sepulchral, in Bronze Age, 24
 Prasede, San, Rome, 258
 Presles, enamels from, 138
 Prickwillow, saucepan, 117
 Processes, technical, in Celtic Christian art, 232
 — — Iron Age, 129
 Psalter of St. John's College, Cambridge, 178
 — Vesp. A. i., 178
 — Vit. F. xi., 178
 Psalters, 176
 Pymont, enamelled vessel, 138
 Pytheas, 3
- Rathconrath, wooden bowl, 127
 Ravenna, screen, 245
 Reask, inscribed stone, 166
 Rectilinear patterns in Late-Celtic art, 159
 Redlands, sculptured cist, 55

- Relic shrines, 210
 Repoussé metal-work, Iron Age, 132
 Rhayader, gold armlet, 170
 Ribchester, 82
 — fibula, 107
 Ricemarchus, Psalter of, 176
 Ringham Low, fibula, 106
 Rings for harness, 96
 Rise, horse-trappings, 94
 Risingham, 82
 — enamelled fibula, 134
 — fibula, 107
 Riveting, Iron Age, 132
 Rock-sculpture in Scandinavia, 60
 Rodenbach, 13
 Rogart, penannular brooch, 228
 Rome taken by the Gauls, 4
 Rosemarkie, erect cross-slab, 184, 283
 Rossie Priory, erect cross-slab, 184
 Rotherley, 82
 Round towers, 196
- Sadberge, sword-sheath, 91
 Safety-pin type of fibula, 100
 Saham Toney, cruciform harness-mounting, 98
 — — enamelled harness-mounting, 143
 — — horse-trappings, 94
 Saltire patterns, 35
 Sandy, pottery, 124
 Sarcophagi, 193
 Saucepans, Kelto-Roman, 117
 Scandinavia, rock-sculpture in, 60
 — spiral ornament in, 51
 Scandinavian features in Celtic art, 252
 Scatterry Island, bell, 198
 Scribes, pens, ink, etc., used by, 232
 Scripture subjects in Celtic art, 296
 Sculptured monuments of Christian period, 180
 Sculptured stone at Newgrange, 49
 Sculptured stones, Late-Celtic, 128
 Sculpture on Bronze Age cists, 55
 Seafeld Tower, armlet, 113
 Seal-box, enamelled, 134
 Seamill Fort, 82
 — — triskele pendant, 121
 Sepulchral remains of Iron Age, 63
 Seskin, sculptured cist, 55
 Sesto-Calende, 9
- Settings of coral, amber, glass, and crystal, 237
 Shading, kinds of, in Late-Celtic art, 156
 Shandwick, erect cross-slab, 184
 Sheen, cup-marks at, 57
 Shields, Late-Celtic, 92
 — South, horse-trappings, 94
 Shoebury, pottery, 124
 Shrines of bells, 204
 — of books, 208
 — of relics, 210
 Silchester, 82
 — enamelled stand, 134
 — fibula, 107, 154
 Silian, cross-shaft, 270
 Silures, 18
 Situlæ, Hallstatt, 145
 — Late-Celtic, 116
 — of bronze, 86
 Skail, penannular brooch, 227
 Sliabh na Calliaghe, 43
 — — — bonework, 127
 — — — engraved bones, 150
 Soldering, 132
 Somme-Bionne, 13
 Southill, Chi-Rho Monogram, 163
 Southwark, dagger-sheath, 92
 Spear-head of Bronze Age, 39
 Spiral, closely coiled, 60
 — knot, 270
 — ornament at Newgrange, 48
 — — at Orchomenos, 54
 — — in Bronze Age, 50
 — — in Egypt, 54
 — — in Scandinavia, 51
 Spirals in Celtic Christian art, 284
 — Late-Celtic, 154
 — from Book of Durrow, 169
 Spoons, Late-Celtic, 119
 Stamfordbury, fire-dogs, 118
 Stamford Hill, armlet, 114
 — — fibula, 106
 — — mirror, 115
 Stand, enamelled, 134
 Standon, enamelled vessel, 138
 Stanhope, armlet, 113
 Stanton, cup-marks at, 57
 Stanwick, horse-trappings, 94
 — Late-Celtic finds at, 75
 — sword-sheath, 91
 Step-patterns, 277
 — in Late-Celtic art, 160
 Stitchell, collar, 111

- Stival, bell, 200
 Stockholm, Gospels, 175
 Stones, sculptured, Late-Celtic, 128
 Storr, penannular brooch, 227
 Stowe Missal, cover of, 170
 — — shrine of, 209
 Strathfillan, bell, 201
 Strokestown Crannog, 81
 — — fibula, 170
 Strypes, spirals at, 50
 Style, Late-Celtic, 143
 Swastika anthropomorphs, 294
 — curved, at Ilkley, 58
 — — on Barlaston bowl, 58
 — —, 60
 — designs, Late-Celtic, 154
 Sweden, bronze axe-head with
 spirals from, 52
 Sword, Hallstatt, 8
 Sword-sheath from La Tène, 11
 — Hunsbury, 132
 Sword-sheaths, Late Celtic, 91
 Swords with antennæ, 86
 Symbols used in Bronze Age, 22

 Tankard, Late-Celtic, 142, 151
 Tankards, Late-Celtic, 116
 Tara brooch, 229
 — — chains, 140
 — — horse-trappings, 95
 — — horse's head ornament, 98
 Tassilo, chalice of, 215
 Tayfield, jet necklace, 42
 Technical processes, Iron Age,
 129
 — — in Celtic Christian art, 232
 Termonfechin, cross, 192
 Textile patterns, Iron Age, 129
 Thames, river, helmet, 93
 — — Late-Celtic finds in, 77
 Thirst House Cave, armllet, 114
 — — — châtelaine, 115
 — — — fibula, 107
 Thor's Cave, 76, 81
 — — flutes, 118
 Tillycoultry, sculptured cist, 55
 Tincommios, coins of, 78
 Trawsfynydd, tankard, 142, 151
 Treceiri, 82
 — triskele pendant, 121
 Trelan Bahow, mirror, 115, 131
 — — Iron Age burials at, 69
 Trenoweth, collar, 111
 Triangle patterns, 31

 Triangular knotwork, 276
 Triskele anthropomorphs, 294
 — designs, Late-Celtic, 154
 — pendants, Late Celtic, 121
 Torques, beaded, 159
 Torrish, jet necklace from, 42
 Torrs, helmet, 93
 Torwoodlee, brooch of, 82
 — horse-trappings, 95
 Towers, round, 196
 Towie, stone ball from, 50
 Trumpet, Late-Celtic, 118
 Tuam, cross, 210
 Tullylease, cross-slab, 181
 Tumulus at Newgrange, 34
 — at Old Parks, 56
 Turoe, Late-Celtic sculpture, 128
 Tweed, river, Late-Celtic finds in,
 77
 Tyne, fibula, 107
 — river, Late-Celtic finds in, 77

 Uffizi Museum, cruciform harness-
 mounting, 98
 — — enamelled harness-mounting,
 134
 Ulbster, erect cross-slab, 184, 276
 Unstan, urn from, 38
 Urns, cinerary, 24
 Urquhart, pin, 108

 Victoria Cave at Settle, 76, 81
 — — fibula, 107, 154
 Vigeans, St., erect cross-slab, 184
 Verica, coins of, 78

 Walmer, fibula, 105
 — spoon, 121
 Wandsworth, dagger-sheath, 92
 Warden, mirror, 115
 Warden, Old, Kimmeridge shale
 vessel, 128
 Warren, Folkestone, fibula, 102
 Warton, sword-sheath, 91
 Water Eaton, fibula, 106
 — — sword-sheath, 91
 Watsch situlæ, 145
 Wellingborough, 82
 Westhall, horse-trappings, 94
 — enamelled harness-rings, 134
 Weston, spoons, 121, 147
 Weymouth, pottery, 124
 Wheel-crosses, 188

- Wheel symbol in Bronze Age, 59
 Whitechurch, pottery, 124
 Winding-band patterns, 57
 Witham, river, dagger-sheath, 92
 — — Late-Celtic finds in, 77
 — — shield, 92, 139
 Whithorn, Chi-Rho Monogram, 163
 — cross-shaft, 270
 Woodwork, Late-Celtic, 126
 Woodway, erect cross-slab, 184
 Wooler, cup-and-ring sculpture, 59
 Wraxhall, collar, 111
 Wrought metal-work, Iron Age, 130
 Wykeham Moor, cup-marks at, 57
 Zoöomorphic designs, Late-Celtic, 144
 Zoömorphs in Celtic Christian art, 249, 287

**PLYMOUTH
WILLIAM BRENDON AND SON
PRINTERS**

A CATALOGUE OF BOOKS
PUBLISHED BY METHUEN
AND COMPANY: LONDON
36 ESSEX STREET
W.C.

CONTENTS

	PAGE		PAGE
GENERAL LITERATURE,	2-24	LITTLE GALLERIES,	29
ANTIQUARY'S BOOKS,	25	LITTLE GUIDES,	29
BUSINESS BOOKS,	25	LITTLE LIBRARY,	29
BYZANTINE TEXTS,	25	METHUEN'S MINIATURE LIBRARY,	30
CHURCHMAN'S BIBLE,	25	RAPIORA,	30
CHURCHMAN'S LIBRARY,	25	SCHOOL EXAMINATION SERIES,	30
CLASSICAL TRANSLATIONS,	25	SOCIAL QUESTIONS OF TO-DAY,	31
COMMERCIAL SERIES,	26	TEXTBOOKS OF TECHNOLOGY,	31
CONNOISSEURS LIBRARY,	26	HANDBOOKS OF THEOLOGY,	31
LIBRARY OF DEVOTION,	26	UNIVERSITY EXTENSION SERIES,	31
ILLUSTRATED POCKET LIBRARY OF PLAIN AND COLOURED BOOKS,	26	WESTMINSTER COMMENTARIES,	32
JUNIOR EXAMINATION SERIES	28	FICTION,	32-39
METHUEN'S JUNIOR SCHOOL-BOOKS,	28	BOOKS FOR BOYS AND GIRLS,	39
LEADERS OF RELIGION,	28	NOVELS OF ALEXANDRE DUMAS,	39
LITTLE BIOGRAPHIES,	28	METHUEN'S ONE SHILLING NOVELS,	39
LITTLE BLUE BOOKS,	28	THE NOVELIST,	40
LITTLE BOOKS ON ART,	29	SIXPENNY LIBRARY,	40

SEPTEMBER 1904

A CATALOGUE OF
MESSRS. METHUEN'S
PUBLICATIONS

Colonial Editions are published of all Messrs. METHUEN'S Novels issued at a price above 2s. 6d., and similar editions are published of some works of General Literature. These are marked in the Catalogue. Colonial editions are only for circulation in the British Colonies and India.

PART I.—GENERAL LITERATURE

Abbot (Jacob). THE BEECHNUT BOOK. Edited by E. V. LUCAS. Illustrated. *Demy 16mo. 2s. 6d.* [Little Blue Books.

Acetos (M. J.). See L. A. SORNET.

Adams (Frank). JACK SPRATT. With 24 Coloured Pictures. *Poet 4to. 2s.*

Adeney (W. F.), M.A. See BENNETT and ADENEY.

Æschylus. AGAMEMNON, CHŒPHORUS, EUMENIDES. Translated by LEWIS CAMPBELL, LL.D., late Professor of Greek at St. Andrews. 5s.

[Classical Translations.

Æsop. FABLES. With 380 Woodcuts by THOMAS BEWICK. *Fcap. 8vo. 3s. 6d. net.*

[Illustrated Pocket Library.

Ainsworth (W. Harrison). WINDSOR CASTLE. With 22 Plates and 87 Woodcuts in the Text by GEORGE CRUIKSHANK. *Fcap. 8vo. 3s. 6d. net.*

[Illustrated Pocket Library.

THE TOWER OF LONDON. With 40 Plates and 58 Woodcuts in the Text by GEORGE CRUIKSHANK. *Fcap. 8vo. 3s. 6d. net.*

[Illustrated Pocket Library.

Alexander (William), D.D., Archbishop of Armagh. THOUGHTS AND COUNSELS OF MANY YEARS. Selected by J. H. BURN, B.D. *Demy 16mo. 2s. 6d.*

Alken (Henry). THE ANALYSIS OF THE HUNTING FIELD. With 7 Coloured Plates and 43 Illustrations on wood. *Fcap. 8vo. 3s. 6d. net.*

[Illustrated Pocket Library.

THE NATIONAL SPORTS OF GREAT BRITAIN. With descriptions in English and French. With 51 Coloured Plates. *Royal Folio. Five Guineas net.*

THE NATIONAL SPORTS OF GREAT BRITAIN. With Descriptions and 51 Coloured Plates by HENRY ALKEN. 4s. 6d. net.

Also a limited edition on large Japanese paper, 30s. net.

This book is completely different from the large folio edition of 'National Sports' by the same artist, and none of the plates are similar. [Illustrated Pocket Library. See also NIMROD and EGAN.

Allen (Jeanie). DURER. With many Illustrations. *Demy 16mo. 2s. 6d. net.*

[Little Books on Art.

Allen (J. Romilly), F.S.A. CELTIC ART. With numerous Illustrations and Plans. *Demy 8vo. 7s. 6d. net.*

[Antiquary's Books.

Almack (E.). BOOKPLATES. With many Illustrations. *Demy 16mo. 2s. 6d. net.*

[Little Books on Art.

Amherst (Lady). A SKETCH OF EGYPTIAN HISTORY FROM THE EARLIEST TIMES TO THE PRESENT DAY. With many Illustrations, some of which are in Colour. *Demy 8vo. 10s. 6d. net.*

Anderson (F. M.). THE STORY OF THE BRITISH EMPIRE FOR CHILDREN. With many Illustrations. *Crown 8vo. 2s.*

Andrewes (Bishop). PRECES PRIVATAE. Edited, with Notes, by F. E. BRIGHTMAN, M.A., of Pusey House, Oxford. *Crown 8vo. 6s.*

Aristophanes. THE FROGS. Translated into English by E. W. HUNTINGFORD, M.A., Professor of Classics in Trinity College, Toronto. *Crown 8vo. 2s. 6d.*

Aristotle. THE NICOMACHEAN ETHICS. Edited, with an Introduction and Notes, by JOHN BURNET, M.A., Professor of Greek at St. Andrews. *Demy 8vo. 15s. net.*

Ashton (E.). THE PEELES AT THE CAPITAL. Illustrated. *Demy 16mo. 2s. 6d.*

[Little Blue Books.

MRS. BARBERRY'S GENERAL SHOP. Illustrated. *Demy 16mo. 2s. 6d.*

[The Little Blue Books.

Asquith (H. H.), The Right Hon., M.P. **TRADE AND THE EMPIRE.** An Examination of Mr. Chamberlain's Proposals. *Demy 8vo. 6s. net.*

Atkins (H. G.) **GOETHE.** With 12 Illustrations. *Fcap. 8vo. 3s. 6d.; leather, 4s. net.* [Little Biographies. Nearly Ready.]

Atkinson (T. D.) **A SHORT HISTORY OF ENGLISH ARCHITECTURE.** With over 200 Illustrations by the Author and others. *Fcap. 8vo. 3s. 6d. net.*

Austen (Jane) **PRIDE AND PREJUDICE.** Edited by E. V. LUCAS. *Two Volumes. Small Pott 8vo. Each volume, cloth, 1s. 6d. net.; leather, 2s. 6d. net.* [Little Library.]

NORTHANGER ABBEY. Edited by E. V. LUCAS. *Small Pott 8vo. Cloth, 1s. 6d. net.; leather, 2s. 6d. net.* [Little Library.]

Bacon (Francis) **THE ESSAYS OF** Edited by EDWARD WRIGHT. *Small Pott 8vo. 1s. 6d. net.; leather, 2s. 6d. net.* [Little Library.]

Baden-Powell (R. S. S.), Major-General. **THE DOWNFALL OF PREMPHEH.** A Diary of Life in Ashanti, 1895. With 21 Illustrations and a Map. *Third Edition. Large Crown 8vo. 6s.*

A Colonial Edition is also published.
THE MATABELE CAMPAIGN, 1896. With nearly 100 Illustrations. *Fourth and Cheaper Edition. Large Crown 8vo. 6s.*

A Colonial Edition is also published.
Baker (W. G.), M.A. **JUNIOR GEOGRAPHY EXAMINATION PAPERS.** *Fcap. 8vo. 1s.* [Junior Exam. Series.]

Baker (Julian L.) F.I.C. F.C.S. **THE BREWING INDUSTRY.** *Crown 8vo. 2s. 6d. net.* [Books on Business.]

Balfour (Graham) **THE LIFE OF ROBERT LOUIS STEVENSON.** *Second Edition. Two Volumes. Demy 8vo. 9s. net.*

A Colonial Edition is also published.
Bally (R. E.) **A FRENCH COMMERCIAL READER.** With Vocabulary. *Second Edition. Crown 8vo. 2s.*

[Commercial Series.]
FRENCH COMMERCIAL CORRESPONDENCE. With Vocabulary. *Third Edition. Crown 8vo. 2s.*

[Commercial Series.]
A GERMAN COMMERCIAL READER. With Vocabulary. *Crown 8vo. 2s.*

[Commercial Series.]
GERMAN COMMERCIAL CORRESPONDENCE. With Vocabulary. *Crown 8vo. 2s. 6d.*

[Commercial Series.]
Banks (Elizabeth L.) **THE AUTOBIOGRAPHY OF A NEWSPAPER GIRL.** With Portrait of the Author and her Dog. *Second Edition. Crown 8vo. 6s.*

A Colonial Edition is also published.
Barham (R. H.) **THE INGOLDSBY LEGENDS.** Edited by J. B. ATLAY. *Two*

Volumes. Small Pott 8vo. Each volume, cloth, 1s. 6d. net.; leather, 2s. 6d. net.

[Little Library.]
Baring-Gould (S.) Author of 'Mehalah,' etc. **THE LIFE OF NAPOLEON BONAPARTE.** With over 450 Illustrations in the Text, and 12 Photogravure Plates. *Gilt top. Large quarto. 36s.*

THE TRAGEDY OF THE CÆSARS. With numerous Illustrations from Busts, Gems, Cameos, etc. *Fifth Edition. Royal 8vo. 15s.*

A BOOK OF FAIRY TALES. With numerous Illustrations and Initial Letters by ARTHUR J. GASKIN. *Second Edition. Crown 8vo. Buckram. 6s.*

A BOOK OF BRITANNY. With numerous Illustrations. *Crown 8vo. 6s.* Uniform in scope and size with Mr. Baring-Gould's well-known books on Devon, Cornwall, and Dartmoor.

OLD ENGLISH FAIRY TALES. With numerous Illustrations by F. D. BEDFORD. *Second Edition. Cr. 8vo. Buckram. 6s.*

A Colonial Edition is also published.
THE VICAR OF MORWENSTOW: A Biography. A new and Revised Edition. With Portrait. *Crown 8vo. 3s. 6d.*

A completely new edition of the well-known biography of R. S. Hawker.
DARTMOOR: A Descriptive and Historical Sketch. With Plans and numerous Illustrations. *Crown 8vo. 6s.*

THE BOOK OF THE WEST. With numerous Illustrations. *Two volumes. Vol. 1. Devon. Second Edition. Vol. 11. Cornwall. Second Edition. Crown 8vo. 6s. each.*

A BOOK OF NORTH WALES. With numerous Illustrations. *Crown 8vo. 6s.*

This book is uniform with Mr. Baring-Gould's books on Devon, Dartmoor, and Brittany.

A BOOK OF SOUTH WALES. With many Illustrations. *Cr. 8vo. 6s.*

A BOOK OF GHOSTS. With many Illustrations. *Cr. 8vo. 6s. net.*

A Colonial Edition is also published.
BRITANNY. Illustrated by J. A. WYLLIE. *Pott 8vo. Cloth, 3s.; leather, 3s. 6d. net.*

[Little Guides.]
OLD COUNTRY LIFE. With 67 Illustrations. *Fifth Edition. Large Cr. 8vo. 6s.*

AN OLD ENGLISH HOME. With numerous Plans and Illustrations. *Cr. 8vo. 6s.*

YORKSHIRE ODDITIES AND STRANGE EVENTS. *Fifth Edition. Crown 8vo. 6s.*

STRANGE SURVIVALS AND SUPERSTITIONS. *Second Edition. Cr. 8vo. 6s.*

A Colonial Edition is also published.
A GARLAND OF COUNTRY SONG: English Folk Songs with their Traditional Melodies. Collected and arranged by S. BARING-GOULD and H. F. SHEPHERD. *Demy 4to. 6s.*

- SONGS OF THE WEST:** Traditional Ballads and Songs of the West of England, with their Melodies. Collected by S. BARING-GOULD, M.A., and H. F. SHEPARD, M.A. In 4 Parts. *Parts I., II., III., 2s. 6d. each. Part IV., 4s. In One Volume, French Morocco, 10s. net.*
- Barker (Aldred F.),** Author of 'Pattern Analysis,' etc. AN INTRODUCTION TO THE STUDY OF TEXTILE DESIGN. With numerous Diagrams and Illustrations. *Demy 8vo. 7s. 6d.*
- Barnes (W. E.), D.D.** ISAIAH. With an Introduction and Notes. *Two Vols. Fcap. 8vo. 2s. net each.* With Map. [Churchman's Bible.
- Barnett (Mrs. P. A.),** A LITTLE BOOK OF ENGLISH PROSE. *Small Pott 8vo. Cloth, 1s. 6d. net; leather, 2s. 6d. net.* [Little Library.
- Baron (E. B. N.), M.A.** FRENCH PROSE COMPOSITION. *Crown 8vo. 2s. 6d. Key, 3s. net.*
- Barrow (H. M.), M.A.** Wadham College, Oxford. TEXTS FOR SERMONS. With a Preface by Canon Scott Holland. *Crown 8vo. 3s. 6d.*
- Basstable (G. F.), M.A.,** Professor of Economics at Trinity College, Dublin. THE COMMERCE OF NATIONS. *Second Edition. Crown 8vo. 2s. 6d.* [Social Questions Series.
- Batson (Mrs. Stephen),** A BOOK OF THE COUNTRY AND THE GARDEN. Illustrated by F. Carruthers Gould and A. C. Gould. *Demy 8vo. 10s. 6d.*
- A CONCISE HANDBOOK OF GARDEN FLOWERS. *Fcap. 8vo. 3s. 6d.*
- Beaman (A. Hulme),** PONS ASINORUM; OR, A GUIDE TO BRIDGE. *Second Edition. Fcap. 8vo. 2s.*
- Beard (W. S.),** JUNIOR ARITHMETIC EXAMINATION PAPERS. *Second Edition. Fcap. 8vo. 1s.* With or without Answers. [Junior Examination Series.
- JUNIOR GENERAL INFORMATION EXAMINATION PAPERS.** *Fcap. 8vo. 1s.* [Junior Examination Series.
- EASY EXERCISES IN ARITHMETIC.** Arranged by. *Cr. 8vo.* Without Answers, 1s. With Answers, 1s. 3d.
- Beckford (Peter),** THOUGHTS ON HUNTING. Edited by J. OTHO PAGET, and Illustrated by G. H. JALLAND. *Second and Cheaper Edition. Demy 8vo. 6s.*
- Beckford (William),** THE HISTORY OF THE CALIPH VATHEK. Edited by E. DENISON ROSS. *Pott 8vo. Cloth, 1s. 6d. net; leather, 2s. 6d. net.* [Little Library.
- Beeching (H. G.), M.A.,** Canon of Westminster. LYRA SACRA: A Book of Sacred Verse. With an Introduction and Notes. *Pott 8vo. Cl., 2s.; leather, 2s. 6d.* [Library of Devotion.
- Behnen (Jacob),** THE SUPERSENSUAL LIFE. Edited by BERNARD HOLLAND. *Fcap. 8vo. 3s. 6d.*
- Belloc (Hilaire),** PARIS. With Maps and Illustrations. *Crown 8vo. 6s.*
- Bellot (H. H. L.), M.A.** THE I'YER AND MIDDLE TEMPLE. With numerous Illustrations. *Crown 8vo. 6s. net.* See also L. A. A. JONES.
- Bennett (W. H.), M.A.** A PRIMER OF THE BIBLE. *Second Edition. Crown 8vo. 2s. 6d.*
- Bennett (W. H.) and Adeney (W. F.),** A BIBLICAL INTRODUCTION. *Second Edition. Crown 8vo. 7s. 6d.*
- Benson (Archbishop),** GOD'S BOARD: Communion Addresses. With Introductory Note by Mrs. Benson. *Fcap. 8vo. 3s. 6d. net.*
- Benson (A. C.), M.A.** TENNYSON. With 8 Illustrations. *Fcap. 8vo. Cloth, 3s. 6d.; Leather, 4s. net.* [Little Biographies.
- Benson (E. M.),** THE WAY OF HOLINESS: a Devotional Commentary on the 119th Psalm. *Crown 8vo. 5s.*
- Bernard (E. B.), M.A.,** Canon of Salisbury. THE ENGLISH SUNDAY. *Fcap. 8vo. 1s. 6d.*
- Bertouche (Baroness de),** THE LIFE OF FATHER IGNATIUS. With Illustrations. *Demy 8vo. 10s. 6d. net.* A Colonial Edition is also published.
- Bethune-Baker (J. F.), M.A.,** Fellow of Pembroke College, Cambridge. A HISTORY OF EARLY CHRISTIAN DOCTRINE. *Demy 8vo. 10s. 6d.* [Handbooks of Theology.
- Bidez (M.).** See Parmentier.
- Biggs (G. R. D.), D.D.** THE EPISTLE TO THE PHILIPPIANS. With an Introduction and Notes. *Fcap. 8vo. 1s. 6d. net.* [Churchman's Bible.
- Bindley (T. Herbert), B.D.** THE OECUMENICAL DOCUMENTS OF THE FAITH. With Introductions and Notes. *Crown 8vo. 6s.* A historical account of the Creeds.
- Binyon (Laurence),** THE DEATH OF ADAM, AND OTHER POEMS. *Second Edition. Crown 8vo. 2s. 6d. net.*
- Blair (Robert),** THE GRAVE: a Poem. Illustrated by 12 Etchings executed by Louis Schiavonetti, from the original inventions of WILLIAM BLAKE. With an Engraved Title-Page and a Portrait of Blake by T. PHILLIPS, R.A. *Fcap. 8vo. 3s. 6d. net.* Also a limited edition on large Japanese paper with India Proofs and a duplicate set of plates. 15s. net. [Illustrated Pocket Library.
- Blake (William),** ILLUSTRATIONS OF THE BOOK OF JOB. Invented and Engraved by. *Fcap. 8vo. 3s. 6d. net.* Also a limited edition on large Japanese paper with India proofs and a duplicate set of plates. 15s. net. [Illustrated Pocket Library.
- SELECTIONS.** Edited by M. PERUGINI. *Small Pott 8vo. 1s. 6d. net; leather, 2s. 6d. net.* [Little Library.

- Maxland (B.)**, M.A. THE SONG OF SONGS. Being Selections from ST. BERNARD. *Small Pott 8vo. Cloth, 2s.; leather, 2s. 6d. net.* [Library of Devotion.]
- Bloom (T. Harvey)**, M.A. SHAKE-SPEARE'S GARDEN. With Illustrations. *Fcap. 8vo. 2s. 6d.; leather, 3s. 6d. net.*
- Boardman (J. H.)**. See W. French.
- Bodley (J. E. O.)** Author of 'France.' THE CORONATION OF EDWARD VII. *Demy 8vo. 21s. net.* By Command of the King.
- Body (George)**, D.D. THE SOUL'S PILGRIMAGE: Devotional Readings from his published and unpublished writings. Selected and arranged by J. H. BURN, B.D., F.R.S.E. *Pott 8vo. 2s. 6d.*
- Bona (Cardinal)**. A GUIDE TO ETERNITY. Edited with an Introduction and Notes, by J. W. STANBRIDGE, B.D. *Pott 8vo. Cloth, 2s.; leather, 2s. 6d. net.* [Library of Devotion.]
- Borrow (George)**. LAVENGRO. Edited by F. HINDES GROOMER. *Two Volumes. Small Pott 8vo. Each volume, cloth, 1s. 6d. net; leather, 2s. 6d. net.* [Little Library.]
- THE ROMAN RYE**. Edited by JOHN SAMPSON. *Small Pott 8vo. Cloth, 1s. 6d. net; leather, 2s. 6d. net.* [Little Library.]
- Boa (J. Bittzema)**. AGRICULTURAL ZOOLOGY. Translated by J. R. AINSWORTH DAVIS, M.A. With an Introduction by ELEANOR A. ORMEROD, F.E.S. With 155 Illustrations. *Crown 8vo. Third Edition. 3s. 6d.*
- Botting (O. G.)**, B.A. JUNIOR LATIN EXAMINATION PAPERS. *Fcap. 8vo. Second Ed. 1s.* [Junior Examination Series.]
- EASY GREEK EXERCISES**. *Cr. 8vo. 2s.*
- Boulton (E. S.)**. GEOMETRY ON MODERN LINES. *Crown 8vo. 2s.*
- Bowden (E. M.)**. THE IMITATION OF BUDDHA: Being Quotations from Buddhist Literature for each Day in the Year. *Fourth Edition. Crown 16mo. 2s. 6d.*
- Bowmaker (E.)**. THE HOUSING OF THE WORKING CLASSES. *Crown 8vo. 2s. 6d.* [Social Questions Series.]
- Boyle (W.)**. CHRISTMAS AT THE ZOO. With Verses by W. BOYLE and 24 Coloured Pictures by H. B. NEILSON. *Pott 4to. 2s.*
- Erabant (F. G.)**, M.A. SUSSEX. Illustrated by E. H. NEW. *Small Pott 8vo. Cloth, 3s.; leather, 3s. 6d. net.* [Little Guides.]
- THE ENGLISH LAKES**. Illustrated by E. H. NEW. *Small Pott 8vo. Cloth, 4s.; leather, 4s. 6d. net.* [Little Guides.]
- Brodrick (Mary) and Morton (Anderson)**. A CONCISE HANDBOOK OF EGYPTIAN ARCHÆOLOGY. With many Illustrations. *Crown 8vo. 3s. 6d.*
- Brooke (A. S.)**, M.A. SLINGSBY AND SLINGSBY CASTLE. With many Illustrations. *Cr. 8vo. 7s. 6d.*
- Brooks (E. W.)**. See F. J. Hamilton.
- Brown (P. H.)**, Fraser Professor of Ancient (Scottish) History at the University of Edinburgh. SCOTLAND IN THE TIME OF QUEEN MARY. *Demy 8vo. 7s. 6d. net.*
- Brownell (C. L.)**. THE HEART OF JAPAN. Illustrated. *Third Edition. Crown 8vo. 6s.* A Colonial Edition is also published.
- Browning (Robert)**. SELECTIONS FROM THE EARLY POEMS OF. With Introduction and Notes by W. HALL GRIFFIN. *Small Pott 8vo. 1s. 6d. net; leather, 2s. 6d. net.* [Little Library.]
- Buckland (Francis T.)**. CURIOSITIES OF NATURAL HISTORY. With Illustrations by HARRY B. NEILSON. *Crown 8vo. 3s. 6d.*
- Buckton (A. M.)**. THE BURDEN OF ENGELA: a Ballad-Epic. *Second Edition. Crown 8vo. 2s. 6d. net.*
- EAGER HEART: A Mystery Play**. *Crown 8vo. 1s. net.*
- Budge (E. A. Wallis)**. THE GODS OF THE EGYPTIANS. With over 100 Coloured Plates and many Illustrations. *Two Volumes. Royal 8vo. £3; 3s. net.*
- Bull (Paul)**, Army Chaplain. GOD AND OUR SOLDIERS. *Crown 8vo. 6s.* A Colonial Edition is also published.
- Bulley (Miss)**. See Lady Dilke.
- Bunyan (John)**. THE PILGRIM'S PROGRESS. Edited, with an Introduction, by C. H. FIRTH, M.A. With 39 Illustrations by R. ANNING BELL. *Cr. 8vo. 6s.*
- GRACE ABOUNDING**. Edited by C. S. FREER, M.A. *Small Pott 8vo. Cloth, 2s.; leather, 2s. 6d. net.* [Library of Devotion.]
- Burch (G. J.)**, M.A., F.R.S. A MANUAL OF ELECTRICAL SCIENCE. With numerous Illustrations. *Crown 8vo. 3s.* [University Extension Series.]
- Burgess (Gelett)**. GOOPS AND HOW TO BE THEM. With numerous Illustrations. *Small 4to. 6s.*
- Burn (A. E.)**, D.D., Prebendary of Lichfield. AN INTRODUCTION TO THE HISTORY OF THE CREEDS. *Demy 8vo. 10s. 6d.* [Handbooks of Theology.]
- Burn (J. H.)**, B.D., A MANUAL OF CONSOLATION FROM THE SAINTS AND FATHERS. *Small Pott 8vo. Cloth, 2s.; leather, 2s. 6d. net.* [Library of Devotion.]
- Burn (J. H.)**, B.D. A DAY BOOK FROM THE SAINTS AND FATHERS. With an Introduction and Notes. *Small Pott 8vo. Cloth, 2s.; leather, 2s. 6d. net.* [Library of Devotion.]
- Burnand (Sir F. C.)**. RECORDS AND REMINISCENCES, PERSONAL AND GENERAL. With many Illustrations. *Demy 8vo. Two Volumes. Third Edition. 5s.* A Colonial Edition is also published.

- Burns (Robert), THE POEMS OF.** Edited by ANDREW LANG and W. A. CRAIGIE. With Portrait. *Third Edition.* *Demy 8vo., gilt top, 6s.*
- Burnside (W. F.), M.A. OLD TESTAMENT HISTORY FOR USE IN SCHOOLS.** *Crown 8vo., 3s. 6d.*
- Burton (Alfred), THE MILITARY ADVENTURES OF JOHNNY NEWCOME.** With 15 Coloured Plates by T. ROWLANDSON. *Fcap. 8vo., 3s. 6d. net.* [Illustrated Pocket Library.]
- THE ADVENTURES OF JOHNNY NEWCOME IN THE NAVY.** With 16 Coloured Plates by T. ROWLANDSON. *Fcap. 8vo., 3s. 6d. net.* [Illus. Pocket Library.]
- Caldecott (Alfred), D.D. THE PHILOSOPHY OF RELIGION IN ENGLAND AND AMERICA.** *Demy 8vo., 10s. 6d.* [Handbooks of Theology.]
- Calderwood (D. S.), Headmaster of the Normal School, Edinburgh. TEST CARDS IN EUCLID AND ALGEBRA.** In three packets of 40, with Answers. 1s. each. Or in three Books, price 2s., 2s., and 3d.
- Cambridge (Ada) [Mrs. Cross]. THIRTY YEARS IN AUSTRALIA.** *Demy 8vo., 7s. 6d.* A Colonial Edition is also published.
- Canning (George), SELECTIONS FROM THE ANTI-JACOBIN;** with additional Poems. Edited by LOYD SANDERS. *Small Pott 8vo., cloth, 1s. 6d. net.; leather, 2s. 6d. net.* [Little Library.]
- Capey (E. F. H.), ERASMUS.** With 12 Illustrations. *Fcap. 8vo., Cloth, 3s. 6d. net.; leather, 4s. net.* [Little Biographies.]
- Carlyle (Thomas), THE FRENCH REVOLUTION.** Edited by C. R. L. FLETCHER, Fellow of Magdalen College, Oxford. *Three Volumes. Crown 8vo., 12s.*
- THE LIFE AND LETTERS OF OLIVER CROMWELL.** With an Introduction by C. H. FIRTH, M.A., and Notes and Appendices by Mrs. S. C. LOMAS. *Three Volumes. Demy 8vo., 18s. net.*
- Carlyle (E. M. and A. J.), M.A. BISHOP LATIMER.** With Portrait. *Crown 8vo., 3s. 6d.* [Leaders of Religion.]
- Chamberlin (Wilbur E.). ORDERED TO CHINA.** *Crown 8vo., 6s.* A Colonial Edition is also published.
- Channer (C. G.) and Roberts (M. E.) LACE-MAKING IN THE MIDLANDS, PAST AND PRESENT.** With 16 full-page Illustrations. *Crown 8vo., 2s. 6d.*
- Chesterfield (Lord), THE LETTERS OF, TO HIS SON.** Edited, with an Introduction, by C. STRACHEY, and Notes by A. CALTHROP. *Two Volumes. Cr. 8vo., 12s.*
- Christian (F. W.), THE CAROLINE ISLANDS.** With many Illustrations and Maps. *Demy 8vo., 12s. 6d. net.*
- Cicero. DE ORATORE I.** Translated by E. N. P. MOOR, M.A. *Crown 8vo., 3s. 6d.* [Classical Translations.]
- SELECT ORATIONS (Pro Milone, Pro Murena, Philippicæ, In Catilinam).** Translated by H. E. D. BLAKISTON, M.A., Fellow and Tutor of Trinity College, Oxford. *Crown 8vo., 5s.* [Classical Translations.]
- DE NATURA DEORUM.** Translated by F. BROOKS, M.A., late Scholar of Balliol College, Oxford. *Crown 8vo., 3s. 6d.* [Classical Translations.]
- DE OFFICIIS.** Translated by G. B. GARDINER, M.A. *Crown 8vo., 2s. 6d.* [Classical Translations.]
- Clarke (F. A.), M.A. BISHOP KEN.** With Portrait. *Crown 8vo., 3s. 6d.* [Leaders of Religion.]
- Cleather (A. L.) and Crump (B.) RICHARD WAGNER'S MUSIC DRAMAS:** Interpretations, embodying Wagner's own explanations. *In Four Volumes. Fcap. 8vo., 2s. 6d. each.*
- VOL. I.—THE RING OF THE NIBELUNG.**
- VOL. II.—PARSIFAL, etc.**
- Glinch (G.). KENT.** Illustrated by F. D. BEDFORD. *Small Pott 8vo., Cloth, 3s.; leather, 3s. 6d. net.* [Little Guides.]
- THE ISLE OF WIGHT.** Illustrated by F. D. BEDFORD. *Small Pott 8vo., Cloth, 3s.; leather, 3s. 6d. net.* [Little Guides.]
- Clough (W. L.) and Dunstan (A. E.) ELEMENTARY EXPERIMENTAL SCIENCE. PHYSICS** by W. T. CLOUGH, A.R.C.S. **CHEMISTRY** by A. E. DUNSTAN, B.Sc. With 2 Plates and 154 Diagrams. *Crown 8vo., 2s.* [Junior School Books.]
- Coast (W. G.), B.A. EXAMINATION PAPERS IN VERGIL.** *Crown 8vo., 2s.*
- Cobb (T.). THE CASTAWAYS OF MEADOWBANK.** Illustrated. *Demy 16mo., 2s. 6d.* [Little Blue Books.]
- THE TREASURY OF PRINCEGATE PRIORY.** Illustrated. *Demy 16mo., 2s. 6d.* [Little Blue Books.]
- THE LOST BALL.** Illustrated. *Demy 16mo., 2s. 6d.* [Little Blue Books.]
- Collingwood (W. G.), M.A. THE LIFE OF JOHN RUSKIN.** With Portraits. *Second and Cheap Edition. Cr. 8vo., 6s.* Also a Poplar Edition. *Cr. 8vo., 2s. 6d. net.*
- Collins (W. E.), M.A. THE BEGINNINGS OF ENGLISH CHRISTIANITY.** With Map. *Cr. 8vo., 3s. 6d.* [Churchman's Library.]
- Colonna. HYPNEROTOMACHIA POLIPHILI UBI HUMANA OMNIA NON NISI SOMNIUM ESSE DOCET ATQUE OBITER PLURIMA SCITU SANE QUAM DIGNA COMMEMORAT.** An edition limited to 350 copies on handmade paper. *Folio. Three Guineas net.*
- Combe (William), THE TOUR OF DR. SYNTAX IN SEARCH OF THE PICTURESQUE.** With 30 Coloured Plates by T. ROWLANDSON. *Fcap. 8vo., 3s. 6d. net.* Also a limited edition on large Japanese paper, 30s. net. [Illustrated Pocket Library.]

THE TOUR OF DR. SYNTAX IN SEARCH OF CONSOLATION. With 24 Coloured Plates by T. ROWLANDSON. 3s. 6d. net.

Also a limited edition on large Japanese paper. 3os. net. [Illustrated Pocket Library.]
THE THIRD TOUR OF DR. SYNTAX IN SEARCH OF A WIFE. With 24 Coloured Plates by T. ROWLANDSON. 3s. 6d. net.

Also a limited edition on large Japanese paper. 3os. net.

[Illustrated Pocket Library.]
THE HISTORY OF JOHNNY QUAE GENUS: The Little Foundling of the late Dr. Syntax. With 24 Coloured Plates by ROWLANDSON. Fcap. 8vo. 3s. 6d. net.

Also a limited edition on large Japanese paper. 3os. net.

[Illustrated Pocket Library.]
THE ENGLISH DANCE OF DEATH, from the Designs of THOMAS ROWLANDSON, with Metrical Illustrations by the Author of 'Doctor Syntax.' With 74 Coloured Plates. Two Volumes. Fcap. 8vo. 9s. net. Also a limited edition on large Japanese paper. 3os. net.

[Illustrated Pocket Library.]
THE DANCE OF LIFE: a Poem. Illustrated with 26 Coloured Engravings by THOMAS ROWLANDSON. Fcap. 8vo. 3s. 6d. net.

Also a limited edition on large Japanese paper. 3os. net.

[Illustrated Pocket Library.]
COOK (A. M.), M.A. See E. C. Marchant.
COOKE-TAYLOR (R. W.) THE FACTORY SYSTEM. Crown 8vo. 2s. 6d.

[Social Questions Series.]
Corrall (Marie). THE PASSING OF THE GREAT QUEEN: A Tribute to the Noble Life of Victoria Regina. Small 4to. 1s.

A CHRISTMAS GREETING. Sm. 4to. 1s.
Corkran (Alice). LEIGHTON. With many Illustrations. Demy 16mo. 2s. 6d. net. [Little Books on Art.]

Cotes (Rosemary). DANTE'S GARDEN. With a Frontispiece. Second Edition. Fcap. 8vo. cloth 2s. 6d.; leather, 3s. 6d. net.

BIBLE FLOWERS. With a Frontispiece and Plan. Fcap. 8vo. 2s. 6d. net.

Cowley (Abraham) THE ESSAYS OF. Edited by H. C. MINCHIN. Small. Pott 8vo. Cloth, 1s. 6d. net; leather, 2s. 6d. net.

[Little Library.]
Cox (J. Charles), LL.D., F.S.A. DERBYSHIRE. Illustrated by J. C. WALL. Small Pott 8vo. Cloth, 2s.; leather, 3s. 6d. net. [Little Guides.]

HAMPSHIRE. Illustrated by M. E. PURSER. Small Pott 8vo. Cloth, 3s.; Leather, 3s. 6d. net. [Little Guides.]

Cox (Harold), B.A. LAND NATIONALIZATION. Crown 8vo. 2s. 6d.

[Social Questions Series.]

Crabbe (George), SELECTIONS FROM THE POEMS OF. Edited by A. C. DEANE. Small Pott 8vo. Cloth, 1s. 6d. net; leather, 2s. 6d. net. [Little Library.]

Craigie (W. A.) A PRIMER OF BURNS. Crown 8vo. 2s. 6d.

Craik (Mrs.) JOHN HALIFAX, GENTLEMAN. Edited by ANNIE MATHESON. Two Volumes. Small Pott 8vo. Each Volume, Cloth, 1s. 6d. net; leather, 2s. 6d. net. [Little Library.]

Crashaw (Richard), THE ENGLISH POEMS OF. Edited by EDWARD HUTTON. Small Pott 8vo. Cloth, 1s. 6d. net; leather, 2s. 6d. net. [Little Library.]

Crawford (F. G.). See Mary C. Danson.

Crouch (W.) BRYAN KING. With a Portrait. Crown 8vo. 3s. 6d. net.

Cruikshank (G.) THE LOVING BAL-LAD OF LORD BATEMAN. With 11 Plates. Crown 16mo. 1s. 6d. net.

From the edition published by C. Tilt, 1811.
Crump (B.). See A. L. Cleather.

Cunliffe (F. H. E.), Fellow of All Souls' College, Oxford. THE HISTORY OF THE BOER WAR. With many Illustrations, Plans, and Portraits. In 2 vols. Vol. 1, 15s.

Cutts (E. L.), D.D. AUGUSTINE OF CANTERBURY. With Portrait. Crown 8vo. 2s. 6d. [Leaders of Religion.]

Daniell (G. W.), M.A. BISHOP WILBER-FORCE. With Portrait. Crown 8vo. 2s. 6d. [Leaders of Religion.]

Danson (Mary C.) and Crawford (F. G.) FATHERS IN THE FAITH. Small 8vo. 1s. 6d.

Dante. LA COMMEDIA DI DANTE. The Italian Text edited by PAGET TOYNBEE, M.A., D.Litt. Crown 8vo. 6s.

THE INFERNO OF DANTE. Translated by H. F. CARY. Edited by PAGET TOYNBEE, M.A., D.Litt. Small Pott 8vo. Cloth, 1s. 6d. net; leather, 2s. 6d. net.

[Little Library.]

THE PURGATORIO OF DANTE. Translated by H. F. CARY. Edited by PAGET TOYNBEE, M.A., D.Litt. Small Pott 8vo. Cloth, 1s. 6d. net; leather, 2s. 6d. net.

[Little Library.]

THE PARADISO OF DANTE. Translated by H. F. CARY. Edited by PAGET TOYNBEE, M.A., D.Litt. Small Pott 8vo. Cloth, 1s. 6d. net; leather, 2s. 6d. net.

[Little Library.]

See also Paget Toynbee.

Darley (George), SELECTIONS FROM THE POEMS OF. Edited by R. A. STREATFIELD. Small Pott 8vo. Cloth, 1s. 6d. net; leather, 2s. 6d. net.

[Little Library.]

Davenport (Cyril). MEZZOTINTS. With 40 Plates in Photogravure. Wide Royal 8vo. 25s. net.

[Connoisseurs Library.]

- JEWELLERY.** With numerous Illustrations. *Demy 16mo.* 2s. 6d. net. [Little Books on Art.]
- Dawson (A. J.). MOROCCO.** Being a bundle of jottings, notes, impressions, tales, and tributes. With many Illustrations. *Demy 8vo.* 10s. 6d. net.
- Deane (A. G.). A LITTLE BOOK OF LIGHT VERSE.** With an Introduction and Notes. *Small Pott 8vo.* Cloth, 1s. 6d. net; leather, 2s. 6d. net. [Little Library.]
- Delbos (Leon). THE METRIC SYSTEM.** *Crown 8vo.* 2s.
- Demosthenes: THE OLYNTHIACS AND PHILIPPICS.** Translated upon a new principle by OTHO HOLLAND. *Crown 8vo.* 2s. 6d.
- Demosthenes. AGAINST CONON AND CALLICLES.** Edited with Notes and Vocabulary, by F. DARWIN SWIFT, M.A. *Fcap. 8vo.* 2s.
- Dickens (Charles). THE PICKWICK PAPERS.** With the 43 Illustrations by SEYMOUR and PHIZ, the two Buss Plates and the 32 Contemporary Onwhym Plates. 3s. 6d. net. This is a particularly interesting volume, containing, as it does, reproductions of very rare plates. [Illustrated Pocket Library.]
- Dickinson (Emily). POEMS.** First Series. *Crown 8vo.* 4s. 6d. net.
- Dickinson (G. L.), M.A., Fellow of King's College, Cambridge. THE GREEK VIEW OF LIFE.** Third Edition. *Crown 8vo.* 2s. 6d. [University Extension Series.]
- Dickson (H. N.), F.R.S.E., F.R.Met. Soc. METEOROLOGY.** Illustrated. *Crown 8vo.* 2s. 6d. [University Extension Series.]
- Dilke (Lady), Bulley (Miss), and Whitley (Miss). WOMEN'S WORK.** *Crown 8vo.* 2s. 6d. [Social Questions Series.]
- Dillon (Edward). PORCELAIN.** With many Plates in Colour and Photogravure. *Wide Royal 8vo.* 15s. net. [Connoisseurs Library.]
- Ditchfield (P. H.), M.A., F.S.A. ENGLISH VILLAGES.** Illustrated. *Crown 8vo.* 6s.
- THE STORY OF OUR ENGLISH TOWNS.** With Introduction by AUGUSTUS JESSOFF, D.D. Second Edition. *Crown 8vo.* 6s.
- OLD ENGLISH CUSTOMS: Extant at the Present Time.** An Account of Local Observances, Festival Customs, and Ancient Ceremonies yet Surviving in Great Britain. *Crown 8vo.* 6s.
- Dixon (W. M.), M.A. A PRIMER OF TENNYSON.** Second Edition. *Crown 8vo.* 2s. 6d.
- ENGLISH POETRY FROM BLAKE TO BROWNING.** Second Edition. *Crown 8vo.* 2s. 6d. [University Extension Series.]
- Dole (N. H.) FAMOUS COMPOSERS.** With Portraits. Two Volumes. *Demy 8vo.* 12s. net.
- Dowden (J.), D.D., Lord Bishop of Edinburgh. THE WORKMANSHIP OF THE PRAYER BOOK: Its Literary and Liturgical Aspects.** Second Edition. *Crown 8vo.* 3s. 6d. [Churchman's Library.]
- Driver (E. B.), D.D., Canon of Christ Church, Regius Professor of Hebrew in the University of Oxford. SERMONS ON SUBJECTS CONNECTED WITH THE OLD TESTAMENT.** *Crown 8vo.* 6s.
- THE BOOK OF GENESIS.** With Notes and Introduction. Second Edition. *Demy 8vo.* 10s. 6d. [Westminster Commentaries.]
- Duguid (Charles),** City Editor of the *Morning Post*, author of the 'Story of the Stock Exchange,' etc. **THE STOCK EXCHANGE.** Second Edition. *Crown 8vo.* 2s. 6d. net. [Books on Business.]
- Duncan (B. J.) (Mrs. COTES),** Author of 'A Voyage of Consolation.' **ON THE OTHER SIDE OF THE LATCH.** Second Edition. *Crown 8vo.* 6s.
- Dunn (J. T.), D.Sc., and Mundella (V. A.) GENERAL ELEMENTARY SCIENCE.** With 114 Illustrations. *Crown 8vo.* 3s. 6d.
- Dunstan (A. E.), R.Sc. See W. T. CLOUGH.**
- Durham (The Earl of). A REPORT ON CANADA.** With an Introductory Note. *Demy 8vo.* 7s. 6d. net.
- Dutt (W. A.) NORFOLK.** Illustrated by B. C. BOULTER. *Small Pott 8vo.* Cloth, 3s.; leather, 3s. 6d. net. [Little Guides.]
- A POPULAR GUIDE TO NORFOLK.** *Medium 8vo.* 6d. net.
- SUFFOLK.** Illustrated by J. WYLIE. *Small Pott 8vo.* Cloth, 3s.; leather, 3s. 6d. net. [Little Guides.]
- THE NORFOLK BROADS.** With coloured and other Illustrations by FRANK SOUTHGATE. *Large Demy 8vo.* 21s. net.
- Earle (John), Bishop of Salisbury. MICRO-COSMOGRAPHIE, OR A PIECE OF THE WORLD DISCOVERED; IN ESSAYS AND CHARACTERS.** Post 16mo. 2s. net. [Rariora.] Reprinted from the Sixth Edition published by Robert Allot in 1633.
- Edwards (Glement). RAILWAY NATIONALIZATION.** *Crown 8vo.* 2s. 6d. [Social Questions Series.]
- Edwards (W. Douglas). COMMERCIAL LAW.** *Crown 8vo.* 2s. [Commercial Series.]
- Egan (Pierce). LIFE IN LONDON, OR THE DAY AND NIGHT SCENES OF JERRY HAWTHORN, ESQ., AND HIS ELEGANT FRIEND, CORINTHIAN TOM.** With 36 Coloured Plates by I. R. and G. CRUIKSHANK. With numerous designs on wood. *Fcap. 8vo.* 4s. 6d. net. Also a limited edition on large Japanese paper. 30s. net. [Illustrated Pocket Library.]

- REAL LIFE IN LONDON, OR THE RAMBLES AND ADVENTURES OF BOB TALLYHO, ESQ., AND HIS COUSIN, THE HON. TOM DASHALL.** With 31 Coloured Plates by ALKEN and ROWLANDSON, etc. *Two Volumes. Fcap. 8vo. 9s. net.*
[Illustrated Pocket Library.]
- THE LIFE OF AN ACTOR.** With 27 Coloured Plates by THEODORE LANE, and several designs on wood. *Fcap. 8vo. 4s. 6d. net.*
[Illustrated Pocket Library.]
- Egerton (H. E.), M.A. A HISTORY OF BRITISH COLONIAL POLICY.** *Demy 8vo. 12s. 6d.*
A Colonial Edition is also published.
- Elaby (C. G.). ROME.** Illustrated by B. C. BOULTER. *Small Pott 8vo. Cloth, 3s.; leather, 3s. 6d. net.* [Little Guides.]
- Ellerton (F. G.).** See S. J. Stone.
- Ellwood (Thomas), THE HISTORY OF THE LIFE OF.** Edited by C. G. CRUMP, M.A. *Crown 8vo. 6s.*
- Engel (E.). A HISTORY OF ENGLISH LITERATURE:** From its Beginning to Tennyson. Translated from the German. *Demy 8vo. 7s. 6d. net.*
- Fairbrother (W. H.), M.A. THE PHILOSOPHY OF T. H. GREEN.** *Second Edition. Crown 8vo. 3s. 6d.*
- FELISSA; OR, THE LIFE AND OPINIONS OF A KITTEN OF SENTIMENT.** With 12 Coloured Plates. *Post 16mo. 2s. 6d. net. (5½×3½).*
From the edition published by J. Harris, 1811.
- Farrer (Reginald). THE GARDEN OF ASIA.** *Crown 8vo. 6s.*
A Colonial Edition is also published.
- Ferrier (Susan). MARRIAGE.** Edited by Miss GOODRICH FREER and Lord IDDESLEIGH. *Two Volumes. Small Pott 8vo. Each volume, cloth, 1s. 6d. net; leather, 2s. 6d. net.* [Little Library.]
- THE INHERITANCE.** *Two Volumes. Small Pott 8vo. Each Volume, cloth, 1s. 6d. net; leather, 2s. 6d. net.* [Little Library.]
- Finn (S. W.), M.A. JUNIOR ALGEBRA EXAMINATION PAPERS.** *Fcap. 8vo. With or Without Answers, 1s.*
[Junior Examination Series.]
- Firth (G. H.), M.A. CROMWELL'S ARMY:** A History of the English Soldier during the Civil Wars, the Commonwealth, and the Protectorate. *Crown 8vo. 7s. 6d.*
- Fisher (G. W.), M.A. ANNALS OF SHREWSBURY SCHOOL.** With numerous Illustrations. *Demy 8vo. 10s. 6d.*
- FitzGerald (Edward), THE RUB'AIYAT OF OMAR KHAYYAM.** From the First Edition of 1839. *Second Edition. Leather, 1s. net.*
[Miniature Library.]
- THE RUB'AIYAT OF OMAR KHAYYAM.** Printed from the Fifth and last Edition. With a Commentary by Mrs. STEPHEN BATSON, and a Biography of Omar by E. D. ROSS. *Crown 8vo. 6s.*
- EUPHRANOR:** a Dialogue on Youth. *Demy 32mo. Leather, 2s. net.*
[Miniature Library.]
- OLONIUS; or Wise Saws and Modern Instances.** *Demy 32mo. Leather, 2s. net.*
[Miniature Library.]
- FitzGerald (E. A.). THE HIGHEST ANDES.** With 2 Maps, 51 Illustrations, 13 of which are in Photogravure, and a Panorama. *Royal 8vo. 30s. net.*
- Flecker (W. H.), M.A., D. C. L., Headmaster of the Dean Close School, Cheltenham. THE STUDENTS' PRAYER BOOK.** Part I. MORNING AND EVENING PRAYER AND LITANY. With an Introduction and Notes. *Crown 8vo. 2s. 6d.*
- Flux (A. W.), M.A., William Dow Professor of Political Economy in McGill University, Montreal; sometime Fellow of St. John's College, Cambridge, and formerly Stanley-Jevons Professor of Political Economy in the Owens Coll., Manchester. ECONOMIC PRINCIPLES.** *Demy 8vo. 7s. 6d. net.*
- Fortescue (Mrs. G.) HOLBEIN.** With 30 Illustrations. *Demy 16mo. 2s. 6d. net.*
[Little Books on Art.]
- Fraser (J. F.). ROUND THE WORLD ON A WHEEL.** With 100 Illustrations. *Third Edition. Crown 8vo. 6s.*
A Colonial Edition is also published.
- French (W.), M.A., Principal of the Storey Institute, Lancaster. PRACTICAL CHEMISTRY. Part I.** With numerous Diagrams. *Crown 8vo. 1s. 6d.*
[Textbooks of Technology.]
- French (W.), M.A., and Boardman (T. H.), M.A. PRACTICAL CHEMISTRY. Part II.** With numerous Diagrams. *Crown 8vo. 1s. 6d.* [Textbooks of Technology.]
- Freudenreich (Ed. von). DAIRY BACTERIOLOGY.** A Short Manual for the Use of Students. Translated by J. R. AINSWORTH DAVIS, M.A. *Second Edition. Revised. Crown 8vo. 2s. 6d.*
- Fulford (H. W.), M.A. THE EPISTLE OF ST. JAMES.** With Notes and Introduction. *Fcap. 8vo. 1s. 6d. net.*
[Churchman's Bible.]
- G. G. and F. G. G. JOHN BULL'S ADVENTURES IN THE FISCAL WONDERLAND.** By CHARLES GRAKE. With 46 Illustrations by F. CARRUTHERS GOULD. *Second Ed. Crown 8vo. 2s. 6d. net.*
- Gambado (Geoffrey Esq.). AN ACADEMY FOR GROWN HORSEMEN:** Containing the completest Instructions for Walking, Trotting, Cantering, Galloping, Stumbling, and Tumbling. Illustrated with 27 Coloured Plates, and adorned with a Portrait of the Author. *Fcap. 8vo. 3s. 6d. net.*
[Illustrated Pocket Library.]

- Gaskell (Mrs.)**, CRANFORD. Edited by E. V. LUCAS. *Small Pott 8vo. Cloth, 1s. 6d. net; leather, 2s. 6d. net.* [Little Library.]
- Gasquet**, the Right Rev. Abbot, O.S.B. ENGLISH MONASTIC LIFE. With Coloured and other Illustrations. *Demy 8vo. 7s. 6d. net.* [Antiquary's Books.]
- George (H. B.)**, M.A., Fellow of New College, Oxford. BATTLES OF ENGLISH HISTORY. With numerous Plans. *Fourth Edition. Crown 8vo. 6s.*
- A HISTORICAL GEOGRAPHY OF THE BRITISH EMPIRE. *Cr. 8vo. 3s. 6d. net.*
- Gibbins (H. de B.)**, Litt.D., M.A. INDUSTRY IN ENGLAND: HISTORICAL OUTLINES. With 5 Maps. *Third Edition. Demy 8vo. 10s. 6d.*
- A COMPANION GERMAN GRAMMAR. *Crown 8vo. 1s. 6d.*
- THE INDUSTRIAL HISTORY OF ENGLAND. *Tenth Edition.* Revised. With Maps and Plans. *Crown 8vo. 3s.* [University Extension Series.]
- THE ECONOMICS OF COMMERCE. *Crown 8vo. 1s. 6d.* [Commercial Series.]
- COMMERCIAL EXAMINATION PAPERS. *Crown 8vo. 1s. 6d.* [Commercial Series.]
- BRITISH COMMERCE AND COLONIES FROM ELIZABETH TO VICTORIA. *Third Edition. Crown 8vo. 2s.* [Commercial Series.]
- ENGLISH SOCIAL REFORMERS. *Second Edition. Crown 8vo. 2s. 6d.* [University Extension Series.]
- Gibbins (H. de B.)**, Litt.D., M.A., and **Hadfield (E. A.)**, of the Hecla Works, Sheffield. A SHORTER WORKING DAY. *Crown 8vo. 2s. 6d.* [Social Questions Series.]
- Gibbon (Edward)**. THE DECLINE AND FALL OF THE ROMAN EMPIRE. A New Edition, edited with Notes, Appendices, and Maps, by J. E. BURR, M.A., Litt.D., Fellow of Trinity College, Dublin. *In Seven Volumes. Demy 8vo. Gilt top, 8s. 6d. each. Also, Crown 8vo. 6s. each.*
- MEMOIRS OF MY LIFE AND WRITINGS. Edited, with an Introduction and Notes, by G. BIRKBECK HILL, LL.D. *Crown 8vo. 6s.*
- Gibson (E. C. S.)**, D.D., Vicar of Leeds. THE BOOK OF JOB. With Introduction and Notes. *Demy 8vo. 6s.* [Westminster Commentaries.]
- THE XXXIX. ARTICLES OF THE CHURCH OF ENGLAND. With an Introduction. *Fourth Edition in One Vol. Demy 8vo. 12s. 6d.* [Handbooks of Theology.]
- JOHN HOWARD**. With 12 Illustrations. *Fcap 8vo. Cloth, 3s. 6d.; leather, 4s. net.* [Little Biographies.]
- Gilbert (A. R.)**. See W. Wilberforce.
- Godfrey (Elizabeth)**. A BOOK OF REMEMBRANCE. *Demy 16mo. 2s. 6d. net.*
- Godley (A. D.)**, M.A., Fellow of Magdalen College, Oxford. LYRA FRIVOLA. *Third Edition. Fcap. 8vo. 2s. 6d.*
- VERSES TO ORDER. *Second Edition. Crown 8vo. 2s. 6d.*
- SECOND STRINGS. *Fcap. 8vo. 2s. 6d.*
- A new volume of humorous verse uniform with *Lyra Frivola*.
- Goldsmith (Oliver)**. THE VICAR OF WAKEFIELD. With 24 Coloured Plates by T. ROWLANDSON. *Royal 8vo. One Guinea net.*
- Reprinted from the edition of 1817. [Burlington Library.]
- Also *Fcap. 8vo. 3s. 6d. net.* Also a limited edition on large Japanese paper. *30s. net.* [Illustrated Pocket Library.]
- Also *Fcap. 32mo.* With 10 Plates in Photographure by Tony Johannot. *Leather, 2s. 6d. net.*
- Goudge (H. L.)**, M.A., Principal of Wells Theological College. THE FIRST EPISTLE TO THE CORINTHIANS. With Introduction and Notes. *Demy 8vo. 6s.* [Westminster Commentaries.]
- Graham (P. Anderson)**. THE RURAL EXODUS. *Crown 8vo. 2s. 6d.* [Social Questions Series.]
- Granger (F. B.)**, M.A., Litt.D. PSYCHOLOGY. *Second Edition. Crown 8vo. 2s. 6d.* [University Extension Series.]
- THE SOUL OF A CHRISTIAN. *Crown 8vo. 6s.*
- Gray (E. M'Queen)**. GERMAN PASSAGES FOR UNSEEN TRANSLATION. *Crown 8vo. 2s. 6d.*
- Gray (P. L.)**, B.Sc., formerly Lecturer in Physics in Mason University College, Birmingham. THE PRINCIPLES OF MAGNETISM AND ELECTRICITY: an Elementary Text-Book. With 181 Diagrams. *Crown 8vo. 2s. 6d.*
- Green (G. Buckland)**, M.A., Assistant Master at Edinburgh Academy, late Fellow of St. John's College, Oxon. NOTES ON GREEK AND LATIN SYNTAX. *Crown 8vo. 2s. 6d.*
- Green (E. T.)**, M.A. THE CHURCH OF CHRIST. *Crown 8vo. 6s.* [Churchman's Library.]
- Greenidge (A. H. J.)**, M.A. A HISTORY OF ROME: During the Later Republic and the Early Principate. *In Six Volumes. Demy 8vo. Vol. I. (133-104 B.C.) 12s. 6d. net.*
- Greenwell (Dora)**, THE POEMS OF. From the edition of 1848. *Leather, 2s. net.* [Miniature Library.]
- Gregory (E. A.)** THE VAULT OF HEAVEN. A Popular Introduction to Astronomy. With numerous Illustrations. *Crown 8vo. 2s. 6d.* [University Extension Series.]

- Gregory (Miss E. G.)** HEAVENLY WISDOM. Selections from the English Mystics. *Pott 8vo. Cloth 2s.; leather, 2s. 6d. net.*
[Library of Devotion. Nearly Ready.]
- Greville Minor.** A MODERN JOURNAL. Edited by J. A. SPENDER. *Crown 8vo. 3s. 6d. net.*
- Grinling (G. H.)** A HISTORY OF THE GREAT NORTHERN RAILWAY, 1845-95. With Illustrations. Revised, with an additional chapter. *Demy 8vo. 10s. 6d.*
- Grubb (E. C.)** BUILDERS' QUANTITIES. With many Illustrations. *Crown 8vo. 4s. 6d.* [Textbooks of Technology.]
- Guiney (L. L.)** RICHARD HURRELL FROUDE. Illustrated. *Demy 8vo. 10s. 6d. net.*
- Gwynn (M. L.)** A BIRTHDAY BOOK. *Royal 8vo. 12s.*
- Hackett (John), B.D.** A HISTORY OF THE ORTHODOX CHURCH OF CYPRUS. With Maps and Illustrations. *Demy 8vo. 15s. net.*
- Haddon (A. C.), Sc.D., F.R.S.** HEAD-HUNTERS, BLACK, WHITE, AND BROWN. With many Illustrations and a Map. *Demy 8vo. 15s.*
- Hadfield (R. A.)** See H. de B. Gibbins.
- Hall (R. N.) and Neal (W. G.)** THE ANCIENT RUINS OF RHODESIA. With numerous Illustrations. *Second Edition, revised, Demy 8vo. 10s. 6d. net.*
- Hall (R. N.)** THE GREAT ZIMBABWE. With numerous Illustrations. *Royal 8vo. 21s. net.*
- Hamilton (F. J.), D.D., and Brooks (E. W.)** ZACHARIAH OF MITYLENE. Translated into English. *Demy 8vo. 12s. 6d. net.*
[Byzantine Texts.]
- Hammond (J. L.)** CHARLES JAMES FOX: A Biographical Study. *Demy 8vo. 10s. 6d.*
- Hannay (D.)** A SHORT HISTORY OF THE ROYAL NAVY, FROM EARLY TIMES TO THE PRESENT DAY. Illustrated. *Two Volumes. Demy 8vo. 7s. 6d. each.* Vol. I. 1200-1688.
- Hannay (James O.), M.A.** THE SPIRIT AND ORIGIN OF CHRISTIAN MONASTICISM. *Crown 8vo. 6s.*
- THE WISDOM OF THE DESERT.** *Crown 8vo. 3s. 6d. net.*
- Hare, (A. T.), M.A.** THE CONSTRUCTION OF LARGE INDUCTION COILS. With numerous Diagrams. *Demy 8vo. 6s.*
- Harrison (Clifford)** READING AND READERS. *Fcap. 8vo. 2s. 6d.*
- Hawthorne (Nathaniel)** THE SCARLET LETTER. Edited by PERCY DEARMER. *Small Pott 8vo. Cloth, 1s. 6d. net; leather, 2s. 6d. net.* [Little Library.]
- HEALTH, WEALTH AND WISDOM.** *Crown 8vo. 1s. net.*
- Heath (Dudley)** MINIATURES. With many Plates in Photogravure. *Wide Royal 8vo. 25s. net.* [Connoisseurs Library.]
- Hedin (Svan)** Gold Medalist of the Royal Geographical Society. THROUGH ASIA. With 300 Illustrations from Sketches and Photographs by the Author, and Maps. *Two Volumes. Royal 8vo. 36s. net.*
- Hello (Ernest)** STUDIES IN SAINTSHIP. Translated from the French by V. M. CRAWFORD. *Fcap. 8vo. 3s. 6d.*
- Henderson (B. W.)**, Fellow of Exeter College, Oxford. THE LIFE AND PRINCIPATE OF THE EMPEROR NERO. With Illustrations. *Demy 8vo. 10s. 6d. net.*
- Henderson (T. F.)** A LITTLE BOOK OF SCOTTISH VERSE. *Small Pott 8vo. Cloth, 1s. 6d. net; leather, 2s. 6d. net.* [Little Library.]
- ROBERT BURNS.** With 12 Illustrations. *Fcap. 8vo. Cloth, 3s. 6d.; leather, 4s. net.* [Little Biographies.]
- Henley (W. E.)** ENGLISH LYRICS. *Crown 8vo. Gilt top. 3s. 6d.*
- Henley (W. E.) and Whibley (C.)** A BOOK OF ENGLISH PROSE. *Crown 8vo. Buckram, gilt top. 6s.*
- Henson (E. H.), B.D.** Canon of Westminster. APOSTOLIC CHRISTIANITY: AS ILLUSTRATED BY THE EPISTLES OF ST. PAUL TO THE CORINTHIANS. *Crown 8vo. 6s.*
- LIGHT AND LEAVEN: HISTORICAL AND SOCIAL SERMONS.** *Crown 8vo. 6s.*
- DISCIPLINE AND LAW.** *Fcap. 8vo. 2s. 6d.*
- THE EDUCATION ACT—AND AFTER.** An Appeal addressed with all possible respect to the Nonconformists. *Crown 8vo. 1s.*
- Herbert (George)** THE TEMPLE. Edited, with an Introduction and Notes, by E. C. S. GIBSON, D.D., Vicar of Leeds. *Small Pott 8vo. Cloth, 2s.; leather, 2s. 6d. net.* [Library of Devotion.]
- Herbert of Cherbury (Lord)** THE LIFE OF. Written by himself. *Leather, 2s. net.* From the edition printed at Strawberry Hill in the year 1764. [Miniature Library.]
- Hewins (W. A. S.), B.A.** ENGLISH TRADE AND FINANCE IN THE SEVENTEENTH CENTURY. *Crown 8vo. 2s. 6d.* [University Extension Series.]
- Heywood (W.)** PALIO AND PONTE: A Book of Tuscan Games. Illustrated. *Royal 8vo. 21s. net.*
- Hilbert (F.)** THE AIR GUN: or, How the Mastermans and Dobson Major nearly lost their Holidays. Illustrated. *Demy 16mo. 2s. 6d.* [Little Blue Books.]
- Hill (Clare)**, Registered Teacher to the City and Guilds of London Institute. MILLINERY, THEORETICAL, AND PRACTICAL. With numerous Diagrams. *Cr. 8vo. 2s.* [Textbooks of Technology.]

- Hill (Henry), B.A.**, Headmaster of the Boy's High School, Worcester, Cape Colony. A SOUTH AFRICAN ARITHMETIC. *Crown 8vo.* 3s. 6d.
This book has been specially written for use in South African schools.
- Hobhouse (Emily).** THE BRUNT OF THE WAR. With Map and Illustrations. *Crown 8vo.* 6s.
A Colonial Edition is also published.
- Hobhouse (L. T.)**, Fellow of C.C.C., Oxford. THE THEORY OF KNOWLEDGE. *Demy 8vo.* 21s.
[Social Questions Series.]
- Hobson (J. A.), M.A.** PROBLEMS OF POVERTY: An Inquiry into the Industrial Condition of the Poor. *Fourth Edition. Crown 8vo.* 2s. 6d.
[Social Questions Series.]
- THE PROBLEM OF THE UNEMPLOYED. *Crown 8vo.* 2s. 6d.
[Social Questions Series.]
- INTERNATIONAL TRADE: A Study of Economic Principles. *Crown 8vo.* 2s. 6d. net.
- Hodgkin (T.), D.C.L.** GEORGE FOX, THE QUAKER. With Portrait. *Crown 8vo.* 3s. 6d.
[Leaders of Religion.]
- Hogg (Thomas Jefferson).** SHELLEY AT OXFORD. With an Introduction by R. A. STREATFIELD. *Fcap. 8vo.* 2s. net.
- Holden-Stone (G. de).** THE AUTOMOBILE INDUSTRY. *Fcap. 8vo.* 2s. 6d. net.
[Books on Business.]
- Holdich (Sir T. H.), K.C.I.E.** THE INDIAN BORDERLAND: being a Personal Record of Twenty Years. Illustrated. *Demy 8vo.* 15s. net.
- Holdsworth (W. S.), M.A.** A HISTORY OF ENGLISH LAW. In Two Volumes. Vol. I. *Demy 8vo.* 10s. 6d. net.
- Holyoake (G. J.).** THE CO-OPERATIVE MOVEMENT TO-DAY. *Third Edition. Crown 8vo.* 2s. 6d.
[Social Questions Series.]
- Hoppner,** A LITTLE GALLERY OF. Twenty examples in photogravure of his finest work. *Demy 16mo.* 2s. 6d. net.
[Little Galleries.]
- Horace:** THE ODES AND EPODES. Translated by A. D. GODLEY, M.A., Fellow of Magdalen College, Oxford. *Crown 8vo.* 2s.
[Classical Translations.]
- Horsburgh (E. L. S.), M.A.** WATERLOO: A Narrative and Criticism. With Plans. *Second Edition. Crown 8vo.* 5s.
- SAVONAROLA.** With Portraits and Illustrations. *Second Edition. Fcap. 8vo.* Cloth, 3s. 6d.; leather, 4s. net.
[Little Biographies.]
- Horton (R. F.), D.D.** JOHN HOWE. With Portrait. *Crown 8vo.* 3s. 6d.
[Leaders of Religion.]
- Hosie (Alexander).** MANCHURIA. With Illustrations and a Map. *Second Edition. Demy 8vo.* 10s. 6d. net.
- How (F. D.).** SIX GREAT SCHOOLMASTERS. With Portraits. *Demy 8vo.* 7s. 6d.
- Howell (G.).** TRADE UNIONISM—NEW AND OLD. *Third Edition. Crown 8vo.* 2s. 6d.
[Social Questions Series.]
- Hudson (Robert).** MEMORIALS OF A WARWICKSHIRE VILLAGE. With many Illustrations. *Demy 8vo.* 10s. 6d. net.
- Hughes (G. E.).** THE PRAISE OF SHAKESPEARE. An English Anthology. With a Preface by SIDNEY LEE. *Demy 8vo.* 3s. 6d. net.
- Hughes (Thomas).** TOM BROWN'S SCHOOL DAYS. With an Introduction and Notes by VERNON RENDALL. *Leather. Royal 32mo.* 2s. 6d. net.
- Hutchinson (Horace G.).** THE NEW FOREST. Described by, Illustrated in colour with 50 Pictures by WALTER TYNDALE and 4 by Miss Lucy Kemp Walch. *Large Demy 8vo.* 21s. net.
- Hutton (A. W.), M.A.** CARDINAL MANNING. With Portrait. *Crown 8vo.* 3s. 6d.
[Leaders of Religion.]
- Hutton (R. H.).** CARDINAL NEWMAN. With Portrait. *Crown 8vo.* 3s. 6d.
[Leaders of Religion.]
- Hutton (W. H.), M.A.** THE LIFE OF SIR THOMAS MORE. With Portraits. *Second Edition. Crown 8vo.* 5s.
- WILLIAM LAUD.** With Portrait. *Second Edition. Crown 8vo.* 3s. 6d.
[Leaders of Religion.]
- Hyett (F. A.).** A SHORT HISTORY OF FLORENCE. *Demy 8vo.* 7s. 6d. net.
- HYPNEROTOMACHIA POLIPHILI UBI HUMANA OMNIA NGN NISI SOMNIUM ESSE DOCET ATQUE OBITER PLURIMA SCITU SANE QUAM DIGNA COMMEMORAT.** An edition limited to 350 copies on handmade paper. *Folio. Three Guineas net.*
- Ibsen (Henrik).** BRAND. A Drama. Translated by WILLIAM WILSON. *Third Edition. Crown 8vo.* 3s. 6d.
- Inge (W. E.), M.A.**, Fellow and Tutor of Hertford College, Oxford. CHRISTIAN MYSTICISM. The Bampton Lectures for 1899. *Demy 8vo.* 10s. 6d. net.
- LIGHT, LIFE, AND LOVE:** A Selection from the German Mystics. With an Introduction and Notes. *Small Fcap. 8vo.* Cloth 2s.; leather, 2s. 6d. net.
[Library of Devotion.]
- Innes (A. D.), M.A.** A HISTORY OF THE BRITISH IN INDIA. With Maps and Plans. *Crown 8vo.* 7s. 6d.

- Jackson (H.), M.A.** A PRIMER OF BUSINESS. *Third Edition. Crown 8vo. 1s. 6d.* [Commercial Series.]
- Jackson (F. Hamilton).** SICILY. With many Illustrations by the Author. *Small Pott 8vo. Cloth, 3s.; Leather, 3s. 6d. net.* [Little Guides.]
- Jacob (F.), M.A.** JUNIOR FRENCH EXAMINATION PAPERS. *Fcap. 8vo. 1s.* [Junior Examination Series.]
- Jeanes (J. Stephen).** TRUSTS, POOLS, AND CORNERS. *Crown 8vo. 2s. 6d.* [Social Questions Series.]
- Jeffreys (D. Gwyn).** DOLLY'S THEATRICALS. Described and Illustrated with 24 Coloured Pictures. *Pott 4to. 2s. 6d.*
- Jenks (E.), M.A.,** Reader of Law in the University of Oxford. ENGLISH LOCAL GOVERNMENT. *Crown 8vo. 2s. 6d.* [University Extension Series.]
- Jessopp (Augustus), D.D.** JOHN DONNE. With Portrait. *Crown 8vo. 3s. 6d.* [Leaders of Religion.]
- Jevons (F. B.), M.A.,** Litt.D., Principal of Hatfield Hall, Durham. EVOLUTION. *Crown 8vo. 2s. 6d.* [Churchman's Library.]
- AN INTRODUCTION TO THE HISTORY OF RELIGION.** *Second Edition. Demy 8vo. 10s. 6d.* [Handbooks of Theology.]
- Johnston (Sir H. H.), K.C.B.** BRITISH CENTRAL AFRICA. With nearly 200 Illustrations and Six Maps. *Second Edition. Crown 4to. 18s. net.*
- Jones (H.).** A GUIDE TO PROFESSIONS AND BUSINESS. *Crown 8vo. 1s. 6d.* [Commercial Series.]
- Jones (L. A. Atherley), K.C.,** M.P., and **Ballot (Hugh H. L.).** THE MINERS' GUIDE TO THE COAL MINES' REGULATION ACTS. *Crown 8vo. 8s. 6d. net.* [Nearly Ready.]
- Julian (Lady) of Norwich.** REVELATIONS OF DIVINE LOVE. Edited by GRACE WARRACK. *Crown 8vo. 3s. 6d.*
- Juvenal.** THE SATIRES OF. Translated by S. G. OWEN. *Crown 8vo. 2s. 6d.* [Classical Translations.]
- Kaufmann (M.).** SOCIALISM AND MODERN THOUGHT. *Crown 8vo. 2s. 6d.* [Social Questions Series.]
- Keating (J. F.), D.D.** THE AGAPE AND THE EUCHARIST. *Crown 8vo. 3s. 6d.*
- Keats (John).** THE POEMS OF. With an Introduction by L. BINYON, and Notes by J. MASEFIELD. *Small Pott 8vo. Cloth, 1s. 6d. net; leather, 2s. 6d. net.* [Little Library.]
- Keats.** THE POEMS OF. Edited with Introduction and Notes by E. de Selincourt, M.A. *Demy 8vo. 7s. 6d. net.*
- Keble (John).** THE CHRISTIAN YEAR. With an Introduction and Notes by W. LOCK, D.D., Warden of Keble College. Illustrated by R. ANNING BELL. *Second Edition. Fcap. 8vo. 3s. 6d.; padded morocco, 5s.*
- THE CHRISTIAN YEAR.** With Introduction and Notes by WALTER LOCK, D.D., Warden of Keble College. *Second Edition. Small Pott 8vo. Cloth, 2s.; leather, 2s. 6d. net.* [Library of Devotion.]
- LYRA INNOCENTIUM.** Edited, with Introduction and Notes, by WALTER LOCK, D.D., Warden of Keble College, Oxford. *Small Pott 8vo. Cloth, 2s.; leather, 2s. 6d. net.* [Library of Devotion.]
- Kempis (Thomas A.).** THE IMITATION OF CHRIST. With an Introduction by DEAN FARRAR. Illustrated by C. M. GERE. *Second Edition. Fcap. 8vo. 3s. 6d.; padded morocco, 5s.*
- THE IMITATION OF CHRIST.** A Revised Translation, with an Introduction by C. BIGG, D.D., late Student of Christ Church. *Third Edition. Small Pott 8vo. Cloth, 2s.; leather, 2s. 6d. net.* [Library of Devotion.]
- A practically new translation of this book which the reader has, almost for the first time, exactly in the shape in which it left the hands of the author.
- THE SAME EDITION IN LARGE TYPE.** *Crown 8vo. 3s. 6d.*
- Kennedy (James Houghton), D.D.,** Assistant Lecturer in Divinity in the University of Dublin. ST. PAUL'S SECOND AND THIRD EPISTLES TO THE CORINTHIANS. With Introduction, Dissertations and Notes. *Crown 8vo. 6s.*
- Kestell (J. D.).** THROUGH SHOT AND FLAME: Being the Adventures and Experiences of J. D. KESTELL, Chaplain to General Christian de Wet. *Crown 8vo. 6s.*
- Kimmins (G. W.), M.A.** THE CHEMISTRY OF LIFE AND HEALTH. Illustrated. *Crown 8vo. 2s. 6d.* [University Extension Series.]
- Kingslake (A. W.).** EOTHEN. With an Introduction and Notes. *Small Pott 8vo. Cloth, 1s. 6d. net; leather, 2s. 6d. net.* [Little Library.]
- Kipling (Rudyard).** BARRACK-ROOM BALLADS. *73rd Thousand. Cr. 8vo. Twentieth Edition. 6s.*
- A Colonial Edition is also published.
- THE SEVEN SEAS.** *62nd Thousand Ninth Edition. Crown 8vo, gilt top, 6s.*
- A Colonial Edition is also published.
- THE FIVE NATIONS.** *41st Thousand. Second Edition. Crown 8vo. 6s.*
- A Colonial Edition is also published.
- DEPARTMENTAL DITTIES.** *Sixteenth Edition. Crown 8vo. Buckram. 6s.*
- A Colonial Edition is also published.

- Knowing (R. J.), M.A.,** Professor of New Testament Exegesis at King's College, London. **THE EPISTLE OF S. JAMES.** With Introduction and Notes. *Demy 8vo. 6s.* [Westminster Commentaries.]
- Lamb (Charles and Mary),** **THE WORKS OF E. V. LUCAS.** With Numerous Illustrations. *In Seven Volumes. Demy 8vo. 7s. 6d. each.*
- THE ESSAYS OF ELIA.** With over 100 Illustrations by A. GARTH JONES, and an Introduction by E. V. LUCAS. *Demy 8vo. 10s. 6d.*
- ELIA, AND THE LAST ESSAYS OF ELIA.** Edited by E. V. LUCAS. *Small Pott 8vo. Cloth, 1s. 6d. net; leather, 2s. 6d. net.* [Little Library.]
- THE KING AND QUEEN OF HEARTS:** An 1805 Book for Children. Illustrated by WILLIAM MULREADY. A new edition, in facsimile, edited by E. V. LUCAS. *1s. 6d.*
- Lambert (F. A. H.),** **SURREY.** Illustrated by E. H. NEW. *Small Pott 8vo, cloth, 2s.; leather, 3s. 6d. net.* [Little Guides.]
- Lambros (Professor),** **ECTHESIS CHRONICA.** Edited by *Demy 8vo. 7s. 6d. net.* [Byzantine Texts.]
- Lane-Poole (Stanley),** **A HISTORY OF EGYPT IN THE MIDDLE AGES.** Fully Illustrated. *Crown 8vo. 6s.*
- Langbridge (F.) M.A.,** **BALLADS OF THE BRAVE:** Poems of Chivalry, Enterprise, Courage, and Constancy. *Second Edition. Crown 8vo. 2s. 6d.*
- Law (William),** **A SERIOUS CALL TO A DEVOUT AND HOLY LIFE.** Edited, with an Introduction, by C. BIGG, D.D., late Student of Christ Church. *Small Pott 8vo, cloth, 2s.; leather, 2s. 6d. net.* [Library of Devotion.]
This is a reprint, word for word and line for line, of the *Editio Princeps.*
- Leach (Henry),** **THE DUKE OF DEVONSHIRE.** A Biography. With 12 Illustrations. *Demy 8vo. 12s. 6d. net.*
A Colonial Edition is also published.
- Lee (Captain Melville),** **A HISTORY OF POLICE IN ENGLAND.** *Crown 8vo. 7s. 6d.*
- Leigh (Percival),** **THE COMIC ENGLISH GRAMMAR.** Embellished with upwards of 50 characteristic Illustrations by JOHN LERCH. *Post 16mo. 2s. 6d. net.*
- Lewes (V. R.), M.A.,** **AIR AND WATER.** Illustrated. *Crown 8vo. 2s. 6d.* [University Extension Series.]
- Lisle (Miss F. de),** **BURNE-JONES.** With 30 Illustrations. *Demy 16mo. 2s. 6d. net.* [Little Books on Art.]
- Littlehales (H.),** See C. Wordsworth.
- Lock (Walter), D.D.,** Warden of Keble College. **ST. PAUL, THE MASTER-BUILDER.** *Crown 8vo. 3s. 6d.*
- JOHN KEBLE.** With Portrait. *Crown 8vo. 3s. 6d.* [Leaders of Religion.]
- Looker (F.),** **LONDON LYRICS.** Edited by A. D. GODLEY, M.A. *Small Pott 8vo, cloth, 2s. 6d. net; leather, 2s. 6d. net.* [Little Library.]
- Longfellow, SELECTIONS FROM.** Edited by LILIAN M. FAITHFULL. *Small Pott 8vo, cloth, 1s. 6d. net; leather, 2s. 6d. net.* [Little Library.]
- Lorimer (George Horace),** **LETTERS FROM A SELF-MADE MERCHANT TO HIS SON.** *Eleventh Edition. Crown 8vo. 6s.*
A Colonial Edition is also published.
- Lover (Samuel),** **HANDY ANDY.** With 24 Illustrations by the Author. *Fcap. 8vo. 3s. 6d. net.* [Illustrated Pocket Library.]
- E. V. L. and C. L. G.,** **ENGLAND DAY BY DAY:** Or, The Englishman's Handbook to Efficiency. Illustrated by GEORGE MORROW. *Fourth Edition. Fcap. 4to. 1s. net.*
A burlesque Year-Book and Almanac.
- Lucian, SIX DIALOGUES** (Nigrinus, Icaro-Menippus, The Cock, The Ship, The Parasite, The Lover of Falsehood). Translated by S. T. IRWIN, M.A., Assistant Master at Clifton; late Scholar of Exeter College, Oxford. *Crown 8vo. 3s. 6d.* [Classical Translations.]
- Lyde (L. W.), M.A.,** **A COMMERCIAL GEOGRAPHY OF THE BRITISH EMPIRE.** *Third Edition. Crown 8vo. 2s.* [Commercial Series.]
- Lydon (Noel S.),** **A JUNIOR GEOMETRY.** With numerous diagrams. *Crown 8vo. 2s.* [Junior School Books.]
- Lytton (Hon. Mrs. A.),** **WOMEN AND THEIR WORK.** *Crown 8vo. 2s. 6d.*
- M. M.,** **HOW TO DRESS AND WHAT TO WEAR.** *Crown 8vo. 2s. net.*
- Macaulay (Lord),** **CRITICAL AND HISTORICAL ESSAYS.** Edited by F. C. MONTAGUE, M.A. *Three Volumes. Cr. 8vo. 18s.*
The only edition of this book completely annotated.
- M'Allen (J. E. B.), M.A.,** **THE PRINCIPLES OF BOOKKEEPING BY DOUBLE ENTRY.** *Crown 8vo. 2s.* [Commercial Series.]
- MacCulloch (J. A.),** **COMPARATIVE THEOLOGY.** *Crown 8vo. 6s.* [Churchman's Library.]
- MacCunn (F.),** **JOHN KNOX.** With Portrait. *Crown 8vo. 3s. 6d.* [Leaders of Religion.]
- McDermott, (E. R.),** Editor of the *Railway News*, City Editor of the *Daily News*. **RAILWAYS.** *Crown 8vo. 2s. 6d. net.* [Books on Business]

- M'Dowall (A. S.)** CHATHAM. With 12 Illustrations. *Fcap. 8vo. Cloth, 3s. 6d.; leather, 4s. net.* [Little Biographies.]
- Mackay (A. M.)** THE CHURCHMAN'S INTRODUCTION TO THE OLD TESTAMENT. *Crown 8vo. 3s. 6d.* [Churchman's Library.]
- Magnus (Laurie), M.A.** A PRIMER OF WORDSWORTH. *Crown 8vo. 2s. 6d.*
- Mahafy (J. P.), Litt.D.** A HISTORY OF THE EGYPT OF THE PTOLEMIES. Fully Illustrated. *Crown 8vo. 6s.*
- Maitland (F. W.), LL.D.** Downing Professor of the Laws of England in the University of Cambridge. CANON LAW IN ENGLAND. *Royal 8vo. 7s. 6d.*
- Malden (H. E.), M.A.** ENGLISH RECORDS. A Companion to the History of England. *Crown 8vo. 3s. 6d.*
- THE ENGLISH CITIZEN: HIS RIGHTS AND DUTIES.** *Crown 8vo. 1s. 6d.*
- Marchant (R. C.), M.A.** Fellow of Peterhouse, Cambridge. A GREEK ANTHOLOGY. *Second Edition. Crown 8vo. 3s. 6d.*
- Marchant (R. C.), M.A., and Cook (A. M.), M.A.** PASSAGES FOR UNSEEN TRANSLATION. *Second Edition. Crown 8vo. 3s. 6d.*
- Marr (J. E.), F.R.S.** Fellow of St John's College, Cambridge. THE SCIENTIFIC STUDY OF SCENERY. *Second Edition. Illustrated. Crown 8vo. 6s.*
- AGRICULTURAL GEOLOGY.** With numerous Illustrations. *Crown 8vo. 6s.*
- Marvell (Andrew).** THE POEMS OF EDWARD WRIGHT. *Small Pott 8vo, cloth, 1s. 6d. net; leather, 2s. 6d. net.* [Little Library.]
- Maskell (A.)** IVORIES. With many plates in Collotype and Photogravure. *Wide Royal 8vo. 25s. net.* [Connoisseurs Library.]
- Mason (A. J.), D.D.** THOMAS CRANMER. With Portrait. *Crown 8vo. 3s. 6d.* [Leaders of Religion.]
- Masseo (George).** THE EVOLUTION OF PLANT LIFE: Lower Forms. With Illustrations. *Crown 8vo. 2s. 6d.* [University Extension Series.]
- Masterman (G. F. G.), M.A.** TENNYSON AS A RELIGIOUS TEACHER. *Crown 8vo. 6s.*
- May (Phil)** THE PHIL MAY ALBUM. *Second Edition. 4to. 1s. net.*
- Mellows (Emma S.).** A SHORT STORY OF ENGLISH LITERATURE. *Crown 8vo. 3s. 6d.*
- Michell (E. B.)** THE ART AND PRACTICE OF HAWKING. With 3 Photogravures by G. E. LODGE, and other Illustrations. *Demy 8vo. 10s. 6d.*
- Millaud (J. G.)** THE LIFE AND LETTERS OF SIR JOHN EVERETT MILLAIS, President of the Royal Academy. With 319 Illustrations, of which 9 are in Photogravure. *2 vols. Royal 8vo. 20s. net.*
- Millaud.** A LITTLE GALLERY OF. Twenty examples in Photogravure of his finest work. *Demy 16mo. 2s. 6d. net.* [Little Galleries.]
- Mills (G. T.), M.I.M.E.** Principal of the Borough Polytechnic College. TECHNICAL ARITHMETIC AND GEOMETRY. With Diagrams. *Crown 8vo. 3s. 6d.* [Textbooks of Technology.]
- Milne (J. G.), M.A.** A HISTORY OF ROMAN EGYPT. Fully Illustrated. *Crown 8vo. 6s.*
- Milton, John,** THE POEMS OF, BOTH ENGLISH AND LATIN, Compos'd at several times. Printed by his true Copies. The Songs were set in Musick by Mr. HENRY LAWES, Gentleman of the Kings Chappel, and one of His Majesties Private Musick. Printed and publish'd according to Order. Printed by RUTH RAWORTH for HUMPHREY MOSELEY, and are to be sold at the signe of the Princes Armes in Pauls Church-yard, 1645.
- THE MINOR POEMS OF JOHN MILTON.** Edited by H. C. BRECHING, M.A., Canon of Westminster. *Small Pott 8vo, cloth, 1s. 6d. net; leather, 2s. 6d. net.* [Little Library.]
- Minchin (H. G.), M.A.** A LITTLE GALLERY OF ENGLISH POETS. *Demy 16mo. 2s. 6d. net.* [Little Galleries.]
- Mitchell (P. Chalmers), M.A.** OUTLINES OF BIOLOGY. Illustrated. *Second Edition. Crown 8vo. 6s.* A text-book designed to cover the Schedule issued by the Royal College of Physicians and Surgeons.
- 'Moll (A.)'** MINING AND MINING INVESTMENTS. *Crown 8vo. 2s. 6d. net.* [Books on Business.]
- Moir (D. M.)** MANSIE WAUCH. Edited by T. F. HENDERSON. *Small Pott 8vo. Cloth, 1s. 6d. net; leather, 2s. 6d. net.* [Little Library.]
- Moore (H. E.)** BACK TO THE LAND: An Inquiry into the cure for Rural Depopulation. *Crown 8vo. 2s. 6d.* [Social Questions Series.]
- Morfill (W. R.),** Oriel College, Oxford. A HISTORY OF RUSSIA FROM PETER THE GREAT TO ALEXANDER II. With Maps and Plans. *Crown 8vo. 7s. 6d.*
- Morich (E. J.),** late of Clifton College. GERMAN EXAMINATION PAPERS IN MISCELLANEOUS GRAMMAR AND IDIOMS. *Sixth Edition. Crown 8vo. 2s. 6d.* [School Examination Series.] A KEY, issued to Tutors and Private Students only, to be had on application to the Publishers. *Second Edition. Crown 8vo. 6s. net.*

Morris (J. E.) THE NORTH RIDING OF YORKSHIRE. Illustrated by R. J. S. BERTRAM, *Small Pott 8vo, cloth, 3s.; leather, 3s. 6d. net.*

[Little Guides.

Morton (Miss Anderson). See Miss Brodrick.

Moule (H. G. G.), D.D., Lord Bishop of Durham. CHARLES SIMEON. With Portrait. *Crown 8vo. 3s. 6d.*

[Leaders of Religion.

Muir (M. M. Pattison), M.A. THE CHEMISTRY OF FIRE. The Elementary Principles of Chemistry. Illustrated. *Crown 8vo. 2s. 6d.*

[University Extension Series.

Mundella (V. A.), M.A. See J. T. Dunn.

Naval Officer (A.) THE ADVENTURES OF A POST CAPTAIN. With 24 coloured plates by Mr. WILLIAMS. *Fcap. 8vo, 3s. 6d. net.* [Illustrated Pocket Library.

Neal (W. G.) See R. N. Hall.

Newman (J. H.) and others. LYRA APOSTOLICA. With an Introduction by CANON SCOTT HOLLAND, and Notes by CANON BRECHING, M.A. *Small Pott 8vo, Cloth, 2s.; leather, 2s. 6d. net.*

[Library of Devotion.

Nichols (J. B. B.) A LITTLE BOOK OF ENGLISH SONNETS. *Small Pott 8vo, Cloth, 1s. 6d. net; leather, 2s. 6d. net.*

[Little Library.

Nicklin (T.), M.A. EXAMINATION PAPERS IN THUCYDIDES. *Crown 8vo. 2s.*

Nimrod. THE LIFE AND DEATH OF JOHN MYTTON, ESQ. With 18 Coloured Plates by HENRY ALKEN and T. J. RAWLINS. *Third Edition. Fcap. 8vo, 3s. 6d. net.*

Also a limited edition on large Japanese paper. *30s. net.*

[Illustrated Pocket Library.

THE LIFE OF A SPORTSMAN. With 35 Coloured Plates by HENRY ALKEN. *Fcap. 8vo. 4s. 6d. net.*

Also a limited edition on large Japanese paper. *30s. net.*

[Illustrated Pocket Library.

Norway (A. H.), Author of 'Highways and Byways in Devon and Cornwall.' NAPLES: PAST AND PRESENT. With many Illustrations. *Crown 8vo, 6s.*

Novalis. THE DISCIPLES AT SAIS AND OTHER FRAGMENTS. Edited by Miss UNA BIRCH. *Fcap. 8vo. 3s. 6d.*

Olliphant (Mrs.) THOMAS CHALMERS. With Portrait. *Crown 8vo. 3s. 6d.*

[Leaders of Religion.

Oman (G. W.), M.A., Fellow of All Souls', Oxford. A HISTORY OF THE ART

OF WAR. Vol. II.: The Middle Ages, from the Fourth to the Fourteenth Century. Illustrated. *Demy 8vo. 21s.*

Ottley (R. L.), D.D., Professor of Pastoral Theology at Oxford and Canon of Christ Church. THE DOCTRINE OF THE INCARNATION. *Second and Cheaper Edition. Demy 8vo. 12s. 6d.*

[Handbooks of Theology.

LANCELOT ANDREWES. With Portrait. *Crown 8vo. 3s. 6d.*

[Leaders of Religion.

Overton (J. H.), M.A. JOHN WESLEY. With Portrait. *Crown 8vo. 3s. 6d.*

[Leaders of Religion.

Owen (Douglas), Barrister-at-Law, Secretary to the Alliance Marine and General Assurance Company. PORTS AND DOCKS. *Crown 8vo. 2s. 6d. net.*

[Books on Business.

Oxford (M. H.), of Guy's Hospital. A HANDBOOK OF NURSING. *Second Edition. Crown 8vo. 3s. 6d.*

Paken (W. G. G.) THE SCIENCE OF HYGIENE. With numerous Illustrations. *Demy 8vo. 15s.*

Parkinson (John), PARADISI IN SOLE PARADISUS TERRISTRIS, OR A GARDEN OF ALL SORTS OF PLEASANT FLOWERS. *Folia. 6s, 2s. net.* Also an Edition of 80 copies on Japanese vellum. *Ten Guineas net.*

Parmentier (John) HELIO-TROPES, OR NEW POSIES FOR SUNDIALS, 1625. Edited by PERCYVAL LONDON. *Quarto. 3s. 6d. net.*

Parmentier (Prof. Léon) and Bidez (M.) EVAGRIUS. *Demy 8vo. 10s. 6d. net.*

[Byzantine Texts.

Pascal, THE THOUGHTS OF. With Introduction and Notes by C. S. JERRAM. *Small Pott 8vo. 2s.; leather, 2s. 6d. net.*

[Library of Devotion.

Paston (George). AUTHORS AND ARTISTS OF ENGLISH COLOURED BOOKS. Illustrated. *Fcap. 8vo. 2s. 6d. net.*

ROMNEY. With many Illustrations. *Demy 16mo. 2s. 6d. net.* [Little Books on Art.

Patterson (A. H.) NOTES OF AN EAST COAST NATURALIST. Illustrated in Colour by F. SOUTHGATE. *Cr. 8vo. 6s.*

Peacock (Miss). MILLET. With 30 Illustrations. *Demy 16mo. 2s. 6d. net.*

Pearce (E. H.), M.A. THE ANNALS OF CHRIST'S HOSPITAL. With many Illustrations. *Demy 8vo. 7s. 6d.*

Peary (R. E.), Gold Medalist of the Royal Geographical Society. NORTHWARD OVER THE GREAT ICE. With over 800 Illustrations. *2 vols. Royal 8vo. 32s. net.*

- Peel (Sidney)**, late Fellow of Trinity College, Oxford, and Secretary to the Royal Commission on the Licensing Laws. **PRACTICAL LICENSING REFORM.** *Second Edition.* Crown 8vo. 2s. 6d.
- Peters (J. F.), D.D.** THE OLD TESTAMENT AND THE NEW SCHOLARSHIP. Cr. 8vo. 6s. [Churchman's Library.]
- Petrie (W. M. Flinders), D.C.L., LL.D.,** Professor of Egyptology at University College. **A HISTORY OF EGYPT, FROM THE EARLIEST TIMES TO THE PRESENT DAY.** Fully Illustrated. *In six volumes.* Crown 8vo. 6s. each.
- VOL. I. PREHISTORIC TIMES TO XVTH DYNASTY.** *Fifth Edition.*
- VOL. II. THE XVIIITH AND XVIIIITH DYNASTIES.** *Fourth Edition.*
- VOL. IV. THE EGYPT OF THE PTOLEMIES.** J. P. MAHAFFY, Litt.D.
- VOL. V. ROMAN EGYPT.** J. G. MILNE, M.A.
- VOL. VI. EGYPT IN THE MIDDLE AGES.** STANLEY LANE-POOLE, M.A.
- RELIGION AND CONSCIENCE IN ANCIENT EGYPT.** Fully Illustrated. Crown 8vo. 2s. 6d.
- SYRIA AND EGYPT, FROM THE TELL EL AMARNA TABLETS.** Crown 8vo. 2s. 6d.
- EGYPTIAN TALES.** Illustrated by TRISTRAM ELLIS. *In Two Volumes.* Crown 8vo. 3s. 6d. each.
- EGYPTIAN DECORATIVE ART.** With 120 Illustrations. Crown 8vo. 3s. 6d.
- Phillips (W. A.)** CANNING. With 12 Illustrations. *Fcap. 8vo. Cloth, 3s. 6d.; leather, 4s. net.* [Little Biographies.]
- Philpotts (Eden).** MY DEVON YEAR. With 38 Illustrations by J. LEV PETHURIDGE. *Large Crown 8vo. 6s.*
- Pieteraar (Philip).** WITH STEYN AND DE WET. *Second Edition.* Crown 8vo. 3s. 6d.
- Plantas.** THE CAPTIVI. Edited, with an Introduction, Textual Notes, and a Commentary, by W. M. LINDSAY, Fellow of Jesus College, Oxford. Demy 8vo. 10s. 6d. net.
- Plowden-Wardlaw (J. T.), B.A.,** King's Coll. Cam. EXAMINATION PAPERS IN ENGLISH HISTORY. Crown 8vo. 2s. 6d. [School Examination Series.]
- Pocock (Roger).** A FRONTIERSMAN. *Third Edition.* Crown 8vo. 6s. A Colonial Edition is also published.
- Podmore (Frank).** MODERN SPIRITUALISM. *Two Volumes.* Demy 8vo. 21s. net. A History and a Criticism.
- Poor (J. Patrick La.)** A MODERN LEGIONARY. Crown 8vo. 6s. A Colonial Edition is also published.
- Pollard (Alice) and Hastings (Ethel).** COROT. With 30 Illustrations. Demy 16mo. [Little Books on Art.]
- Pollard (A. W.).** OLD PICTURE BOOKS. With many Illustrations. Demy 8vo. 7s. 6d. net.
- Pollard (Eliza F.).** GREUZE AND BOUCHER. Demy 16mo. 2s. 6d. net. [Little Books on Art.]
- Pollock (David), M.I.N.A.,** Author of *Modern Shipbuilding and the Men engaged in it*, etc., etc. THE SHIPBUILDING INDUSTRY. Crown 8vo. 2s. 6d. net. [Books on Business.]
- Potter (M. C.), M.A., F.L.S.** A TEXT-BOOK OF AGRICULTURAL BOTANY. Illustrated. *Second Edition.* Crown 8vo. 4s. 6d. [University Extension Series.]
- Potter Boy (An Old).** WHEN I WAS A CHILD. Crown 8vo. 6s.
- Pradeau (G.).** A KEY TO THE TIME ALLUSIONS IN THE DIVINE COMEDY. With a Dial. *Small quarto. 3s. 6d.*
- France (G.).** See R. WYON.
- Prescott (O. L.).** ABOUT MUSIC, AND WHAT IT IS MADE OF. Crown 8vo. 3s. 6d. net.
- Price (L. L.), M.A.,** Fellow of Oriel College, Oxon. A HISTORY OF ENGLISH POLITICAL ECONOMY. *Fourth Edition.* Crown 8vo. 2s. 6d. [University Extension Series.]
- Primrose (Deborah).** A MODERN BCEOTIA. Cr. 8vo. 6s. [Nearly Ready.]
- PROTECTION AND INDUSTRY.** By various Writers. Crown 8vo. 1s. 6d. net.
- Pugin and Rowlandson.** THE MICRO-COSM OF LONDON, OR LONDON IN MINIATURE. With 104 Illustrations in colour. *In Three Volumes. Small 4to.*
- "Q." THE GOLDEN POMP.** A Procession of English Lyrics. Arranged by A. T. QUILLER COUCH. Crown 8vo. Buckram. 6s.
- QUEVEDO VILLEGAS,** THE VISIONS OF DOM FRANCISCO DE, Knight of the Order of St. James. Made English by R. L. From the edition printed for H. Herringmas, 1668. *Leather, 2s. net.* [Miniature Library.]
- G. R. and E. S.** THE WOODHOUSE CORRESPONDENCE. Crown 8vo. 6s.
- Rackham (R. B.), M.A.** THE ACTS OF THE APOSTLES. With an Introduction and Notes. Demy 8vo. *New and Cheaper Ed. 10s. 6d.* [Westminster Commentaries.]
- Randolph (B. W.), D.D.,** Principal of the Theological College, Ely. THE PSALMS OF DAVID. With an Introduction and Notes. *Small Part 8vo. Cloth, 2s.; leather, 2s. 6d. net.* [Library of Devotion.]
- Rannie (D. W.), M.A.** A STUDENT'S HISTORY OF SCOTLAND. Cr. 8vo. 3s. 6d.

- Rashdall (Hastings), M.A.**, Fellow and Tutor of New College, Oxford. **DOCTRINE AND DEVELOPMENT.** *Crown 8vo. 6s.*
- Rawstorne (Lawrence, Esq.).** **GAMONIA:** or, The Art of Preserving Game; and an Improved Method of making plantations and covers, explained and illustrated by. With 15 Coloured Drawings by T. RAWLINS. *Fcap. 8vo. 3s. 6d. net.* [Illustrated Pocket Library.]
- A Real Paddy.** **REAL LIFE IN IRELAND,** or The Day and Night Scenes of Brian Boru, Esq., and his Elegant Friend, Sir Shawn O'Dogherty. With 19 Coloured Plates by HEATH, MARKS, etc. *Fcap. 8vo. 3s. 6d. net.* [Illustrated Pocket Library.]
- Reason (W.), M.A.** **UNIVERSITY AND SOCIAL SETTLEMENTS.** *Crown 8vo. 2s. 6d.* [Social Questions Series.]
- Redfern (W. B.),** Author of 'Ancient Wood and Iron Work in Cambridge,' etc. **ROYAL AND HISTORIC GLOVES AND ANCIENT SHOES.** Profusely Illustrated in colour and half-tone. *Quarto, £2, 2s. net.*
- Reynolds, A LITTLE GALLERY OF.** Twenty examples in photogravure of his finest work. *Demy 16mo. 2s. 6d. net.* [Little Galleries.]
- Roberts (M. E.).** See C. C. Channer.
- Robertson (A.), D.D.,** Lord Bishop of Exeter. **REGNUM DEL.** The Bampton Lectures of 1901. *Demy 8vo. 12s. 6d. net.*
- Robertson (G. Grant), M.A.,** Fellow of All Souls' College, Oxford, Examiner in the Honour School of Modern History, Oxford, 1901-1904. **SELECT STATUTES, CASES, AND CONSTITUTIONAL DOCUMENTS, 1660-1832.** *Demy 8vo. 10s. 6d. net.*
- Robertson (Sir G. S.) K.C.S.I.** **CHITRAL:** The Story of a Minor Siege. With numerous Illustrations, Map and Plans. *Fourth Edition. Crown 8vo. 6s.*
- Robinson (A. W.), M.A.** **THE EPISTLE TO THE GALATIANS.** With an Introduction and Notes. *Fcap. 8vo. 1s. 6d. net.* [Churchman's Bible.]
- Robinson (Cecilia).** **THE MINISTRY OF DEACONESSES.** With an Introduction by the late Archbishop of Canterbury. *Crown 8vo. 3s. 6d.*
- Rochebonand (La).** **THE MAXIMS OF.** Translated by DEAN STANHOPE. Edited by G. H. POWELL. *Small/Pott 8vo, cloth, 1s. 6d. net; leather, 2s. 6d. net.* [Little Library.]
- Rodwell (G.), B.A.** **NEW TESTAMENT GREEK.** A Course for Beginners. With a Preface by WALTER LOCK, D.D., Warden of Keble College. *Fcap. 8vo. 2s. 6d.*
- Roos (Fred).** **ANCIENT COFFERS AND CUPBOARDS:** Their History and Description. With many Illustrations. *Quarto, £3, 3s. net.*
- Rogers (A. G. L.), M.A.,** Editor of the last volume of *The History of Agriculture and Prices in England.* **THE AGRICULTURAL INDUSTRY.** *Crown 8vo. 2s. 6d. net.* [Books on Business.]
- Romney.** **A LITTLE GALLERY OF.** Twenty examples in Photogravure of his finest work. *Demy 16mo. 2s. 6d. net.* [Little Galleries.]
- Roscoe (E.S.), ROBERT HARLEY, EARL OF OXFORD.** Illustrated. *Demy 8vo. 7s. 6d.*
This is the only life of Harley in existence.
- BUCKINGHAMSHIRE.** Illustrated by F. D. BEDFORD. *Small/Pott 8vo, cloth 3s.; leather, 3s. 6d.* [Little Guides.]
- Rose (Edward).** **THE ROSE READER.** With numerous Illustrations. *Crown 8vo. 2s. 6d. Also in 4 Parts. Parts I. and II. 6d. each; Part I. 1. 8d.; Part IV. 10d.*
- Ruble (A. E.), M.A.,** Head Master of College, Eltham. **THE GOSPEL ACCORDING TO ST. MARK.** With three Maps. *Crown 8vo. 1s. 6d.* [Junior School Books.]
- THE ACTS OF THE APOSTLES.** *Crown 8vo. 2s.* [Junior School Books.]
- THE FIRST BOOK OF KINGS.** With Notes. *Crown 8vo. 1s. 6d.* [Junior School Books.]
- Russell (W. Clark).** **THE LIFE OF ADMIRAL LORD COLLINGWOOD.** With Illustrations by F. BRANGWYN. *Fourth Edition. Crown 8vo. 6s.*
A Colonial Edition is also published.
- St. Anselm, THE DEVOTIONS OF.** Edited by C. C. J. WEBB, M.A. *Small/Pott 8vo. Cloth, 2s.; leather, 2s. 6d. net.* [Library of Devotion.]
- St. Augustine, THE CONFESSIONS OF.** Newly Translated, with an Introduction and Notes, by C. BIGG, D.D., late Student of Christ Church. *Third Edition. Small/Pott 8vo. Cloth, 2s.; leather, 2s. 6d. net.* [Library of Devotion.]
- 'Saki' (Munro H.) REGINALD.** *Fcap. 2s. 6d. net.*
- Sales (St. Francis de).** **ON THE LOVE OF GOD.** Edited by W. J. KNOX-LITTLE, M.A. *Small/Pott 8vo. Cloth, 2s.; leather, 2s. 6d. net.* [Library of Devotion.]
- Salmon (A. L.).** **CORNWALL.** Illustrated by B. C. BOULTER. *Small/Pott 8vo. Cloth, 3s.; leather, 3s. 6d. net.* [Little Guides.]
- A POPULAR GUIDE TO DEVON.** *Medium 8vo. 6d. net.*
- Sargeant (J.), M.A.** **ANNALS OF WESTMINSTER SCHOOL.** With numerous Illustrations. *Demy 8vo. 7s. 6d.*
- Sathas (G.).** **THE HISTORY OF PSELLUS.** *Demy 8vo. 12s. net.* [Byzantine Texts.]

- Schmitt (John).** THE CHRONICLE OF MOREA. *Demy 8vo.* 15s. *net.*
[Byzantine Texts.]
- Seeley (E. G.) F. R. S.** DRAGONS OF THE AIR. With many Illustrations. *Crown 8vo.* 6s.
- Sells (V. P.), M. A.** THE MECHANICS OF DAILY LIFE. Illustrated. *Crown 8vo.* 2s. 6d. (University Extension Series.)
- Selous (Edmund).** TOMMY SMITH'S ANIMALS. Illustrated by G. W. ORD. *Second Edition. Fcap. 8vo.* 2s. 6d.
- Settle (J. H.).** ANECDOTES OF BRITISH SOLDIERS. *Crown 8vo.* 3s. 6d. *net.*
A Colonial Edition is also published.
- Shakespeare (William).** THE FOUR FOLIOS, 1623; 1632; 1664; 1685. Each *Four Guineas net*, or a complete set, *Twelve Guineas net.*
- The Arden Shakespeare.** *Demy 8vo.* 3s. 6d. each volume. General Editor, W. J. CRAIG. An Edition of Shakespeare in single Plays. Edited with a full Introduction, Textual Notes, and a Commentary at the foot of the page.
- HAMLET.** Edited by EDWARD DOWDEN, Litt.D.
- ROMEO AND JULIET.** Edited by EDWARD DOWDEN, Litt.D.
- KING LEAR.** Edited by W. J. CRAIG.
- JULIUS CÆSAR.** Edited by M. MACMILLAN, M.A.
- THE TEMPEST.** Edited by MORTON LUCE.
- OTHELLO.** Edited by H. C. HART.
- CYMBELINE.** Edited by EDWARD DOWDEN.
- TITUS ANDRONICUS.** Edited by H. B. BAILDON.
- THE MERRY WIVES OF WINDSOR.** Edited by H. C. HART.
- MIDSUMMER NIGHT'S DREAM.** Edited by H. CUNINGHAM.
- KING HENRY V.** Edited by H. A. EVANS.
- TITUS ANDRONICUS.** Edited by H. B. BAILDON.
- ALL'S WELL THAT ENDS WELL.** Edited by W. O. BRIGSTOCKE.
- THE TAMING OF THE SHREW.** Edited by R. M. BOND.
- The Little Quarto Shakespeare. Post 16mo. Leather, price 1s. net each volume.**
- TWO GENTLEMEN OF VERONA.**
- A COMEDY OF ERRORS.**
- THE TEMPEST.**
- THE MERRY WIVES OF WINDSOR.**
- MEASURE FOR MEASURE.**
- LOVE'S LABOUR'S LOST.**
- A MIDSUMMER NIGHT'S DREAM.**
- MUCH ADO ABOUT NOTHING.**
- AS YOU LIKE IT.**
- THE MERCHANT OF VENICE.**
- ALL'S WELL THAT ENDS WELL.**
- A WINTER'S TALE.**
- THE TAMING OF THE SHREW.**
- TWELFTH NIGHT.**
- KING JOHN.**
- KING RICHARD II.**
- KING HENRY IV. Part I.**
- KING HENRY IV. Part II.**
- KING HENRY V.**
- KING HENRY VI. Part I.**
- KING HENRY VI. Part II.**
- KING HENRY VI. Part III.**
- KING RICHARD III.**
- KING HENRY VIII.**
- TROILUS AND CRESSIDA.**
- CORIOLANUS.**
- TITUS ANDRONICUS.**
- ROMEO AND JULIET.**
- TIMON OF ATHENS.**
- JULIUS CÆSAR.**
- Sharp (A.).** VICTORIAN POETS. *Crown 8vo.* 2s. 6d. [University Extension Series.]
- Sharp (Mrs. E. A.).** REMBRANDT. With 30 Illustrations. *Demy 8vo.* 2s. 6d. *net.* [Little Books on Art.]
- Shedlock (J. S.).** THE PIANOFORTE SONATA: Its Origin and Development. *Crown 8vo.* 5s.
- Shelley (Percy B.).** ADONAI; an Elegy on the death of John Keats, Author of Endymion, etc. Pisa. From the types of Didot, 1821. 2s. *net.*
- Sherwell (Arthur), M. A.** LIFE IN WEST LONDON. *Third Edition. Crown 8vo.* 2s. 6d. [Social Questions Series.]
- Sichel (Walter).** DISRAELI: A Study in Personality and Ideas. With 3 Portraits. *Demy 8vo.* 12s. 6d. *net.*
A Colonial Edition is also published.
- BEACONSFIELD.** With 12 Illustrations. *Fcap. 8vo, cloth, 3s. 6d.; leather, 4s. net.* [Little Biographies.]
- Sime (J.).** REYNOLDS. With many Illustrations. *Demy 16mo.* 2s. 6d. *net.* [Little Books on Art.]
- Simonson (G. A.).** FRANCESCO GUARDI. With 32 Plates. *Royal folio. £s. 2s. net.*
- Sketchley (E. E. D.).** WATTS. With many Illustrations. *Demy 16mo.* 2s. 6d. *net.* [Little Books on Art.]
- Skipton (H. P. E.).** HOPPNER. With numerous Illustrations. *Demy 16mo.* 2s. 6d. *net.* [Little Books on Art.]
- Sladen (Douglas).** SICILY. With over 200 Illustrations. *Crown 8vo.* 5s. *net.*
- Small (Evan), M. A.** THE EARTH. An Introduction to Physiography. Illustrated. *Crown 8vo.* 2s. 6d. [University Extension Series.]
- Smallwood, (M. G.).** VANDYCK. With many Illustrations. *Demy 16mo.* 2s. 6d. *net.* [Little Books on Art.]

- Smedley (F. E.). FRANK FAIRLEGH.** With 28 Plates by GEORGE CRUIKSHANK. *Fcap. 8vo. 3s. 6d. net.*
[Illustrated Pocket Library.]
- Smith (Adam). THE WEALTH OF NATIONS.** Edited with an Introduction and numerous Notes by EDWIN CANNAN, M.A. *Two volumes. Demy 8vo. 21s. net.*
- Smith (Horace and James). REJECTED ADDRESSES.** Edited by A. D. GODLEY, M.A. *Small Pott 8vo, cloth. 1s. 6d. net.; leather, 2s. 6d. net.* [Little Library.]
- Snell (F. J.). A BOOK OF EXMOOR.** Illustrated. *Crown 8vo. 6s.*
- Sophocles. ELECTRA AND AJAX.** Translated by E. D. A. MORSEHEAD, M.A., Assistant Master at Winchester. *2s. 6d.* [Classical Translations.]
- Sornet (L. A.) and Acostas (M. J.).** Modern Language Masters at King Edward's School, Birmingham. **A JUNIOR FRENCH GRAMMAR.** *Crown 8vo. 2s.*
[Junior School Books.]
- South (Wilton E.), M.A. THE GOSPEL ACCORDING TO ST. MATTHEW.** *Crown 8vo. 1s. 6d.* [Junior School Books.]
- Southey (R.) ENGLISH SEAMEN.** Vol. I. (Howard, Clifford, Hawkins, Drake, Cavendish). Edited, with an Introduction, by DAVID HANNAY. *Second Edition. Crown 8vo. 6s.*
Vol. II. (Richard Hawkins, Grenville, Essex, and Raleigh). *Crown 8vo. 6s.*
- Spence (C. H.), M.A., Clifton College. HISTORY AND GEOGRAPHY EXAMINATION PAPERS.** *Second Edition. Crown 8vo. 2s. 6d.*
[School Examination Series.]
- Sponner (W. A.), M.A., Warden of New College, Oxford. BISHOP BUTLER.** With Portrait. *Crown 8vo. 3s. 6d.*
[Leaders of Religion.]
- Stanbridge (J. W.), B.D., late Canon of York, and sometime Fellow of St. John's College, Oxford. A BOOK OF DEVOTIONS.** *Second Edition. Small Pott 8vo. Cloth, 2s.; leather, 2s. 6d. net.* [Library of Devotion.]
- 'Stancliffe.' GOLF DO'S AND DONT'S.** *Second Edition. Fcap. 8vo. 1s.*
- Stedman (A. M. M.), M.A. INITIA LATINA: Easy Lessons on Elementary Accidence.** *Sixth Edition. Fcap. 8vo. 1s.*
- FIRST LATIN LESSONS.** *Eighth Edition. Crown 8vo. 2s.*
- FIRST LATIN READER.** With Notes adapted to the Shorter Latin Primer and Vocabulary. *Sixth Edition revised. 18mo. 1s. 6d.*
- EASY SELECTIONS FROM CÆSAR.** The Helvetian War. *Second Edition. 18mo. 1s.*
- EASY SELECTIONS FROM LIVY.** Part I. The Kings of Rome. *18mo. Second Edition. 1s. 6d.*
- EASY LATIN PASSAGES FOR UNSEEN TRANSLATION.** *Ninth Edition. Fcap. 8vo. 1s. 6d.*
- EXEMPLA LATINA.** First Exercises in Latin Accidence. With Vocabulary. *Third Edition. Crown 8vo. 1s.*
- EASY LATIN EXERCISES ON THE SYNTAX OF THE SHORTER AND REVISED LATIN PRIMER.** With Vocabulary. *Ninth and Cheaper Edition, re-written. Crown 8vo. 1s. 6d. Key, 3s. net. Original Edition. 2s. 6d.*
- THE LATIN COMPOUND SENTENCE: Rules and Exercises.** *Second Edition. Crown 8vo. 1s. 6d.* With Vocabulary. *2s.*
- NOTANDA QUÆDAM: Miscellaneous Latin Exercises on Common Rules and Idioms.** *Fourth Edition. Fcap. 8vo. 1s. 6d.* With Vocabulary. *2s. Key, 2s. net.*
- LATIN VOCABULARIES FOR REPETITION: Arranged according to Subjects.** *Eleventh Edition. Fcap. 8vo. 1s. 6d.*
- A VOCABULARY OF LATIN IDIOMS.** *18mo. Second Edition. 1s.*
- STEPS TO GREEK.** *Second Edition, revised. 18mo. 1s.*
- A SHORTER GREEK PRIMER.** *Crown 8vo. 1s. 6d.*
- EASY GREEK PASSAGES FOR UNSEEN TRANSLATION.** *Third Edition, revised. Fcap. 8vo. 1s. 6d.*
- GREEK VOCABULARIES FOR REPETITION.** Arranged according to Subjects. *Third Edition. Fcap. 8vo. 1s. 6d.*
- GREEK TESTAMENT SELECTIONS.** For the use of Schools. With Introduction, Notes, and Vocabulary. *Third Edition. Fcap. 8vo. 2s. 6d.*
- STEPS TO FRENCH.** *Sixth Edition. 18mo. 8d.*
- FIRST FRENCH LESSONS.** *Sixth Edition, revised. Crown 8vo. 1s.*
- EASY FRENCH PASSAGES FOR UNSEEN TRANSLATION.** *Fifth Edition, revised. Fcap. 8vo. 1s. 6d.*
- EASY FRENCH EXERCISES ON ELEMENTARY SYNTAX.** With Vocabulary. *Fourth Edition. Crown 8vo. 2s. 6d. Key, 3s. net.*
- FRENCH VOCABULARIES FOR REPETITION: Arranged according to Subjects.** *Twelfth Edition. Fcap. 8vo. 1s.*
- FRENCH EXAMINATION PAPERS IN MISCELLANEOUS GRAMMAR AND IDIOMS.** *Twelfth Edition. Crown 8vo. 2s. 6d.* [School Examination Series.]
A Key, issued to Tutors and Private Students only, to be had on application to the Publishers. *Fifth Edition. Crown 8vo. 6s. net.*

- GENERAL KNOWLEDGE EXAMINATION PAPERS.** *Fifth Edition.* Crown 8vo. 2s. 6d. [School Examination Series. Key (*Third Edition*) issued as above. 7s. net.]
- GREEK EXAMINATION PAPERS IN MISCELLANEOUS GRAMMAR AND IDIOMS.** *Seventh Edition.* Crown 8vo. 2s. 6d. [School Examination Series. Key (*Third Edition*) issued as above. 6s. net.]
- LATIN EXAMINATION PAPERS IN MISCELLANEOUS GRAMMAR AND IDIOMS.** *Twelfth Edition.* Crown 8vo. 2s. 6d. [School Examination Series. Key (*Fifth Edition*) issued as above. 6s. net.]
- Steel (E. Killott), M.A., F.C.S.** THE WORLD OF SCIENCE. Including Chemistry, Heat, Light, Sound, Magnetism, Electricity, Botany, Zoology, Physiology, Astronomy, and Geology. 147 Illustrations. *Second Edition.* Crown 8vo. 2s. 6d.
- PHYSICS EXAMINATION PAPERS.** Crown 8vo. 2s. 6d. [School Examination Series.]
- Stephenson (C.),** of the Technical College, Bradford, and **Suddards (F.),** of the Yorkshire College, Leeds. ORNAMENTAL DESIGN FOR WOVEN FABRICS. Illustrated. *Demy 8vo. Second Edition.* 7s. 6d.
- Stephenson (J.), M.A.** THE CHIEF TRUTHS OF THE CHRISTIAN FAITH. Crown 8vo. 3s. 6d.
- Sterne (Laurence).** A SENTIMENTAL JOURNEY. Edited by H. W. PAUL. *Small Pott 8vo. Cloth, 1s. 6d. net; leather, 2s. 6d. net.* [Little Library.]
- Sterry (W.), M.A.** ANNALS OF ETON COLLEGE. With numerous Illustrations. *Demy 8vo. 7s. 6d.*
- Stewart (Katherine).** BY ALLAN WATER. *Second Edition.* Crown 8vo. 6s.
- Stevenson (R. L.)** THE LETTERS OF ROBERT LOUIS STEVENSON TO HIS FAMILY AND FRIENDS. Selected and Edited, with Notes and Introductions, by SIDNEY COLVIN. *Sixth and Cheaper Edition.* Crown 8vo. 12s.
- LIBRARY EDITION.** *Demy 8vo. 2 vols. 25s. net.* A Colonial Edition is also published.
- VAILIMA LETTERS.** With an Etched Portrait by WILLIAM STRANG. *Third Edition.* Crown 8vo. Buckram. 6s.
- A Colonial Edition is also published.
- THE LIFE OF R. L. STEVENSON.** See G. Balfour.
- Stevenson (M. I.)** FROM SARANAC TO THE MARQUESAS. Being Letters written by Mrs. M. I. STEVENSON during 1887-8 to her sister, Miss JANE WHITE BALFOUR. With an Introduction by
- GEORGE W. BALFOUR, M.D., LL.D., F.R.S.S. *Crown 8vo. 6s. net.* A Colonial Edition is also published.
- Stoddart (Anna M.)** ST. FRANCIS OF ASSISI. With 16 Illustrations. *Fcap. 8vo. Cloth, 3s. 6d.; leather, 4s. net.* [Little Biographies.]
- Stone (E. D.), M.A.,** late Assistant Master at Eton. SELECTIONS FROM THE ODYSSEY. *Fcap. 8vo. 1s. 6d.*
- Stone (S. J.).** POEMS AND HYMNS. With a Memoir by F. G. ELLERTON, M.A. With Portrait. *Crown 8vo. 6s.*
- Straker (F.),** Assoc. of the Institute of Bankers, and Lecturer to the London Chamber of Commerce. THE MONEY MARKET. *Crown 8vo. 2s. 6d. net.* [Books on Business.]
- Streane (A. W.), D.D.** ECCLESIASTES. With an Introduction and Notes. *Fcap. 8vo. 1s. 6d. net.* [Churchman's Bible.]
- Stroud (H.), D.Sc., M.A.,** Professor of Physics in the Durham College of Science, Newcastle-on-Tyne. PRACTICAL PHYSICS. Fully Illustrated. *Crown 8vo. 1s. 6d.* [Textbooks of Technology.]
- Strutt (Joseph).** THE SPORTS AND PASTIMES OF THE PEOPLE OF ENGLAND. Illustrated by many engravings. Revised by J. Charles Cox, LL.D., F.S.A. *Quarto. 21s. net.*
- Stuart (Capt. Donald).** THE STRUGGLE FOR PERSIA. With a Map. *Crown 8vo. 6s.*
- Suckling (Sir John).** FRAGMENTA AUREA: a Collection of all the Incomparable Peeces, written by. And published by a friend to perpetuate his memory. Printed by his own copies. Printed for HUMPHREY MOSLEY, and are to be sold at his shop, at the sign of the Princes Arms in St. Paul's Churchyard, 1646.
- Suddards (F.).** See C. Stephenson.
- Surtees (R. S.).** HANDLEY CROSS. With 17 Coloured Plates and 100 Woodcuts in the Text by JOHN LEBCH. *Fcap. 8vo. 4s. 6d. net.* Also a limited edition on large Japanese paper. 30s. net. [Illustrated Pocket Library.]
- MR. SPONGE'S SPORTING TOUR.** With 13 Coloured Plates and 90 Woodcuts in the Text by JOHN LEBCH. *Fcap. 8vo. 3s. 6d. net.* Also a limited edition on large Japanese paper. 30s. net. [Illustrated Pocket Library.]
- JORROCKS' JAUNTS AND JOLLITIES.** With 15 Coloured Plates by H. ALKEN. *Fcap. 8vo. 3s. 6d. net.* Also a limited edition on large Japanese paper. 30s. net. [Illustrated Pocket Library.]

- ASK MAMMA. With 13 Coloured Plates and 70 Woodcuts in the Text by JOHN LEECH. *Fcap. 8vo.* 3s. 6d. net.
- Also a limited edition on large Japanese paper. 30s. net.
- [Illustrated Pocket Library. Nearly Ready.]
- Swift (Jonathan). THE JOURNAL TO STELLA. Edited by G. A. AIRKEN. *Crown 8vo.* 6s.
- Symes (J. E.), M.A. THE FRENCH REVOLUTION. *Second Edition. Crown 8vo.* 2s. 6d. [University Extension Series.]
- Syrett (Netta). A SCHOOL YEAR. Illustrated. *Demy 16mo.* 2s. 6d. [Little Blue Books.]
- Tacitus. AGRICOLA. With Introduction, Notes, Map, etc. By R. F. DAVIS, M.A., late Assistant Master at Weymouth College. *Crown 8vo.* 2s.
- GERMANIA. By the same Editor. *Crown 8vo.* 2s.
- AGRICOLA AND GERMANIA. Translated by R. B. TOWNSEND, late Scholar of Trinity College, Cambridge. *Crown 8vo.* 2s. 6d. [Classical Translations.]
- Tauler (J.). THE INNER WAY. Being Thirty-six Sermons for Festivals by JOHN TAULER. Edited by A. W. HUTTON, M.A. *Small Pott 8vo.* Cloth, 2s.; leather, 2s. 6d. net. [Library of Devotion.]
- Taunton (E. L.). A HISTORY OF THE JESUITS IN ENGLAND. With Illustrations. *Demy 8vo.* 21s. net.
- Taylor (A. E.). THE ELEMENTS OF METAPHYSICS. *Demy 8vo.* 10s. 6d. net.
- Taylor (F. G.), M.A. COMMERCIAL ARITHMETIC. *Third Edition. Crown 8vo.* 1s. 6d. [Commercial Series.]
- Taylor (Miss J. A.). SIR WALTER RALEIGH. With 12 Illustrations. *Fcap. 8vo.* Cloth, 3s. 6d.; leather, 4s. net. [Little Biographies.]
- Taylor (T. M.), M.A., Fellow of Gonville and Caius College, Cambridge. A CONSTITUTIONAL AND POLITICAL HISTORY OF ROME. *Crown 8vo.* 7s. 6d.
- Tennyson (Alfred, Lord). THE EARLY POEMS OF. Edited with Notes and an Introduction, by J. CHURTON COLLINS, M.A. *Crown 8vo.* 6s.
- IN MEMORIAM, MAUD, AND THE PRINCESS. Edited by J. CHURTON COLLINS, M.A. *Crown 8vo.* 6s.
- MAUD. Edited by ELIZABETH WORDSWORTH. *Small Pott 8vo.* Cloth, 1s. 6d. net; leather, 2s. 6d. net. [Little Library.]
- IN MEMORIAM. Edited by H. C. BEECHING, M.A. *Small Pott 8vo.* Cloth, 1s. 6d. net; leather, 2s. 6d. net. [Little Library.]
- THE EARLY POEMS OF. Edited by J. C. COLLINS, M.A. *Small Pott 8vo.* Cloth, 1s. 6d. net; leather, 2s. 6d. net. [Little Library.]
- THE PRINCESS. Edited by ELIZABETH WORDSWORTH. *Small Pott 8vo.* Cloth, 1s. 6d. net; leather, 2s. 6d. net. [Little Library.]
- Terry (G. S.). THE YOUNG PRETENDER. With 12 Illustrations. *Fcap. 8vo.* Cloth, 3s. 6d.; leather, 4s. net. [Little Biographies.]
- Terton (Alice). LIGHTS AND SHADOWS IN A HOSPITAL. *Crown 8vo.* 3s. 6d.
- Thackeray (W. M.). VANITY FAIR. Edited by STEPHEN GWYNN. *Three Volumes. Small Pott 8vo.* Each volume, cloth, 1s. 6d. net; leather, 2s. 6d. net. [Little Library.]
- PENDENNIS. Edited by STEPHEN GWYNN. *Three Volumes. Small Pott 8vo.* Each volume, cloth, 1s. 6d. net; leather, 2s. 6d. net. [Little Library.]
- ESMOND. Edited by STEPHEN GWYNN. *Small Pott 8vo.* Cloth, 1s. 6d. net; leather, 2s. 6d. net. [Little Library.]
- CHRISTMAS BOOKS. Edited by STEPHEN GWYNN. *Small Pott 8vo.* Cloth, 1s. 6d. net; leather, 2s. 6d. net. [Little Library.]
- Theobald (F. W.), M.A. INSECT LIFE. Illustrated. *Crown 8vo.* 2s. 6d. [University Extension Series.]
- Thompson (A. E.). CAMBRIDGE AND ITS COLLEGES. Illustrated by E. H. NEW. *Small Pott 8vo.* Cloth, 3s.; leather, 3s. 6d. net. [Little Guides.]
- Tilston (Mary W.). DAILY STRENGTH FOR DAILY NEEDS. *Fcap. 8vo.* 3s. 6d. Also editions in superior binding 5s. and 6s.
- Tompkins (H. W.), F.R.H.S. HERTFORDSHIRE. Illustrated by E. H. NEW. *Small Pott 8vo.* Cloth, 3s.; leather, 3s. 6d. net. [Little Guides.]
- Townley (Lady Susan). MY CHINESE NOTE-BOOK. With 16 Illustrations. *Demy 8vo.* 10s. 6d. net. A Colonial Edition is also published.
- Toynbee (Paget), M.A. D.Litt. DANTE STUDIES AND RESEARCHES. *Demy 8vo.* 10s. 6d. net.
- DANTE ALIGHIERI. With 12 Illustrations. *Second Edition. Fcap. 8vo.* Cloth, 3s. 6d.; leather, 4s. net. [Little Biographies.]
- Trench (Herbert). DEIRDRE WED: and Other Poems. *Crown 8vo.* 5s.
- Trevelyan (G. M.), Fellow of Trinity College, Cambridge. ENGLAND UNDER THE STUARTS. *Demy 8vo.* 10s. 6d. net.
- Troutbeck (G. E.). WESTMINSTER ABBEY. Illustrated by F. D. BEDFORD. *Small Pott 8vo.* Cloth, 3s.; leather, 3s. 6d. net. [Little Guides.]
- Tuckwell (Gertrude). THE STATE AND ITS CHILDREN. *Crown 8vo.* 2s. 6d. [Social Questions Series.]
- Twining (Louisa). WORKHOUSES AND PAUPERISM. *Crown 8vo.* 2s. 6d. [Social Questions Series.]

- Taylor (E. A.), B.A., F.C.S.** A JUNIOR CHEMISTRY. *Crown 8vo.* 2s. 6d. [Junior School Books.
- Tyrell-Gill (Frances),** TURNER. *Demy 16mo.* 2s. 6d. net. [Little Books on Art.
- Vaughan (Henry),** THE POEMS OF. Edited by EDWARD HUTTON. *Small Pott 8vo.* Cloth, 1s. 6d. net; leather, 2s. 6d. net. [Little Library.
- Voegelin (A.), M.A.** JUNIOR GERMAN EXAMINATION PAPERS. *Fcap. 8vo.* 1s. [Junior Examination Series.
- Wade (G. W.), D.D.** OLD TESTAMENT HISTORY. With Maps. *Second Edition.* *Crown 8vo.* 6s. This book presents a connected account of the Hebrew people during the period covered by the Old Testament; and has been drawn up from the Scripture records in accordance with the methods of historical criticism.
- Wagner (Richard).** See A. L. CLEATHER.
- Wall (J. C.)** DEVILS. Illustrated by the Author. *Demy 8vo.* 4s. 6d. net.
- Walters (H. B.)** GREEK ART. With many Illustrations. *Demy 16mo.* 2s. 6d. net. [Little Books on Art.
- Walton (Isaac) and Cotton (Charles).** THE COMPLETE ANGLER. With 14 Plates and 77 Woodcuts in the Text. *Fcap. 8vo.* 3s. 6d. net. [Illustrated Pocket Library. This volume is reproduced from the beautiful edition of John Major of 1824-5.
- THE COMPLETE ANGLER.** Edited by J. BUCHAN. *Small Pott 8vo.* Cloth, 1s. 6d. net; leather, 2s. 6d. net. [Little Library.
- Warmelo (D. S. Van),** ON COMMANDO. With Portrait. *Crown 8vo.* 3s. 6d.
- Waterhouse (Mrs. Alfred).** A LITTLE BOOK OF LIFE AND DEATH. Selected. *Fourth Edition.* *Small Pott 8vo.* Cloth, 1s. 6d. net; leather, 2s. 6d. net. [Little Library.
- WITH THE SIMPLE HEARTED:** Little Homilies to Women in Country Places. *Fcap. 8vo.* 2s. net.
- Weatherhead (T. G.), M.A.** EXAMINATION PAPERS IN HORACE. *Crown 8vo.* 2s. [Junior Examination Series.
- JUNIOR GREEK EXAMINATION PAPERS.** *Fcap. 8vo.* 1s. [Junior Examination Series.
- Webb (W. T.)** A BOOK OF BAD CHILDREN. With 50 Illustrations by H. C. SANDY. *Demy 16mo.* 2s. 6d. [Little Blue Books.
- Webber (F. G.)** CARPENTRY AND JOINERY. With many Illustrations. *Third Edition.* *Crown 8vo.* 3s. 6d.
- Wells (Sidney H.)** PRACTICAL MECHANICS. With 75 Illustrations and Diagrams. *Second Edition.* *Crown 8vo.* 3s. 6d. [Textbooks of Technology.
- Wells (J.), M.A.,** Fellow and Tutor of Wadham College. OXFORD AND OXFORD LIFE. By Members of the University. *Third Edition.* *Crown 8vo.* 2s. 6d.
- A SHORT HISTORY OF ROME.** *Fifth Edition.* With 3 Maps. *Cr. 8vo.* 3s. 6d. This book is intended for the Middle and Upper Forms of Public Schools and for Pass Students at the Universities. It contains copious Tables, etc.
- OXFORD AND ITS COLLEGES.** Illustrated by E. H. New. *Fifth Edition.* *Pott 8vo.* Cloth, 3s.; leather, 3s. 6d. net. [Little Guides.
- Wetmore (Helen C.)** THE LAST OF THE GREAT SCOUTS ('Buffalo Bill'). With Illustrations. *Second Edition.* *Demy 8vo.* 6s.
- Whibley (O.).** See Henley and Whibley.
- Whibley (L.), M.A.,** Fellow of Pembroke College, Cambridge. GREEK OLIGARCHIES; THEIR ORGANISATION AND CHARACTER. *Crown 8vo.* 6s.
- Whitaker (G. H.), M.A.** THE EPISTLE OF ST. PAUL THE APOSTLE TO THE EPHESIANS. With an Introduction and Notes. *Fcap. 8vo.* 1s. 6d. net. [Churchman's Bible.
- White (Gilbert).** THE NATURAL HISTORY OF SELBORNE. Edited by L. C. MIALL, F.R.S., assisted by W. WARDE FOWLER, M.A. *Crown 8vo.* 6s.
- Whitfield (E. E.)** PRECIS WRITING AND OFFICE CORRESPONDENCE. *Second Edition.* *Crown 8vo.* 2s. [Commercial Series.
- COMMERCIAL EDUCATION IN THEORY AND PRACTICE.** *Crown 8vo.* 5s. [Commercial Series. An introduction to Methuen's Commercial Series treating the question of Commercial Education fully from both the point of view of the teacher and the parent.
- Whitehead (A. W.)** COLIGNY. With many Illustrations. *Demy 8vo.* 12s. 6d. net.
- Whitley (Miss).** See Lady Dilke.
- Whyte (A. G.), B.Sc.** Editor of *Electrical Investments.* THE ELECTRICAL INDUSTRY. *Crown 8vo.* 2s. 6d. net. [Books on Business.
- Wilberforce (Wilfrid) and Gilbert (A. E.)** VELASQUEZ. With many Illustrations. *Demy 16mo.* 2s. 6d. net. [Little Books on Art.
- Wilkins (W. H.), B.A.** THE ALIEN INVASION. *Crown 8vo.* 2s. 6d. [Social Questions Series.
- Williamson (W.)** THE BRITISH GARDENER. Illustrated. *Demy 8vo.* 10s. 6d.
- Williamson (W.) B.A.** JUNIOR ENGLISH EXAMINATION PAPERS. *Fcap. 8vo.* 1s. [Junior Examination Series.

- A JUNIOR ENGLISH GRAMMAR.** With numerous passages for parsing and analysis, and a chapter on Essay Writing. *Crown 8vo. 2s.* [Junior School Books.]
- A CLASS-BOOK OF DICTATION PASSAGES.** *Eighth Edition. Crown 8vo. 1s. 6d.* [Junior School Books.]
- EASY DICTATION AND SPELLING.** *Third Edition. Fcap. 8vo. 1s.*
- Wilmot-Burton (E. M.). THE MAKERS OF EUROPE.** *Crown 8vo. Second Edition. 3s. 6d.*
A Text-book of European History for Middle Forms.
- THE STORY OF THE ANCIENT WORLD.** With Maps and Illustrations. *Crown 8vo. 3s. 6d.*
- Wilson (Bishop). SACRA PRIVATA.** Edited by A. E. BURN, B.D. *Small Pott 8vo. Cloth, 2s.; leather, 2s. 6d. net.* [Library of Devotion.]
- Willson (Beckles). LORD STRATHCONA: the Story of his Life.** Illustrated. *Demy 8vo. 7s. 6d.*
A Colonial Edition is also published.
- Wilson (A. J.),** Editor of the *Investor's Review*, City Editor of the *Daily Chronicle*. **THE INSURANCE INDUSTRY.** *Crown 8vo. 2s. 6d. net.* [Books on Business.]
- Wilson (H. A.). LAW IN BUSINESS.** *Crown 8vo. 2s. 6d. net.* [Books on Business.]
- Wilton (Richard), M.A. LYRA PASTORALIS: Songs of Nature, Church, and Home.** *Pott 8vo. 2s. 6d.*
A volume of devotional poems.
- Wimbolt (S. E.), M.A.,** Assistant Master in Christ's Hospital. **EXERCISES IN LATIN ACCIDENCE.** *Crown 8vo. 1s. 6d.*
An elementary book adapted for Lower Forms to accompany the Shorter Latin Primer.
- LATIN HEXAMETER VERSE: An Aid to Composition.** *Crown 8vo. 3s. 6d. Key, 5s. net.*
- Windle (R. C. A.), D.Sc., F.R.S. SHAKESPEARE'S COUNTRY.** Illustrated by E. H. New. *Second Edition. Small Pott 8vo. cloth, 3s.; leather, 3s. 6d. net.* [Little Guides.]
- THE MALVERN COUNTRY.** Illustrated by E. H. New. *Small Pott 8vo. Cloth, 3s.; leather, 3s. 6d. net.* [Little Guides.]
- REMAINS OF THE PREHISTORIC AGE IN ENGLAND.** With numerous Illustrations and Plans. *Demy 8vo. 7s. 6d. net.* [Antiquary's Books.]
- CHESTER.** Illustrated by E. H. New. *Crown 8vo. 3s. 6d. net.* [Ancient Cities.]
- Winterbotham (Canon) M.A., B.Sc., LL.B. THE KINGDOM OF HEAVEN HERE AND HEREAFTER.** *Crown 8vo. 3s. 6d.* [Churchman's Library.]
- Wood (J. A. E.). HOW TO MAKE A DRESS.** Illustrated. *Third Edition. Cr. 8vo. 1s. 6d.* [Textbooks of Technology.]
- Wordsworth (Christopher), M.A., and Littlehales (Henry). OLD SERVICE BOOKS OF THE ENGLISH CHURCH.** With Coloured and other Illustrations. *Demy 8vo. 7s. 6d. net.* [Antiquary's Books.]
- Wordsworth (W.). SELECTIONS.** Edited by NOWELL C. SMITH, M.A. *Small Pott 8vo. Cloth, 1s. 6d. net; leather, 2s. 6d. net.* [Little Library.]
- Wordsworth (W.) and Coleridge (S. T.). LYRICAL BALLADS.** Edited by GEORGE SAMPSON. *Small Pott 8vo. Cloth, 1s. 6d. net; leather, 2s. 6d. net.* [Little Library.]
- Wright (Arthur), M.A.,** Fellow of Queen's College, Cambridge. **SOME NEW TESTAMENT PROBLEMS.** *Crown 8vo. 6s.* [Churchman's Library.]
- Wright (Sophie). GERMAN VOCABULARIES FOR REPETITION.** *Fcap. 8vo. 1s. 6d.*
- Wyld (A. B.). MODERN ABYSSINIA.** With a Map and a Portrait. *Demy 8vo. 15s. net.*
- Wyndham (G.), M.P. THE POEMS OF WILLIAM SHAKESPEARE.** With an Introduction and Notes. *Demy 8vo. Buckram, gilt top. 10s. 6d.*
- Wyon (E.) and France (S.). THE LAND OF THE BLACK MOUNTAIN.** Being a description of Montenegro. With 40 Illustrations. *Crown 8vo. 6s.*
A Colonial Edition is also published.
- Yeats (W. B.). AN ANTHOLOGY OF IRISH VERSE.** *Revised and Enlarged Edition. Crown 8vo. 3s. 6d.*
- Yendis (M.). THE GREAT RED FROG.** A Story told in 40 Coloured Pictures. *Fcap. 8vo. 1s. net.*
- Young (Filion). THE COMPLETE MOTORIST.** With many Illustrations. *Demy 8vo. 12s. 6d. net.*
- Young (T. M.). THE AMERICAN COTTON INDUSTRY: A Study of Work and Workers.** With an Introduction by ELIJAH HELM, Secretary to the Manchester Chamber of Commerce. *Crown 8vo. cloth, 2s. 6d.; paper boards, 1s. 6d.*

Antiquary's Books, The

General Editor, J. CHARLES COX, LL.D., F.S.A.

ENGLISH MONASTIC LIFE. By the Right Rev. Abbot Gasquet, O.S.B. Illustrated. *Demy 8vo. 7s. 6d. net.***REMAINS OF THE PREHISTORIC AGE IN ENGLAND.** By R. C. A. Windle, D.Sc., F.R.S. With numerous illustrations and Plans. *Demy 8vo. 4s. 6d. net.***OLD SERVICE BOOKS OF THE ENGLISH CHURCH.** By Christopher Wordsworth, M.A., and Henry Littlehales. With Coloured and other Illustrations. *Demy 8vo. 7s. 6d. net.***CELTIC ART.** By J. Rosalby Allen, F.S.A. With numerous illustrations and Plans. *Demy 8vo. 7s. 6d. net.***Business, Books on**
Crown 8vo. 2s. 6d. net.

The first Twelve volumes are—

PORTS AND DOCKS. By Douglas Owen.**RAILWAYS.** By E. R. McDermott.**THE STOCK EXCHANGE.** By Chas Duguid. *Second Edition.***THE INSURANCE INDUSTRY.** By A. J. Wilson.**THE ELECTRICAL INDUSTRY.** By A. G. Whyte, B.Sc.**THE SHIPBUILDING INDUSTRY.** By David Pollock, M.I.N.A.**THE MONEY MARKET.** By F. Straker.**THE AGRICULTURAL INDUSTRY.** By A. G. L. Rogers, M.A.**LAW IN BUSINESS.** By H. A. Wilson.**THE BREWING INDUSTRY.** By Julian L. Baker, F.I.C., F.C.S.**THE AUTOMOBILE INDUSTRY.** By G. de H. Stone.**MINING AND MINING INVESTMENTS.** By 'A. Moll.**Byzantine Texts**

Edited by J. B. BURY, M.A., Litt.D.

ZACHARIAH OF MITYLENE. Translated by F. J. Hamilton, D.D., and E. W. Brooks. *Demy 8vo. 12s. 6d. net.***EVAGRIUS.** Edited by Léon Parmentier and M. Bidez. *Demy 8vo. 10s. 6d. net.***THE HISTORY OF PSELLUS.** Edited by C. Sathas. *Demy 8vo. 15s. net.***ECTHESIS CHRONICA.** Edited by Professor Lambros. *Demy 8vo. 7s. 6d. net.***THE CHRONICLE OF MORBA.** Edited by John Schmitt. *Demy 8vo. 15s. net.***Churchman's Bible, The**

General Editor, J. H. BURN, B.D., F.R.S.E.

The volumes are practical and devotional, and the text of the Authorised Version is explained in sections, which correspond as far as possible with the Church Lectionary.

THE EPISTLE TO THE GALATIANS. Edited by A. W. Robinson, M.A. *Fcap. 8vo. 2s. 6d. net.***ECCLESIASTES.** Edited by A. W. Straneo, D.D. *Fcap. 8vo. 1s. 6d. net.***THE EPISTLE TO THE PHILIPPIANS.** Edited by C. R. D. Biggs, D.D. *Fcap. 8vo. 1s. 6d. net.***THE EPISTLE OF ST. JAMES.** Edited by H. W. Fulford, M.A. *Fcap. 8vo. 1s. 6d. net.***ISAIAH.** Edited by W. E. Barnes, D.D., Hulsean Professor of Divinity. *Two Volumes. Fcap. 8vo. 2s. net each. With Map.***THE EPISTLE OF ST. PAUL THE APOSTLE TO THE EPHESIANS.** Edited by G. H. Whitaker, M.A. *Fcap. 8vo. 1s. 6d. net.***Churchman's Library, The**

General Editor, J. H. BURN, B.D., F.R.S.E.

THE BEGINNINGS OF ENGLISH CHRISTIANITY. By W. E. Collins, M.A. With Map. *Crown 8vo. 3s. 6d.***SOME NEW TESTAMENT PROBLEMS.** By Arthur Wright, M.A. *Crown 8vo. 6s.***THE KINGDOM OF HEAVEN HERE AND HERE-AFTER.** By Canon Winterbotham, M.A., B.Sc., LL.B. *Crown 8vo. 3s. 6d.***THE WORKMANSHIP OF THE PRAYER BOOK; Its Literary and Liturgical Aspects.** By J. Dowden, D.D. *Second Edition. Crown 8vo. 3s. 6d.***EVOLUTION.** By F. B. Jevons, M.A., Litt.D. *Crown 8vo. 3s. 6d.***THE OLD TESTAMENT AND THE NEW SCHOLARSHIP.** By J. W. Peters, D.D. *Crown 8vo. 6s.***THE CHURCHMAN'S INTRODUCTION TO THE OLD TESTAMENT.** Edited by A. M. Mackay, B.A. *Crown 8vo. 3s. 6d.***THE CHURCH OF CHRIST.** By E. T. Green, M.A. *Crown 8vo. 6s.***COMPARATIVE THEOLOGY.** By J. A. MacCulloch. *Crown 8vo. 6s.***Classical Translations**

Edited by H. F. FOX, M.A., Fellow and Tutor of Brasenose College, Oxford.

*Crown 8vo.***ÆSCHYLUS—Agamemnon, Choephoroe, Eumenides.** Translated by Lewis Campbell, LL.D. 5s.**CICERO—De Oratore I.** Translated by E. N. P. Moor, M.A. 3s. 6d.**CICERO—Select Orations (Pro Milone, Pro Mureno, Philippic II., in Catilina).** Translated by H. E. D. Bakstun, M.A. 5s.**CICERO—De Natura Deorum.** Translated by F. Brooks, M.A. 3s. 6d.**CICERO—De Officiis.** Translated by G. R. Gardiner, M.A. 2s. 6d.**HORACE—The Odes and Epodes.** Translated by A. Godley, M.A. 2s.**LUCIAN—Six Dialogues (Nigrinus, Icaro-Menippus, The Cock, The Ship, The Parasite, The Lover of Falsehood).** Translated by S. T. Irwin, M.A. 3s. 6d.**SOPHOCLES—Electra and Ajax.** Translated by E. D. A. Morshead, M.A. 2s. 6d.**TACITUS—Agricola and Germania.** Translated by R. B. Townshend. 2s. 6d.**THE SATIRES OF JUVENAL.** Translated by S. G. Owen. *Crown 8vo. 2s. 6d.*

Commercial Series, Methuen's
 Edited by H. DE B. GIBBINS, Litt.D., M.A.

Crown 8vo.

- COMMERCIAL EDUCATION IN THEORY AND PRACTICE. By E. E. Whitfield, M.A. 5s.
 An introduction to Methuen's Commercial Series treating the question of Commercial Education fully from both the point of view of the teacher and of the parent.
- BRITISH COMMERCE AND COLONIES FROM ELIZABETH TO VICTORIA. By H. de B. Gibbins, Litt.D., M.A. *Third Edition.* 2s.
- COMMERCIAL EXAMINATION PAPERS. By H. de B. Gibbins, Litt.D., M.A. 1s. 6d.
- THE ECONOMICS OF COMMERCE. By H. de B. Gibbins, Litt.D., M.A. 1s. 6d.
- A GERMAN COMMERCIAL READER. By S. E. Bally, With Vocabulary. 2s.
- A COMMERCIAL GEOGRAPHY OF THE BRITISH EMPIRE. By L. W. Lyde, M.A. *Third Edition.* 2s.
- A PRIMER OF BUSINESS. By S. Jackson, M.A. *Third Edition.* 1s. 6d.
- COMMERCIAL ARITHMETIC. By F. G. Taylor, M.A. *Third Edition.* 1s. 6d.
- FRENCH COMMERCIAL CORRESPONDENCE. By S. E. Bally. With Vocabulary. *Third Edition.* 2s.
- GERMAN COMMERCIAL CORRESPONDENCE. By S. E. Bally. With Vocabulary. 2s. 6d.
- A FRENCH COMMERCIAL READER. By S. E. Bally. With Vocabulary. *Second Edition.* 2s.
- PRECIS WRITING AND OFFICE CORRESPONDENCE. By E. E. Whitfield, M.A. *Second Edition.* 2s.
- A GUIDE TO PROFESSIONS AND BUSINESS. By H. Jones. 1s. 6d.
- THE PRINCIPLES OF BOOK-KEEPING BY DOUBLE ENTRY. By J. E. B. M'Allen, M.A. 2s.
- COMMERCIAL LAW. By W. Douglas Edwards. 2s.

Connoisseurs Library, The

Wide Royal 8vo. 25s. net.

The first volumes are—

MEZZOTINTS. By Cyril Davenport.
 MINIATURES. By Dudley Heath.

PORCELAIN. By Edward Dillon.
 IVORIES. By A. Maskell.

Devotion, The Library of

With Introductions and (where necessary) Notes.

Small Pott 8vo, cloth, 2s. ; leather, 2s. 6d. net.

- THE CONFESSIONS OF ST. AUGUSTINE. Edited by C. Bigg, D.D. *Third Edition.*
- THE CHRISTIAN YEAR. Edited by Walter Lock, D.D. *Second Edition.*
- THE IMITATION OF CHRIST. Edited by C. Bigg, D.D. *Second Edition.*
- A BOOK OF DEVOTIONS. Edited by J. W. Stanbridge, B.D. *Second Edition.*
- LYRA INNOCENTIUM. Edited by Walter Lock, D.D.
- A SERIOUS CALL TO A DEVOUT AND HOLY LIFE. Edited by C. Bigg, D.D. *Second Edition.*
- THE TEMPLE. Edited by E. C. S. Gibson, D.D.
- A GUIDE TO ETERNITY. Edited by J. W. Stanbridge, B.D.
- THE PSALMS OF DAVID. Edited by B. W. Randolph, D.D.
- LYRA APOSTOLICA. Edited by Canon Scott Holland and Canon H. C. Beeching, M.A.
- THE INNER WAY. Edited by A. W. Hutton, M.A.
- THE THOUGHTS OF PASCAL. Edited by C. S. Jerram, M.A.
- ON THE LOVE OF GOD. By St. Francis de Sales. Edited by W. J. Knox-Little, M.A.
- A MANUAL OF CONSOLATION FROM THE SAINTS AND FATHERS. Edited by J. H. Burn, B.D.
- THE SONG OF SONGS. Edited by B. Blaxland, M.A.
- THE DEVOTIONS OF ST. ANSELM. Edited by C. C. J. Webb, M.A.
- GRACE ABOUNDING. By John Bunyan. Edited by S. C. Freer, M.A.
- BISHOP WILSON'S SACRA PRIVATA. Edited by A. E. Burn, B.D.
- LYRA SACRA: A Book of Sacred Verse. Edited by H. C. Beeching, M.A., Canon of Westminster.
- A DAY BOOK FROM THE SAINTS AND FATHERS. Edited by J. H. Burn, B.D.
- HEAVENLY WISDOM. A Selection from the English Mystics. Edited by E. C. Gregory.
- LIGHT, LIFE, AND LOVE. A Selection from the German Mystics. Edited by W. R. Inge, M.A.

Illustrated Pocket Library of Plain and Coloured Books, The

Fcap. 8vo. 3s. 6d. net to 4s. 6d. net each volume.

A series, in small form, of some of the famous illustrated books of fiction and general literature. These are faithfully reprinted from the first or best editions without introduction or notes.

COLOURED BOOKS

- THE LIFE AND DEATH OF JOHN MYTTON, ESQ. By Nimrod. With 18 Coloured Plates by Henry Alken and T. J. Rawlins. *Third Edition.* 3s. 6d. net. Also a limited edition on large Japanese paper. 30s. net.
- THE LIFE OF A SPORTSMAN. By Nimrod. With 35 Coloured Plates by Henry Alken. 4s. 6d. net. Also a limited edition on large Japanese paper. 30s. net.
- HANDLEY CROSS. By R. S. Surtees. With 17 Coloured Plates and 100 Woodcuts in the Text by John Leech. 4s. 6d. net. Also a limited edition on large Japanese paper. 30s. net.
- MR. SPONGE'S SPORTING TOUR. By R. S. Surtees. With 13 Coloured Plates and 90 Woodcuts in the Text by John Leech. 3s. 6d. net. Also a limited edition on large Japanese paper. 30s. net.

[Continued.]

THE ILLUSTRATED POCKET LIBRARY—continued.

JORROCK'S JAUNTS AND JOLLITIES. By R. S. Surtees. With 15 Coloured Plates by H. Alken. 3s. 6d. net.
Also a limited edition on large Japanese paper. 30s. net.

This volume is reprinted from the extremely rare and costly edition of 1843, which contains Alken's very fine illustrations instead of the usual ones by Philz.

ASK MAMMA. By R. S. Surtees. With 13 Coloured Plates and 70 Woodcuts in the Text by John Leech. 3s. 6d. net.
Also a limited edition on large Japanese paper. 30s. net.

THE ANALYSIS OF THE HUNTING FIELD. By R. S. Surtees. With 7 Coloured Plates by Henry Alken, and 43 Illustrations on Wood. 3s. 6d. net.

THE TOUR OF DR. SYNTAX IN SEARCH OF THE PICTURESQUE. By William Combe. With 30 Coloured Plates by T. Rowlandson. 3s. 6d. net.
Also a limited edition on large Japanese paper. 30s. net.

THE TOUR OF DOCTOR SYNTAX IN SEARCH OF CONSOLATION. By William Combe. With 24 Coloured Plates by T. Rowlandson. 3s. 6d. net.
Also a limited edition on large Japanese paper. 30s. net.

THE THIRD TOUR OF DOCTOR SYNTAX IN SEARCH OF A WIFE. By William Combe. With 24 Coloured Plates by T. Rowlandson. 3s. 6d. net.
Also a limited edition on large Japanese paper. 30s. net.

THE HISTORY OF JOHNNY QUAR GENUS: the Little Foundling of the late Dr. Syntax. By the Author of 'The Three Tours.' With 24 Coloured Plates by Rowlandson. 3s. 6d. net. 100 copies on large Japanese paper. 21s. net.
Also a limited edition on large Japanese paper. 30s. net.

THE ENGLISH DANCE OF DEATH, from the Designs of T. Rowlandson, with Metrical Illustrations by the Author of 'Doctor Syntax.' *Two Volumes.* 9s. net.
This book contains 76 Coloured Plates.
Also a limited edition on large Japanese paper. 30s. net.

THE DANCE OF LIFE: A Poem. By the Author of 'Doctor Syntax.' Illustrated with 26 Coloured Engravings by T. Rowlandson. 3s. 6d. net.
Also a limited edition on large Japanese paper. 30s. net.

LIFE IN LONDON: or, the Day and Night Scenes of Jerry Hawthorn, Esq., and his Elegant Friend,

Corinthian Tom. By Pierce Egan. With 36 Coloured Plates by J. R. and G. Cruikshank. With numerous Designs on Wood. 4s. 6d. net.
Also a limited edition on large Japanese paper. 30s. net.

REAL LIFE IN LONDON: or, the Rambles and Adventures of Bob Tallyho, Esq., and his Cousin, The Hon. Tom Deshall. By an Amateur (Pierce Egan). With 31 Coloured Plates by Alken and Rowlandson, etc. *Two Volumes.* 9s. net.

THE LIFE OF AN ACTOR. By Pierce Egan. With 27 Coloured Plates by Theodore Lane, and several Designs on Wood. 4s. 6d. net.

THE VICAR OF WAKEFIELD. By Oliver Goldsmith, With 24 Coloured Plates by T. Rowlandson. 3s. 6d. net.
Also a limited edition on large Japanese paper. 30s. net.
A reproduction of a very rare book.

THE MILITARY ADVENTURES OF JOHNNY NEWCOME. By an Officer. With 19 Coloured Plates by T. Rowlandson. 3s. 6d. net.

THE NATIONAL SPORTS OF GREAT BRITAIN. With Descriptions and 51 Coloured Plates by Henry Alken. 4s. 6d. net.
Also a limited edition on large Japanese paper. 30s. net.

This book is completely different from the large folio edition of 'National Sports' by the same artist, and none of the plates are similar.

THE ADVENTURES OF A POST CAPTAIN. By A Naval Officer. With 24 Coloured Plates by Mr. Williams. 3s. 6d. net.

GAMONIA: or, the Art of Preserving Game; and an Improved Method of making Plantations and Covers, explained and illustrated by Lawrence Rawstone, Esq. With 15 Coloured Plates by T. Rawlin. 3s. 6d. net.

AN ACADEMY FOR GROWN HORSEMEN: containing the completest Instructions for Walking, Trotting, Cantering, Galloping, Stumbling, and Tumbling. Illustrated with 27 Coloured Plates, and adorned with a Portrait of the Author. By Geoffrey Gambado, Esq. 3s. 6d. net.

REAL LIFE IN IRELAND, or the Day and Night Scenes of Brian Boru, Esq., and his Elegant Friend, Sir Shawn O'Dogherty. By a Real Paddy. With 19 Coloured Plates by Heaths, Marks, etc. 3s. 6d. net.

THE ADVENTURES OF JOHNNY NEWCOME IN THE NAVY. By Alfred Burton. With 16 Coloured Plates by T. Rowlandson. 3s. 6d. net.

PLAIN BOOKS

THE GRAVE: A Poem. By Robert Blair. Illustrated by 12 Etchings executed by Louis Schiavonetti from the Original Inventions of William Blake. With an Engraved Title Page and a Portrait of Blake by T. Phillips, R.A. 3s. 6d. net.

The Illustrations are reproduced in photogravure. Also a limited edition on large Japanese paper, with India proofs and a duplicate set of the plates. 15s. net.

ILLUSTRATIONS OF THE BOOK OF JOB. Invented and engraved by William Blake. 3s. 6d. net.

These famous Illustrations—21 in number—are reproduced in photogravure. Also a limited edition on large Japanese paper, with India proofs and a duplicate set of the plates. 15s. net.

ESOP'S FABLES. With 380 Woodcuts by Thomas Bewick. 3s. 6d. net.

WINDSOR CASTLE. By W. Harrison Ainsworth.

With 22 Plates and 87 Woodcuts in the Text by George Cruikshank. 3s. 6d. net.

THE TOWER OF LONDON. By W. Harrison Ainsworth. With 40 Plates and 58 Woodcuts in the Text by George Cruikshank. 3s. 6d. net.

FRANK FAIRLEIGH. By F. E. Smedley. With 30 Plates by George Cruikshank. 3s. 6d. net.

HANDY ANDY. By Samuel Lover. With 24 Illustrations by the Author. 3s. 6d. net.

THE COMPIRAT ANGLER. By Isaac Walton and Charles Cotton. With 14 Plates and 77 Woodcuts in the Text. 3s. 6d. net.

This volume is reproduced from the beautiful edition of John Major of 1824.

THE PICKWICK PAPERS. By Charles Dickens, With the 43 Illustrations by Seymour and Philz, the two Esau Plates, and the 38 Contemporary Onwhya Plates. 3s. 6d. net.

Junior Examination SeriesEdited by A. M. M. STEDMAN, M.A. *Fcap. 8vo. 1s.*

- JUNIOR FRENCH EXAMINATION PAPERS. By F. Jacob, B.A.
 JUNIOR LATIN EXAMINATION PAPERS. *Second Edition.* By C. G. Botting, M.A.
 JUNIOR ENGLISH EXAMINATION PAPERS. By W. Williamson, B.A.
 JUNIOR ARITHMETIC EXAMINATION PAPERS. By W. S. Beard, *Second Edition.*
 JUNIOR ALGEBRA EXAMINATION PAPERS. By S. W. Finn, M.A.
 JUNIOR GREEK EXAMINATION PAPERS. By T. C. Weatherhead, M.A.
 JUNIOR GENERAL INFORMATION EXAMINATION PAPERS. By W. S. Beard.
 JUNIOR GEOGRAPHY EXAMINATION PAPERS. By W. G. Baker, M.A.
 JUNIOR GERMAN EXAMINATION PAPERS. By A. Voegelin, M.A.

Junior School-Books, Methuen's

Edited by O. D. INSKIP, LL.D., and W. WILLIAMSON, B.A.

- A CLASS-BOOK OF DICTATION PASSAGES. By W. Williamson, B.A. *Eighth Edition. Crown 8vo. 1s. 6d.*
 THE GOSPEL ACCORDING TO ST. MATTHEW. Edited by E. Wilton South, M.A. *Crown 8vo. 1s. 6d.*
 THE GOSPEL ACCORDING TO ST. MARK. Edited by A. E. Rubie, M.A., Headmaster of College, Egham. With Three Maps. *Crown 8vo. 1s. 6d.*
 A JUNIOR ENGLISH GRAMMAR. By W. Williamson, B.A. With numerous passages for parsing and analysis, and a chapter on Essay Writing. *Crown 8vo. 2s.*
 A JUNIOR CHEMISTRY. By E. A. Tyler, B.A., F.C.S., Science Master at Swansea Grammar School, With 73 Illustrations. *Crown 8vo. 2s. 6d.*
 THE ACTS OF THE APOSTLES. Edited by A. E. Rubie, M.A., Headmaster of College, Egham. *Crown 8vo. 2s.*
 THE FIRST BOOK OF KINGS. Edited by A. E. Rubie, M.A. *Crown 8vo. 1s. 6d.*
 A JUNIOR FRENCH GRAMMAR. By L. A. Sornet and M. J. Acatos, Modern Language Masters at King Edward's School, Birmingham. *Cr. 8vo. 2s.*
 ELEMENTARY EXPERIMENTAL SCIENCE. PHYSICS by W. T. Clough, A.R.C.S. CHEMISTRY by A. E. Dunstan, B.Sc. With 5 Plates and 154 Diagrams. *Crown 8vo. 2s.*
 A JUNIOR GEOMETRY. By Noel S. Lydon. With 59 Diagrams. *Crown 8vo. 2s.*

Leaders of ReligionEdited by H. C. BEECHING, M.A., Canon of Westminster. *With Portraits. Crown 8vo. 3s. 6d.*

A series of short biographies of the most prominent leaders of religious life and thought of all ages and countries.

- CARDINAL NEWMAN. By R. H. Hutton.
 JOHN WESLEY. By J. H. Overton, M.A.
 BISHOP WILBERFORCE. By G. W. Dantell, M.A.
 CARDINAL MANNING. By A. W. Hutton, M.A.
 CHARLES SIMON. By H. C. G. Moule, D.D.
 JOHN KEBLE. By Walter Lock, D.D.
 THOMAS CHALMERS. By Mrs. Oliphant.
 LANCELOT ANDREWES. By R. L. Orley, M.A.
 AUGUSTINE OF CANTERBURY. By E. L. Cuttis, D.D.
 WILLIAM LAUD. By W. H. Hutton, M.A.
 JOHN KNOX. By F. MacCunn.
 JOHN HOWE. By R. F. Horton, D.D.
 BISHOP KIM. By F. A. Clarke, M.A.
 GEORGE FOX, THE QUAKER. By T. Hodgkin D.C.L.
 JOHN DONNE. By Augustus Jessopp, D.D.
 THOMAS CRANMER. By A. J. Mason, D.D.
 BISHOP LATIMER. By R. M. Carlyle and A. J. Carlyle, M.A.
 BISHOP BUTLER. By W. A. Spooner, M.A.

Little Biographies*Fcap. 8vo. Each volume, cloth, 3s. 6d.; leather, 4s. net.*

- DANTE ALIGHIERI. By Paget Toynbee, M.A. D.Lit. With 12 Illustrations. *Second Edition.*
 SAVONAROLA. By E. L. S. Horsburgh, M.A. With 12 Illustrations. *Second Edition.*
 JOHN HOWARD. By E. C. S. Gibson, D.D., Vicar of Leeds. With 12 Illustrations.
 TENNYSON. By A. C. Benson, M.A. With 9 Illustrations.
 WALTER RALEIGH. By J. A. Taylor. With 12 Illustrations.
 ERASMUS. By E. F. H. Capey. With 12 Illustrations.
 THE YOUNG PRETENDER. By C. S. Terry. With 12 Illustrations.
 ROBERT BURNS. By T. F. Henderson. With 12 Illustrations.
 CHATHAM. By A. S. M'Dowall. With 12 Illustrations.
 ST. FRANCIS OF ASSISI. By Anna M. Stoddart. With 16 Illustrations.
 CANNING. By W. A. Phillips. With 12 Illustrations.
 BEACONSFIELD. By Walter Siebel. With 12 Illustrations.
 GOETHE. By H. G. Atkins. With 12 Illustrations.

Little Blue Books, The
General Editor, E. V. LUCAS.*Illustrated. Demy 16mo. 2s. 6d.*

1. THE CASTAWAYS OF MEADOWBANK. By T. Cobb.
 2. THE BEECHNUT BOOK. By Jacob Abbott. Edited by E. V. Lucas.
 3. THE AIR GUN. By T. Hilbert.
 4. A SCHOOL YEAR. By Netta Syrett.
 5. THE PELES AT THE CAPITAL. By Roger Ashton.

[Continued.]

THE LITTLE BLUE BOOKS—continued.

- | | |
|---|---|
| 6. THE TREASURE OF PRINCEGATE PRIORY. By T. Cobb. | 8. A BOOK OF BAD CHILDREN. By W. T. Webb. |
| 7. MRS. BARBERY'S GENERAL SHOP. By Roger Ashton. | 9. THE LOST BALL. By Thomas Cobb. |

Little Books on Art

Demy 16mo. 2s. 6d. net.

- | | |
|--|--|
| GREEK ART. H. R. Walters. | TURNER. F. Tyrrell-Gill. |
| BOOKPLATES. E. Almack. | DURER. Jessie Allen. |
| REYNOLDS. J. Sims. | HOFFNER. H. P. K. Skipton. |
| ROMNEY. George Paston. | HOLBEIN. Mrs. G. Fortescue. |
| WATTS. Miss R. E. D. Sketchley. | MILLER. Miss N. Peacock. |
| LIGHTON. Alice Corkran. | BURNE-JONES. Miss F. de Lisle. |
| VILLASQUEZ. Wilfrid Wilberforce and A. R. Gilbert. | REMBRANDT. Mrs. E. A. Sharp. |
| GREUZE AND BOUCHER. Eliza F. Pollard. | COROT. Alice Pollard and Ethel Birnstingl. |
| VANDYCK. M. G. Smallwood. | |

Little Galleries, The

Demy 16mo. 2s. 6d. net.

- | | |
|--|------------------------------|
| A LITTLE GALLERY OF REYNOLDS. | A LITTLE GALLERY OF HOFFNER. |
| A LITTLE GALLERY OF ROMNEY. | A LITTLE GALLERY OF MILLAIS. |
| A LITTLE GALLERY OF ENGLISH PORTRAITS. | |

Little Guides, The

Small Pott 8vo, cloth, 3s.; leather, 3s. 6d. net.

- | | |
|---|---|
| OXFORD AND ITS COLLEGES. By J. Wells, M.A. Illustrated by E. H. New. <i>Fourth Edition.</i> | THE ENGLISH LAKES. By F. G. Brabant, M.A. Illustrated by E. H. New. <i>4s.; leather, 4s. 6d. net.</i> |
| CAMBRIDGE AND ITS COLLEGES. By A. Hamilton Thompson. Illustrated by E. H. New. | KENT. By G. Clinch. Illustrated by F. D. Bedford. |
| THE MALVERN COUNTRY. By B. C. A. Windle, D.Sc., F.R.S. Illustrated by E. H. New. | ROME. By C. G. Elaby. Illustrated by B. C. Boulter. |
| SHAKESPEARE'S COUNTRY. By B. C. A. Windle, D.Sc., F.R.S. Illustrated by E. H. New. <i>Second Edition.</i> | THE ISLE OF WIGHT. By G. Clinch. Illustrated by F. D. Bedford. |
| SUSSEX. By F. G. Brabant, M.A. Illustrated by E. H. New. | SURREY. By F. A. H. Lambert. Illustrated by E. H. New. |
| WESTMINSTER ABBEY. By G. E. Troutbeck. Illustrated by F. D. Bedford. | BUCKINGHAMSHIRE. By E. S. Roscoe. Illustrated by F. D. Bedford. |
| NORFOLK. By W. A. Dutt. Illustrated by R. C. Boulter. | SUFFOLK. By W. A. Dutt. Illustrated by J. Wylie. |
| CORNWALL. By A. L. Salmon. Illustrated by R. C. Boulter. | DERBYSHIRE. By J. Charles Cox, LL.D., F.S.A. Illustrated by J. C. Wall. |
| BRITTANY. By S. Baring-Gould. Illustrated by J. Wylie. | THE NORTH RIDING OF YORKSHIRE. By J. E. Morris. Illustrated by R. J. S. Bertram. |
| HERTFORDSHIRE. By H. W. Tompkins, F.R.H.S. Illustrated by E. H. New. | HAMPSHIRE. By J. C. Cox. Illustrated by M. E. Purser. |
| | SICILY. By F. H. Jackson. With many illustrations by the Author. |

Little Library, The

With Introductions, Notes, and Photogravure Frontispieces.

Small Pott 8vo. Each Volume, cloth, 1s. 6d. net; leather, 2s. 6d. net.

- | | |
|---|--|
| VANITY FAIR. By W. M. Thackeray. Edited by S. Gwynn. <i>Three Volumes.</i> | THE PRINCESS. By Alfred, Lord Tennyson. Edited by Elizabeth Wordsworth. |
| PENDERENNIS. By W. M. Thackeray. Edited by S. Gwynn. <i>Three Volumes.</i> | MAUD. By Alfred, Lord Tennyson. Edited by Elizabeth Wordsworth. |
| ESMOND. By W. M. Thackeray. Edited by S. Gwynn. | IN MEMORIAM. By Alfred, Lord Tennyson. Edited by H. C. Beching, M.A. |
| CHRISTMAS BOOKS. By W. M. Thackeray. Edited by S. Gwynn. | THE EARLY POEMS OF ALFRED, LORD TENNYSON. Edited by J. C. Collins, M.A. |
| SELECTIONS FROM GEORGE CRABBE. Edited by A. C. Drake. | A LITTLE BOOK OF ENGLISH LYRICS. With Notes. |
| JOHN HALIFAX, GENTLEMAN. By Mrs. Craik. Edited by Annie Matheson. <i>Two Volumes.</i> | THE INFERNO OF DANTE. Translated by H. F. Cary. Edited by Paget Toynbee, M.A., D.Lit. |
| PRIDE AND PREJUDICE. By Jane Austen. Edited by E. V. Lucas. <i>Two Volumes.</i> | THE PURGATORIO OF DANTE. Translated by H. F. Cary. Edited by Paget Toynbee, M.A., D.Lit. |
| NORTHANGER ABBEY. By Jane Austen. Edited by E. V. Lucas. | THE PARADISO OF DANTE. Translated by H. F. Cary. Edited by Paget Toynbee, M.A., D.Lit. |

(Continued.)

THE LITTLE LIBRARY—continued.

A LITTLE BOOK OF SCOTTISH VERSE. Edited by T. F. Henderson.
 A LITTLE BOOK OF LIGHT VERSE. Edited by A. C. Deane.
 A LITTLE BOOK OF ENGLISH SONNETS. Edited by J. B. Nichols.
 POEMS. By John Keats. With an Introduction by L. Binyon, and Notes by J. Massfield.
 A complete Edition.
 THE MINOR POEMS OF JOHN MILTON. Edited by H. C. Beeching, M.A.
 THE POEMS OF HENRY VAUGHAN. Edited by Edward Hutton.
 SELECTIONS FROM WORDSWORTH. Edited by Nowell C. Smith.
 SELECTIONS FROM THE EARLY POEMS OF ROBERT BROWNING. Edited by W. Hall Griffin, M.A.
 THE ENGLISH POEMS OF RICHARD CRASHAW. Edited by Edward Hutton.
 SELECTIONS FROM WILLIAM BLAKE. Edited by M. Perugini.
 SELECTIONS FROM THE POEMS OF GEORGE DARLEY. Edited by R. A. Streatfield.
 LYRICAL BALLADS. By W. Wordsworth and S. T. Coleridge. Edited by George Sampson.
 SELECTIONS FROM LONGFELLOW. Edited by Lillian M. Faithfull.
 SELECTIONS FROM THE ANTI-JACOBIN; with George Canning's additional Poems. Edited by Lloyd Sanders.
 THE POEMS OF ANDREW MARVELL. Edited by Edward Wright.
 A LITTLE BOOK OF LIFE AND DEATH. Edited by Mrs. Alfred Waterhouse. *Fourth Edition.*
 A LITTLE BOOK OF ENGLISH PROSE. Edited by Mrs. P. A. Barnatt.
 EOTHEN. By A. W. Kinglake. With an Introduction and Notes.

CRANFORD. By Mrs. Gaskell. Edited by E. V. Lucas.
 LAVENGRO. By George Borrow. Edited by F. Hindaes Groomer. *Two Volumes.*
 THE ROMANY RYE. By George Borrow. Edited by John Simpson.
 THE HISTORY OF THE CALIPH VATHEK. By William Beckford. Edited by E. Denison Ross.
 THE COMPLEAT ANGLER. By Isaak Walton. Edited by J. Buchan.
 MARRIAGE. By Susan Ferrier. Edited by Miss Goodrich-Freer and Lord Idlesleigh. *Two Volumes.*
 THE INHERITANCE. By Susan Ferrier. Edited by Miss Goodrich-Freer and Lord Idlesleigh. *Two Volumes.*
 ELIA, AND THE LAST ESSAYS OF ELIA. By Charles Lamb. Edited by E. V. Lucas.
 THE ESSAYS OF ABRAHAM COWLEY. Edited by H. C. Minchin.
 THE ESSAYS OF FRANCIS BACON. Edited by Edward Wright.
 THE MAXIMS OF LA ROCHEFOUCAULD. Translated by Dean Stanhope. Edited by G. H. Powell.
 A SENTIMENTAL JOURNEY. By Laurence Sterne. Edited by H. W. Paul.
 MANSIE WAUCH. By D. M. Moir. Edited by T. F. Henderson.
 THE INGOLDSBY LEGENDS. By R. H. Barham. Edited by J. B. Atlay. *Two Volumes.*
 THE SCARLET LETTER. By Nathaniel Hawthorne. Edited by P. Desnoes.
 REJECTED ADDRESSES. By Horace and James Smith. Edited by A. D. Godley, M.A.
 LONDON LYRICS. By F. Locker. Edited by A. D. Godley, M.A.
 A reprint of the First Edition.

Miniature Library, Methuen's

EUPHRANOR: a Dialogue on Youth. By Edward FitzGerald. From the edition published by W. Pickering in 1851. *Demy 32mo. Leather, 2s. net.*
 POLONIUS: or Wise Saws and Modern Instances. By Edward FitzGerald. From the edition published by W. Pickering in 1852. *Demy 32mo. Leather, 2s. net.*
 THE RUBAIYAT OF OMAR KHAYYAM. By Edward FitzGerald. From the 1st edition of 1859. *Second Edition. Leather, 2s. net.*

THE LIFE OF EDWARD, LORD HERBERT OF CHERBURY. Written by himself. From the edition printed at Strawberry Hill in the year 1764. *Medium 32mo. Leather, 2s. net.*
 THE VISIONS OF DOM FRANCISCO DE QUEVEDO VILEGAS, Knight of the Order of St. James. Made English by R. L. From the edition printed for H. Herringman, 1668. *Leather, 2s. net.*
 POEMS. By Dora Greenwell. From the edition of 1848. *Leather, 2s. net.*

School Examination Series

Edited by A. M. M. STEDMAN, M.A. *Crown 8vo. 2s. 6d.*

FRENCH EXAMINATION PAPERS. By A. M. M. Stedman, M.A. *Twelfth Edition.*
 A KEY, issued to Tutors and Private Students only, to be had on application to the Publishers. *Fifth Edition. Crown 8vo. 6s. net.*
 LATIN EXAMINATION PAPERS. By A. M. M. Stedman, M.A. *Twelfth Edition.*
 KEY (*Fourth Edition*) issued as above. *6s. net.*
 GREEK EXAMINATION PAPERS. By A. M. M. Stedman, M.A. *Seventh Edition.*
 KEY (*Second Edition*) issued as above. *6s. net.*
 GERMAN EXAMINATION PAPERS. By R. J. Morich. *Fifth Edition.*
 KEY (*Second Edition*) issued as above. *6s. net.*

HISTORY AND GEOGRAPHY EXAMINATION PAPERS. By C. H. Spence, M.A., Clifton College. *Second Edition.*
 PHYSICS EXAMINATION PAPERS. By R. E. Steel, M.A., F.C.S.
 GENERAL KNOWLEDGE EXAMINATION PAPERS. By A. M. M. Stedman, M.A. *Fourth Edition.*
 KEY (*Third Edition*) issued as above. *7s. net.*
 EXAMINATION PAPERS IN ENGLISH HISTORY. By J. Tait Powden-Wardlaw, B.A.

Social Questions of To-day

Edited by H. DE B. GIBBINS, Litt.D., M.A.

Crown 8vo. 2s. 6d.

- TRADE UNIONISM—NEW AND OLD.** By G. Howell. *Third Edition.*
- THE CO-OPERATIVE MOVEMENT TO-DAY.** By G. J. Holyoake. *Second Edition.*
- PROBLEMS OF POVERTY.** By J. A. Hobson, M.A. *Fourth Edition.*
- THE COMMERCE OF NATIONS.** By C. F. Bastable, M.A. *Third Edition.*
- THE ALIEN INVASION.** By W. H. Wilkins, B.A.
- THE RURAL EXODUS.** By P. Anderson Graham.
- LAND NATIONALIZATION.** By Harold Cox, B.A.
- A SHORTER WORKING DAY.** By H. de B. Gibbins and R. A. Radford.
- BACK TO THE LAND: An Inquiry into Rural Depopulation.** By H. E. Moore.
- TRUSTS, POOLS, AND CORNERS.** By J. Stephen Jeans.
- THE FACTORY SYSTEM.** By R. W. Cooke-Taylor.
- THE STATE AND ITS CHILDREN.** By Gertrude Tuckwell.
- WOMEN'S WORK.** By Lady Dilke, Miss Bailey, and Miss Whitley.
- SOCIALISM AND MODERN THOUGHT.** By M. Kaufmann.
- THE HOUSING OF THE WORKING CLASSES.** By E. Bowmaker.
- THE PROBLEM OF THE UNEMPLOYED.** By J. A. Hobson, M.A.
- LIFE IN WEST LONDON.** By Arthur Sherwell, M.A. *Third Edition.*
- RAILWAY NATIONALIZATION.** By Clement Edwards.
- WORKHOUSES AND PAUPERISM.** By Louisa Twining.
- UNIVERSITY AND SOCIAL SETTLEMENTS.** By W. Reason, M.A.

Technology, Textbooks of

Edited by PROFESSOR J. WERTHEIMER, F.I.C.

Fully Illustrated.

- HOW TO MAKE A DRESS.** By J. A. E. Wood. *Third Edition. Crown 8vo. 1s. 6d.*
- CARPENTRY AND JOINERY.** By F. C. Webber. *Third Edition. Crown 8vo. 3s. 6d.*
- PRACTICAL MECHANICS.** By Sidney H. Wells. *Second Edition. Crown 8vo. 3s. 6d.*
- PRACTICAL PHYSICS.** By H. Stroud, D.Sc., M.A. *Crown 8vo. 3s. 6d.*
- MILLINERY, THEORETICAL AND PRACTICAL.** By Clare Hill. *Crown 8vo. 2s.*
- PRACTICAL CHEMISTRY.** By W. French, M.A. *Crown 8vo. Part I. Second Edition, 2s. 6d. Part II. TECHNICAL ARITHMETIC AND GEOMETRY. By C. T. Mills, M.L.M.E. With Diagrams. Crown 8vo. 3s. 6d.*
- BUILDER'S QUANTITIES.** By H. C. Grubb. With many illustrations. *Crown 8vo. 4s. 6d.*

Theology, Handbooks of

- THE XXXIX ARTICLES OF THE CHURCH OF ENGLAND.** Edited by E. C. S. Gibson, D.D. *Third and Cheaper Edition in One Volume. Demy 8vo. 2s. 6d.*
- AN INTRODUCTION TO THE HISTORY OF RELIGION.** By F. B. Jevons, M.A., Litt.D. *Second Edition. Demy 8vo. 10s. 6d.*
- THE DOCTRINE OF THE INCARNATION.** By R. L. Otley, M.A. *Second and Cheaper Edition. Demy 8vo. 2s. 6d.*
- AN INTRODUCTION TO THE HISTORY OF THE CREEDS.** By A. E. Burn, B.D. *Demy 8vo. 10s. 6d.*
- THE PHILOSOPHY OF RELIGION IN ENGLAND AND AMERICA.** By Alfred Caldecott, D.D. *Demy 8vo. 10s. 6d.*
- A HISTORY OF EARLY CHRISTIAN DOCTRINE.** By J. F. Bethune-Baker, M.A., Fellow of Pembroke College, Cambridge. *Demy 8vo. 10s. 6d.*

University Extension Series

Edited by J. E. SYMES, M.A.,

Principal of University College, Nottingham.

Crown 8vo. Price (with some exceptions) 2s. 6d.

A series of books on historical, literary, and scientific subjects, suitable for extension students and home-reading circles. Each volume is complete in itself, and the subjects are treated by competent writers in a broad and philosophic spirit.

- THE INDUSTRIAL HISTORY OF ENGLAND.** By H. de B. Gibbins, Litt.D., M.A. *Tenth Edition. Revised. With Maps and Plans. 2s.*
- A HISTORY OF ENGLISH POLITICAL ECONOMY.** By L. L. Price, M.A. *Third Edition.*
- VICTORIAN POETS.** By A. Sharp.
- THE FRENCH REVOLUTION.** By J. E. Symes, M.A.
- PSYCHOLOGY.** By F. S. Granger, M.A. *Second Edition.*
- THE EVOLUTION OF PLANT LIFE: Lower Forms.** By G. Masece. Illustrated.
- AIR AND WATER.** By V. B. Lewes, M.A. Illustrated.
- THE CHEMISTRY OF LIFE AND HEALTH.** By C. W. Kimmins, M.A. Illustrated.
- THE MECHANICS OF DAILY LIFE.** By V. P. Sells, M.A. Illustrated.
- ENGLISH SOCIAL REFORMERS.** By H. de B. Gibbins, Litt.D., M.A. *Second Edition.*
- ENGLISH TRADE AND FINANCE IN THE SEVENTEENTH CENTURY.** By W. A. S. Hewins, B.A.
- THE CHEMISTRY OF FIRE.** By M. M. Pattison Muir, M.A. Illustrated.
- A TEXT-BOOK OF AGRICULTURAL BOTANY.** By M. C. Potter, M.A., F.L.S. Illustrated. *Second Edition. 4s. 6d.*
- THE VAULT OF HEAVEN.** A Popular Introduction to Astronomy. By R. A. Gregory. With numerous illustrations.
- METEOROLOGY.** By H. N. Dickson, F.R.S.E., F.R. Met. Soc. Illustrated.
- A MANUAL OF ELECTRICAL SCIENCE.** By George J. Burch, M.A., F.R.S. Illustrated. 2s.
- THE EARTH.** An Introduction to Physiography. By Evan Small, M.A. Illustrated.
- INSECT LIFE.** By F. W. Theobald, M.A. Illustrated.
- ENGLISH POETRY FROM BLAKE TO BROWNING.** By W. M. Dixon, M.A. *Second Edition.*
- ENGLISH LOCAL GOVERNMENT.** By E. Jenks, M.A.
- THE GREEK VIEW OF LIFE.** By G. L. Dickinson. *Third Edition.*

Westminster Commentaries The

General Editor, WALTER LOCK, D.D., Warden of Keble College,
Dean Ireland's Professor of Exegesis in the University of Oxford.

THE BOOK OF GENESIS. Edited with Introduction and Notes by S. R. Driver, D.D., Canon of Christ Church, and Regius Professor of Hebrew at Oxford. Second Edition. Demy 8vo. 10s. 6d.
THE BOOK OF JOB. Edited by E. C. S. Gibson, D.D. Demy 8vo. 6s.
THE ACTS OF THE APOSTLES. Edited by R. B.

Rackham, M.A. Demy 8vo. Second and Cheaper Edition. 10s. 6d.
THE FIRST EPISTLE OF PAUL THE APOSTLE TO THE CORINTHIANS. Edited by H. L. Goudge, M.A. Demy 8vo. 6s.
THE EPISTLE OF ST. JAMES. Edited by R. J. Knowling, M.A. Demy 8vo. 6s.

PART II.—FICTION

Marie Corelli's Novels.

Crown 8vo

6s. each.

A ROMANCE OF TWO WORLDS. Twenty-Fourth Edition.

VENDETTA. Twentieth Edition.

THELMA. Thirtieth Edition.

ARDATH: THE STORY OF A DEAD SELF. Fifteenth Edition.

THE SOUL OF LILITH. Twelfth Edit.

WORMWOOD. Thirteenth Edition.

BARABBAS: A DREAM OF THE WORLD'S TRAGEDY. Thirty-Ninth Edition.

'The tender reverence of the treatment and the imaginative beauty of the writing have reconciled us to the daring of the conception. This "Dream of the World's Tragedy" is a lofty and not inadequate paraphrase of the supreme climax of the inspired narrative.'—*Dublin Review*.

THE SORROWS OF SATAN. Forty-Eighth Edition.

'A very powerful piece of work. . . . The conception is magnificent, and is likely to win an abiding place within the memory of man. . . . The author has immense command of language, and a limitless audacity. . . . This interesting and remarkable romance will live long after much of the ephemeral literature of the day is forgotten. . . . A literary phenomenon . . . novel, and even

ublime.'—W. T. STEAD in the *Review of Reviews*.

THE MASTER CHRISTIAN.

[165th Thousand.

'It cannot be denied that "The Master Christian" is a powerful book; that it is one likely to raise uncomfortable questions in all but the most self-satisfied readers, and that it strikes at the root of the failure of the Churches—the decay of faith—in a manner which shows the inevitable disaster heaping up. . . . The good Cardinal Bonpré is a beautiful figure, fit to stand beside the good Bishop in "Les Misérables." It is a book with a serious purpose expressed with absolute unconventionality and passion. . . . And this is to say it is a book worth reading.'—*Examiner*.

TEMPORAL POWER: A STUDY IN SUPREMACY. [150th Thousand.

'It is impossible to read such a work as "Temporal Power" without becoming convinced that the story is intended to convey certain criticisms on the ways of the world and certain suggestions for the betterment of humanity. . . . If the chief intention of the book was to hold the mirror up to shame, injustice, dishonesty, cruelty, and neglect of conscience, nothing but praise can be given to that intention.'—*Morning Post*.

GOD'S GOOD MAN: A SIMPLE LOVE STORY.

Anthony Hope's Novels.

Crown 8vo

6s. each.

THE GOD IN THE CAR. Ninth Edition.

'A very remarkable book, deserving of critical analysis impossible within our limit; brilliant, but not superficial; well considered, but not elaborated; constructed with the proverbial art that conceals, but yet allows itself to be enjoyed by readers to whom fine literary method is a keen pleasure.'—*The World*.

A CHANGE OF AIR. Sixth Edition.

'A graceful, vivacious comedy, true to

human nature. The characters are traced with a masterly hand.'—*Times*.

A MAN OF MARK. Fifth Edition.

'Of all Mr. Hope's books, "A Man of Mark" is the one which best compares with "The Prisoner of Zenda."—*National Observer*.

THE CHRONICLES OF COUNT ANTONIO. Fifth Edition.

'It is a perfectly enchanting story of love and chivalry, and pure romance. The Count is the most constant, desperate, and

modest and tender of lovers, a peerless gentleman, an intrepid fighter, a faithful friend, and a magnanimous foe."—*Guardian*.

PHROSO. Illustrated by H. R. MILLAR. *Sixth Edition.*

'The tale is thoroughly fresh, quick with vitality, stirring the blood.'—*St. James's Gazette*.

SIMON DALE. Illustrated. *Sixth Edition.*

'There is searching analysis of human nature, with a most ingeniously constructed plot. Mr. Hope has drawn the contrasts

of his women with marvellous subtlety and delicacy.'—*Times*.

THE KING'S MIRROR. *Fourth Edition.*

'In elegance, delicacy, and tact it ranks with the best of his novels, while in the wide range of its portraiture and the subtlety of its analysis it surpasses all his earlier ventures.'—*Spectator*.

QUISANTE. *Fourth Edition.*

'The book is notable for a very high literary quality, and an impress of power and mastery on every page.'—*Daily Chronicle*.

THE DOLLY DIALOGUES.

W. W. Jacobs' Novels

Crown 8vo. 3s. 6d. each.

MANY CARGOES. *Twenty-Seventh Edition.*

SEA URCHINS. *Tenth Edition.*

A MASTER OF CRAFT. Illustrated. *Sixth Edition.*

'Can be unreservedly recommended to all who have not lost their appetites for wholesome laughter.'—*Spectator*.

'The best humorous book published for many a day.'—*Black and White*.

LIGHT FREIGHTS. Illustrated. *Fourth Edition.*

'His wit and humour are perfectly irresistible. Mr. Jacobs writes of skippers, and mates, and seamen, and his crew are the jolliest lot that ever sailed.'—*Daily News*.

'Laughter in every page.'—*Daily Mail*.

Lucas Malet's Novels

Crown 8vo. 6s. each.

COLONEL ENDERBY'S WIFE. *Third Edition.*

A COUNSEL OF PERFECTION. *New Edition.*

LITTLE PETER. *Second Edition. 3s. 6d.*

THE WAGES OF SIN. *Fourteenth Edition.*

THE CARISSIMA. *Fourth Edition.*

THE GATELESS BARRIER. *Fourth Edition.*

'In "The Gateless Barrier" it is at once evident that, whilst Lucas Malet has preserved her birthright of originality, the artistry, the actual writing, is above even the high level of the books that were born before.'—*Westminster Gazette*.

THE HISTORY OF SIR RICHARD CALMADY. *Seventh Edition.* A Limited Edition in Two Volumes. *Crown 8vo. 12s.*

'A picture finely and amply conceived.

In the strength and insight in which the story has been conceived, in the wealth of fancy and reflection bestowed upon its execution, and in the moving sincerity of its pathos throughout, "Sir Richard Calmady" must rank as the great novel of a great writer.'—*Literature*.

'The ripest fruit of Lucas Malet's genius. A picture of maternal love by turns tender and terrible.'—*Spectator*.

'A remarkably fine book, with a noble motive and a sound conclusion.'—*Pilot*.

Gilbert Parker's Novels

Crown 8vo. 6s. each.

PIERRE AND HIS PEOPLE. *Fifth Edition.*

'Stories happily conceived and finely executed. There is strength and genius in Mr. Parker's style.'—*Daily Telegraph*.

MRS. FALCHION. *Fourth Edition.*

'A splendid study of character.'—*Athenæum*.

THE TRANSLATION OF A SAVAGE. *Second Edition.*

THE TRAIL OF THE SWORD. Illustrated. *Eighth Edition.*

'A rousing and dramatic tale. A book like this is a joy inexpressible.'—*Daily Chronicle*.

WHEN VALMOND CAME TO PONTIAC: The Story of a Lost Napoleon. *Fifth Edition.*

'Here we find romance—real, breathing, living romance. The character of Valmond is drawn unerringly.'—*Pall Mall Gazette*.

AN ADVENTURER OF THE NORTH: The Last Adventures of 'Fretty Pierre.' *Third Edition.*

'The present book is full of fine and moving stories of the great North.'—*Glasgow Herald*.

THE SEATS OF THE MIGHTY. Illustrated. *Thirteenth Edition*.

'Mr. Parker has produced a really fine historical novel.'—*Athenaeum*.

'A great book.'—*Black and White*.

THE BATTLE OF THE STRONG: a

Romance of Two Kingdoms. Illustrated. *Fourth Edition*.

'Nothing more vigorous or more human has come from Mr. Gilbert Parker than this novel.'—*Literature*.

THE POMP OF THE LAVIETTES.

Second Edition. 2s. 6d.

'Unforced pathos, and a deeper knowledge of human nature than he has displayed before.'—*Pall Mall Gazette*.

Arthur Morrison's Novels

Crown 8vo. 6s. each.

TALES OF MEAN STREETS. *Sixth Edition*.

'A great book. The author's method is amazingly effective, and produces a thrilling sense of reality. The writer lays upon us a master hand. The book is simply appalling and irresistible in its interest. It is humorous also; without humour it would not make the mark it is certain to make.'—*World*.

A CHILD OF THE JAGO. *Fourth Edition*.

'The book is a masterpiece.'—*Pall Mall Gazette*.

TO LONDON TOWN. *Second Edition*.

'This is the new Mr. Arthur Morrison, gracious and tender, sympathetic and human.'—*Daily Telegraph*.

CUNNING MURRELL.

'Admirable. . . . Delightful humorous relief . . . a most artistic and satisfactory achievement.'—*Spectator*.

THE HOLE IN THE WALL. *Third Edition*.

'A masterpiece of artistic realism. It has a finality of touch that only a master may command.'—*Daily Chronicle*.

'An absolute masterpiece, which any novelist might be proud to claim.'—*Graphic*.

'"The Hole in the Wall" is a masterly piece of work. His characters are drawn with amazing skill. Extraordinary power.'—*Daily Telegraph*.

Eden Phillpotts' Novels

Crown 8vo. 6s. each.

LYING PROPHETS.

CHILDREN OF THE MIST. *Fifth Edition*.

THE HUMAN BOY. With a Frontispiece.

Fourth Edition.

'Mr. Phillpotts knows exactly what school-boys do, and can lay bare their inmost thoughts; likewise he shows an all-pervading sense of humour.'—*Academy*.

SONS OF THE MORNING. *Second Edition*.

'A book of strange power and fascination.'—*Morning Post*.

THE STRIKING HOURS. *Second Edition*.

'Tragedy and comedy, pathos and humour, are blended to a nicety in this volume.'—*World*.

'The whole book is redolent of a fresher

and ampler air than breathes in the circumscribed life of great towns.'—*Spectator*.

THE RIVER. *Third Edition*.

'"The River" places Mr. Phillpotts in the front rank of living novelists.'—*Punch*.

'Since "Lorna Doone" we have had nothing so picturesque as this new romance.'—*Birmingham Gazette*.

'Mr. Phillpotts's new book is a masterpiece which brings him indisputably into the front rank of English novelists.'—*Pall Mall Gazette*.

'This great romance of the River Dart. The finest book Mr. Eden Phillpotts has written.'—*Morning Post*.

THE AMERICAN PRISONER. *Third Edition*.

S. Baring-Gould's Novels

Crown 8vo. 6s. each.

ARMINELL. *Fifth Edition*.

URITH. *Fifth Edition*.

IN THE ROAR OF THE SEA. *Seventh Edition*.

CHEAP JACK ZITA. *Fourth Edition*.

MARGERY OF QUETHER. *Third Edition*.

THE QUEEN OF LOVE. *Fifth Edition*.

JACQUETTA. *Third Edition*.

KITTY ALONE. *Fifth Edition*.

NOËML. Illustrated. *Fourth Edition*.

THE BROOM-SQUIRE. Illustrated.

Fourth Edition.

DARTMOOR IDYLLS.

THE PENNYCOMEQUICKS. *Third Edition.*
GUAVAS THE TINNER. Illustrated. *Second Edition.*
BLADYS. Illustrated. *Second Edition.*
DOMITIA. Illustrated. *Second Edition.*
PABO THE PRIEST.

WINIFRED. Illustrated. *Second Edition.*
THE FROBISHERS.
ROYAL GEORGIE. Illustrated.
MISS QUILLET. Illustrated.
LITTLE TU'PENNY. *A New Edition. 6d.*
CHRIS OF ALL SORTS.
IN DEWISLAND.

Robert Barr's Novels

Crown 8vo. 6s. each.

IN THE MIDST OF ALARMS. *Third Edition.*
 'A book which has abundantly satisfied us by its capital humour.'—*Daily Chronicle.*
THE MUTABLE MANY. *Second Edition.*
 'There is much insight in it, and much excellent humour.'—*Daily Chronicle.*

THE COUNTESS TEKLA. *Third Edition.*
 'Of these mediæval romances, which are now gaining ground "The Countess Tekla" is the very best we have seen.'—*Pall Mall Gazette.*
THE LADY ELECTRA.

Albanesi (E. Maria). **SUSANNAH AND ONE OTHER.** *Fourth Edition. Crown 8vo. 6s.*
THE BLUNDER OF AN INNOCENT. *Crown 8vo. 6s.*
CAPRICIOUS CAROLINE. *Crown 8vo. 6s.*
LOVE AND LOUISA. *Crown 8vo. 6s.*
PETER, A PARASITE. *Crown 8vo. 6s.*
Anstey (F.), Author of 'Vice Versâ.' **A BAYARD FROM BENGAL.** Illustrated by **BERNARD PARTRIDGE.** *Third Edition. Crown 8vo. 3s. 6d.*
Bachelor (Irving), Author of 'Eben Holden.' **DARREL OF THE BLESSED ISLES.** *Third Edition. Crown 8vo. 6s.*
Bagot (Richard), **A ROMAN MYSTERY.** *Third Edition. Crown 8vo. 6s.*
Balfour (Andrew), **VENGEANCE IS MINE.** Illustrated. *Crown 8vo. 1s. net.*
Balfour (M. G.), **THE FALL OF THE SPARROW.** *Crown 8vo. 6s.*
Baring-Gould (E.), See page 34 and 1s. Novels.
Barlow (Jane), **THE LAND OF THE SHAMROCK.** *Crown 8vo. 6s.*
FROM THE EAST UNTO THE WEST. *Crown 8vo. 1s. net.*
Barr (Robert), See page 35 and 1s. Novels.
Begbie (Harold), **THE ADVENTURES OF SIR JOHN SPARROW.** *Crown 8vo. 6s.*
Belloc (Hilaire) **M. R. BURDEN, DEALER IN HARDWARE.** With 36 Illustrations by G. K. CHESTERTON. *Crown 8vo. 6s.*
Benson (E. F.), **DODO: A Detail of the Day.** *Crown 8vo. 6s.*
THE CAPSINA. *Crown 8vo. 1s. net.*
Benson (Margaret), **SUBJECT TO VANITY.** *Crown 8vo. 3s. 6d.*
Besant (Sir Walter), **A FIVE YEARS' TRYST, and Other Stories.** *Crown 8vo. 1s. net.*

Bowles (G. Stewart), **A STRETCH OFF THE LAND.** *Crown 8vo. 6s.*
Bullock (Shan. F.), **THE SQUIREEN.** *Crown 8vo. 6s.*
THE RED LEAGUERS. *Crown 8vo. 6s.*
Burton (J. Bloundelle), **THE YEAR ONE: A Page of the French Revolution.** Illustrated. *Crown 8vo. 6s.*
DENOUNCED. *Crown 8vo. 6s.*
THE CLASH OF ARMS. *Crown 8vo. 6s.*
ACROSS THE SALT SEAS. *Crown 8vo. 1s. net.*
THE FATE OF VALSEC. *Cr. 8vo. 6s.*
A BRANDED NAME. *Crown 8vo. 6s.*
Capes (Bernard), Author of 'The Lake of Wine.' **THE EXTRAORDINARY CONFESIONS OF DIANA PLEASE.** *Crown 8vo. 6s.*
Cheaney (Weatherby), **THE BAPTIST RING.** *Crown 8vo. 6s.*
THE TRAGEDY OF THE GREAT EMERALD. *Crown 8vo. 6s.*
THE MYSTERY OF A BUNGALOW. *Crown 8vo. 6s.*
Clifford (Hugh), **A FREE LANCE OF TO-DAY.** *Crown 8vo. 6s.*
Cobb (Thomas), **A CHANGE OF FACE.** *Crown 8vo. 6s.*
Cobban (J. Maclaren), **THE KING OF ANDAMAN: A Saviour of Society.** *Crown 8vo. 6s.*
WILT THOU HAVE THIS WOMAN? *Crown 8vo. 6s.*
THE ANGEL OF THE COVENANT. *Crown 8vo. 6s.*
Corbett (Julian), **A BUSINESS IN GREAT WATERS.** *Crown 8vo. 6s.*
Corelli (Marie), See page 32.
Cotes (Mrs. Everard), See S. J. DUNCAN.
Crane (Stephen) and Barr (Robert), **THE O'RUDDY.** *Crown 8vo. 6s.*
Crockett (S. R.), Author of 'The Raiders,' etc. **LOCHINVAR.** Illustrated. *Second Edition. Crown 8vo. 6s.*
THE STANDARD BEARER. *Cr. 8vo. 6s.*

- Croker (B. M.).** ANGEL. *Third Edition.*
Crown 8vo. 6s.
PEGGY OF THE BARTONS. *Fifth Edition.* *Crown 8vo. 6s.*
A STATE SECRET. *Third Edition.*
Crown 8vo. 3s. 6d.
JOHANNA. *Second Edition.* *Cr. 8vo. 6s.*
THE HAPPY VALLEY. *Crown 8vo. 6s.*
- Doyle (A. Conan),** Author of 'Sherlock Holmes,' 'The White Company,' etc.
ROUND THE RED LAMP. *Ninth Edition.* *Crown 8vo. 6s.*
- Duncan (Sara Jeannette)** (Mrs. Everard Cotes), Author of 'A Voyage of Consolation.'
THOSE DELIGHTFUL AMERICANS. Illustrated. *Third Edition.* *Crown 8vo. 6s.*
THE PATH OF A STAR. Illustrated. *Second Edition.* *Crown 8vo. 6s.*
THE POOL IN THE DESERT. *Crown 8vo. 6s.*
A VOYAGE OF CONSOLATION. *Cr. 8vo. 3s. 6d.*
- Fenn (G. Manville).** AN ELECTRIC SPARK. *Crown 8vo. 6s.*
A DOUBLE KNOT. *Crown 8vo. 2s. 6d.*
- Findlater (J. H.).** THE GREEN GRAVES OF BALGOWRIE. *Fourth Edition.* *Crown 8vo. 6s.*
A DAUGHTER OF STRIFE. *Crown 8vo. 1s. net.*
- Findlater (Mary).** OVER THE HILLS. *Second Edition.* *Crown 8vo. 6s.*
BETTY MUSGRAVE. *Second Edition.* *Crown 8vo. 6s.*
A NARROW WAY. *Third Edition.* *Crown 8vo. 6s.*
THE ROSE OF JOY. *Second Edition.* *Crown 8vo. 6s.*
- Pitastephon (Gerald).** MORE KIN THAN KIND. *Crown 8vo. 6s.*
- Fletcher (J. S.).** THE BUILDERS. *Crown 8vo. 6s.*
LUCIAN THE DREAMER. *Crown 8vo. 6s.*
DAVID MARCH. *Crown 8vo. 6s.*
- Francis (M. E.).** MISS ERIN. *Second Edition.* *Crown 8vo. 1s. net.*
- Fraser (Mrs. Hugh),** Author of 'The Stolen Emperor.'
THE SLAKING OF THE SWORD. *Crown 8vo. 6s.*
- Gallon (Tom),** Author of 'Kiddy.'
RICK-ERBY'S FOLLY. *Crown 8vo. 6s.*
- Gaunt (Mary).** DEADMAN'S. *Crown 8vo. 6s.*
THE MOVING FINGER. *Crown 8vo. 3s. 6d.*
- Gerard (Dorothea),** Author of 'Lady Baby.'
THE CONQUEST OF LONDON. *Second Edition.* *Crown 8vo. 6s.*
HOLY MATRIMONY. *Second Edition.* *Crown 8vo. 6s.*
- THINGS THAT HAVE HAPPENED.** *Crown 8vo. 6s.*
MADE OF MONEY. *Crown 8vo. 6s.*
THE BRIDGE OF LIFE. *Cr. 8vo. 6s.*
- Gerard (Emily).** THE HERONS' TOWER. *Crown 8vo. 6s.*
- Glichrist (B. Murray).** WILLOW-BRAKE. *Crown 8vo. 6s.*
- Gissing (George),** Author of 'Demos,' 'In the Year of Jubilee,' etc.
THE TOWN TRAVELLER. *Second Edition.* *Crown 8vo. 6s.*
THE CROWN OF LIFE. *Crown 8vo. 6s.*
- Glanville (Ernest).** THE DESPATCH RIDER. *Crown 8vo. 3s. 6d.*
THE INCA'S TREASURE. Illustrated. *Crown 8vo. 3s. 6d.*
- Gleig (Charles).** BUNTER'S CRUISE. Illustrated. *Crown 8vo. 3s. 6d.*
- Goss (G. F.).** THE REDEMPTION OF DAVID CORSON. *Third Edition.* *Crown 8vo. 6s.*
- Harrison (Mrs. Burton).** A PRINCESS OF THE HILLS. Illustrated. *Crown 8vo. 6s.*
- Herbertson (Agnes G.).** PATIENCE DEAN. *Crown 8vo. 6s.*
- Hichens (Robert),** Author of 'Flames,' etc.
THE PROPHET OF BERKELEY SQUARE. *Second Ed.* *Crown 8vo. 6s.*
TONGUES OF CONSCIENCE. *Second Edition.* *Crown 8vo. 6s.*
FELIX. *Fourth Edition.* *Crown 8vo. 6s.*
THE WOMAN WITH THE FAN. *Fifth Edition.* *Cr. 8vo. 6s.*
BYEWAYS. *Crown 8vo. 3s. 6d.*
THE GARDEN OF ALLAH. *Crown 8vo. 6s.*
- Hobbes (John Oliver),** Author of 'Robert Orange.'
THE SERIOUS WOOING. *Crown 8vo. 6s.*
- Hope (Anthony).** See page 32.
- Hough (Emerson).** THE MISSISSIPPI BUBBLE. Illustrated. *Crown 8vo. 6s.*
- Housman (Clemence).** SCENES FROM THE LIFE OF AGLOVALE. Illustrated. *Crown 8vo. 3s. 6d.*
- Hunt (Violet).** THE HUMAN INTEREST. *Crown 8vo. 6s.*
- Hyne (C. J. Cutcliffe),** Author of 'Captain Kettle.'
MR. HORROCKS, PURSER. *Third Edition.* *Crown 8vo. 6s.*
- Jacobs (W. W.).** See page 33.
- James (Henry),** Author of 'What Maisie Knew.'
THE SOFT SIDE. *Second Edition.* *Crown 8vo. 6s.*
THE BETTER SORT. *Crown 8vo. 6s.*
THE AMBASSADORS. *Second Edition.* *Crown 8vo. 6s.*
THE GOLDEN BOWL. *Crown 8vo. 6s.*
- Janson (Gustaf).** ABRAHAM'S SACRIFICE. *Crown 8vo. 6s.*

- Lawless (Hon. Emily).** TRAITS AND CONFIDENCES. *Crown 8vo. 6s.*
MELCHO. *Crown 8vo. 1s. net.*
- Lawson (Harry),** Author of 'When the Billy Boik.' CHILDREN OF THE BUSH. *Crown 8vo. 6s.*
- London (Annie).** A WOMAN OF SENTIMENT. *Crown 8vo 16s.*
- Linton (E. Lynn).** THE TRUE HISTORY OF JOSHUA DAVIDSON, Christian and Communist. *Twelfth Edition. Medium 8vo. 6d.*
- Long (J. Luther),** Co-Author of 'The Darling of the Gods.' MADAME BUTTERFLY. *Crown 8vo. 6s.*
 SIXTY JANE. *Crown 8vo. 6s.*
- Lorimer (Norma).** MIRRYPANN. *Crown 8vo. 6s.*
 JOSIAH'S WIFE. *Crown 8vo. 6s.*
- Lyall (Edna).** DERRICK VAUGHAN, NOVELIST. *42nd Thousand. Crown 8vo. 3s. 6d.*
- McCarthy (Justin E.),** Author of 'If I were King.' THE LADY OF LOYALTY HOUSE. *Crown 8vo. 6s.*
- Mackie (Pauline Bradford).** THE VOICE IN THE DESERT. *Crown 8vo. 6s.*
- Macnaughtan (E.).** THE FORTUNE OF CHRISTINA MACNAB. *Third Edition. Crown 8vo. 6s.*
- Malet (Lucas).** See page 33.
- Mann (Mrs. M. E.).** OLIVIA'S SUMMER. *Second Edition. Crown 8vo. 6s.*
 A LOST ESTATE. *A New Edition. Crown 8vo. 6s.*
 THE PARISH OF HILBY. *A New Edition. Crown 8vo. 6s.*
 THE PARISH NURSE. *Crown 8vo. 6s.*
 GRAN'MA'S JANE. *Crown 8vo. 6s.*
 MRS. PETER HOWARD. *Cr. 8vo. 6s.*
 A WINTER'S TALE. *Crown 8vo. 6s.*
 THERE WAS ONCE A PRINCE. Illustrated. *Crown 8vo. 3s. 6d.*
 WHEN ARNOLD COMES HOME. Illustrated. *Crown 8vo. 3s. 6d.*
- Marriott (Charles),** Author of 'The Column.' GENEVRA. *Crown 8vo. 6s.*
- Marsh (Richard).** MARVELS AND MYSTERIES. *Crown 8vo. 6s.*
 THE TWICKENHAM PEERAGE. *Second Edition. Crown 8vo. 6s.*
 A METAMORPHOSIS. *Crown 8vo. 6s.*
 GARNERED. *Crown 8vo. 6s.*
 A DUEL. *Crown 8vo. 6s.*
- Mason (A. E. W.),** Author of 'The Courtship of Morrice Buckler,' 'Miranda of the Balcony,' etc. CLEMENTINA. Illustrated. *Crown 8vo. Second Edition. 6s.*
- Mathers (Helen),** Author of 'Comin' thro' the Rye.' HONEY. *Fourth Edition. Crown 8vo. 6s.*
 GRIFF OF GRIFFITHSCOURT. *Crown 8vo. 6s.*
 THE FERRYMAN. *Crown 8vo. 6s.*
- Meads (L. T.).** DRIFT. *Crown 8vo. 6s.*
 RESURGAM. *Crown 8vo. 6s.*
- 'Miss Molly' (The Author of).** THE GREAT RECONCILER. *Crown 8vo. 6s.*
- Mitford (Bertram).** THE SIGN OF THE SPIDER. Illustrated. *Sixth Edition. Crown 8vo. 3s. 6d.*
 IN THE WHIRL OF THE RISING. *Second Edition. Crown 8vo. 6s.*
- Montresor (F. F.),** Author of 'Into the Highways and Hedges.' THE ALIEN. *Third Edition. Crown 8vo. 6s.*
- Morrison (Arthur).** See page 34.
- Nesbit (E.),** (Mrs. E. Bland). THE RED HOUSE. Illustrated. *Fourth Edition. Crown 8vo. 6s.*
 THE LITERARY SENSE. *Cr. 8vo. 6s.*
- Norris (W. E.).** THE CREDIT OF THE COUNTY. Illustrated. *Second Edition. Crown 8vo. 6s.*
 THE EMBARRASSING ORPHAN. *Crown 8vo. 6s.*
 HIS GRACE. *Third Edition. Cr. 8vo. 6s.*
 THE DESPOTIC LADY. *Crown 8vo. 6s.*
 CLARISSA FURIOSA. *Crown 8vo. 6s.*
 AN OCTAVE. *Second Edition. Crown 8vo. 6s.*
 NIGEL'S VOCATION. *Crown 8vo. 6s.*
 JACK'S FATHER. *Crown 8vo. 2s. 6d.*
 LORD LEONARD THE LUCKLESS. *Crown 8vo. 1s. net.*
- Olyphant (Mrs.).** THE TWO MARYS. *Crown 8vo. 6s.*
 THE LADY'S WALK. *Crown 8vo. 6s.*
 THE PRODIGALS. *Crown 8vo. 1s. net.*
- Ollivant (Alfred).** OWD BOB, THE GREY DOG OF KENMUIR. *Sixth Edition. Crown 8vo. 6s.*
- Oppenheim (E. Phillips).** MASTER OF MEN. *Third Edition. Crown 8vo. 6s.*
- Oxenham (John),** Author of 'Barbe of Grand Bayou.' A WEAVER OF WEBS. *Crown 8vo. 6s.*
- Pain (Barry).** THREE FANTASIES. *Crown 8vo. 1s.*
 LINDLEY KAYS. *Crown 8vo. 6s.*
- Parker (Gilbert).** See page 33.
- Pemberton (Max).** THE FOOTSTEPS OF A THRONE. Illustrated. *Second Edition. Crown 8vo. 6s.*
 I CROWN THEE KING. With Illustrations by Frank Dadd and A. Forrester. *Crown 8vo. 6s.*
- Penny (Mrs. F. E.).** A MIXED MARRIAGE. *Crown 8vo. 1s. net.*
- Phillipotts (Eden).** See page 34.
- Pickthall (Marmaduke).** SAID THE FISHERMAN. *Fourth Edition. Crown 8vo. 16s.*
- Pryce (Richard).** THE QUIET MRS. FLEMING. *Crown 8vo. 3s. 6d.*
- 'Q.'** Author of 'Dead Man's Rock.' THE WHITE WOLF. *Second Edition. Crown 8vo. 6s.*

- Queux (W. le).** THE HUNCHBACK OF WESTMINSTER. *Second Edition.* Crown 8vo. 6s.
THE CLOSED BOOK. Crown 8vo. 6s.
Rhys (Grace). THE WOOING OF SHEILA. *Second Edition.* Crown 8vo. 6s.
 THE PRINCE OF LISNOVER. Crown 8vo. 6s.
Rhys (Grace) and Another. THE DIVERTED VILLAGE. With Illustrations by DOROTHY GWYN JEFFREYS. Crown 8vo. 6s.
Ridge (W. Pett). LOST PROPERTY. *Second Edition.* Crown 8vo. 6s.
 SECRETARY TO BAYNE, M.P. Crown 8vo. 6s.
 ERB. *Second Edition.* Crown 8vo. 6s.
 A SON OF THE STATE. Crown 8vo. 3s. 6d.
 A BREAKER OF LAWS. Cr. 8vo. 3s. 6d.
 MRS. GALER'S BUSINESS. Crown 8vo. 6s.
Ritchie (Mrs. David G.). THE TRUTHFUL LIAR. Crown 8vo. 6s.
Roberts (G. G. D.). THE HEART OF THE ANCIENT WOOD. Crown 8vo. 3s. 6d.
Russell (W. Clark). MY DANISH SWEET-HEART. Illustrated. *Fourth Edition.* Crown 8vo. 6s.
 ABANDONED. *Second Edition.* Crown 8vo. 6s.
Sergeant (Adeline). Author of 'The Story of a Penitent Soul.' THE MASTER OF BEECHWOOD. Crown 8vo. 6s.
 BARBARA'S MONEY. *Second Edition.* Crown 8vo. 6s.
 ANTHEA'S WAY. Crown 8vo. 6s.
 THE YELLOW DIAMOND. *Second Edition.* Crown 8vo. 6s.
 UNDER SUSPICION. Crown 8vo. 6s.
 THE LOVE THAT OVERCAME. Crown 8vo. 6s.
 THE ENTHUSIAST. Crown 8vo. 6s.
 ACCUSED AND ACCUSER. Crown 8vo. 6s.
 THE PROGRESS OF RACHEL. Cr. 8vo. 6s.
Shannon (W. F.). THE MESS DECK. Crown 8vo. 3s. 6d.
 JIM TWELVES. *Second Edition.* Crown 8vo. 3s. 6d.
Sonnichsen (Albert). DEEP SEA VAGABONDS. Crown 8vo. 6s.
Strain (E. E.). ELMSLIE'S DRAG-NET. Crown 8vo. 6s.
Stringer (Arthur). THE SILVER POPPY. Crown 8vo. 6s.
Sutherland (Duchess of). ONE HOUR AND THE NEXT. *Third Edition.* Crown 8vo. 1s. net.
Swan (Annie). LOVE GROWN COLD. *Second Edition.* Crown 8vo. 1s. net.
Swift (Benjamin). SIREN CITY. Crown 8vo. 6s.
Tanqueray (Mrs. R. M.). THE ROYAL QUAKER. Crown 8vo. 6s.
Thompson (Vance). SPINNERS OF LIFE. Crown 8vo. 6s.
Waineman (Paul). A HEROINE FROM FINLAND. Crown 8vo. 1s. net.
 BY A FINNISH LAKE. Crown 8vo. 6s.
 THE SONG OF THE FOREST. Crown 8vo. 6s.
Watson (H. B. Marriott). ALARMS AND EXCURSIONS. Cr. 8vo. 6s.
 CAPTAIN FORTUNE. Cr. 8vo. 6s.
Wells (H. G.). THE SEA LADY. Crown 8vo. 6s.
Weyman (Stanley). Author of 'A Gentleman of France.' UNDER THE RED ROBE. With Illustrations by R. C. WOODVILLE. *Eighteenth Edition.* Crown 8vo. 6s.
White (Stewart E.). Author of 'The Blazed Trail.' CONJUROR'S HOUSE. A Romance of the Free Trail. *Second Edition.* Crown 8vo. 6s.
Williamson (Mrs. C. N.). Author of 'The Barnstormers.' PAPA. *Second Edition.* Crown 8vo. 6s.
 THE ADVENTURE OF PRINCESS SLYVIA. Crown 8vo. 3s. 6d.
 THE WOMAN WHO DARED. Crown 8vo. 6s.
 THE SEA COULD TELL. *Second Edition.* Crown 8vo. 6s.
Williamson (C. N. and A. M.). THE LIGHTNING CONDUCTOR: Being the Romance of a Motor Car. Illustrated. *Sixth Edition.* Crown 8vo. 6s.
 THE PRINCESS PASSES. Cr. 8vo. 6s.
Yeats (S. Levett). ORRAIN. Crown 8vo. 6s.

Boys and Girls, Books for

Crown 8vo. 3s. 6d.

- THE ICELANDER'S SWORD. By S. Baring-Gould.
 ONLY A GUARD-ROOM DOG. By Edith E. Cuthell.
 THE DOCTOR OF THE JULIET. By Harry Collingwood.
 MASTER ROCKAFELLAR'S VOYAGE. By W. Clark Russell.
 SYD BELTON: Or, the Boy who would not go to Sea By G. Manville Fenn.
 THE RED GRANGE. By Mrs. Molesworth.
 A GIRL OF THE PEOPLE. By L. T. Meade.
 HEPHY GIPSY. By L. T. Meade. ar. 6d.
 THE HONOURABLE MISS. By L. T. Meade.

Dumas, The Novels of Alexandre

Price 6s. Double Volume, 1s.

THE THREE MUSKETEERS. With a long Introduction by Andrew Lang. Double volume.
 THE PRINCE OF THIEVES. *Second Edition.*
 ROBIN HOOD. A Sequel to the above.
 THE CORSICAN BROTHERS.
 GEORGES.
 CROP-EARED JACQUOT.
 TWENTY YEARS AFTER. Double volume.
 AMAURY.
 THE CASTLE OF EPFSTEIN.
 THE SNOWBALL.
 CECILE; OR, THE WEDDING GOWN.
 ACTE.
 THE BLACK TULIP.
 THE VICOMTE DE BRAGELONNE.
 THE CONVICT'S SON.
 THE WOLF-LEADER.
 NANON; OR, THE WOMEN'S WAR.
 PAULINE; MURAT; AND PASCAL BRUNO.
 THE ADVENTURES OF CAPTAIN PAMPHILE.
 FERNANDE.
 GABRIEL LAMBERT.
 THE REMINISCENCES OF ANTONY.
 CATHERINE BLUM.
 THE CHEVALIER D'HARMENTAL.

CONSCIENCE

Illustrated Edition.

THE THREE MUSKETEERS. Illustrated in Colour by Frank Adams.
 THE PRINCE OF THIEVES. Illustrated in Colour by Frank Adams.
 ROBIN HOOD THE OUTLAW. Illustrated in Colour by Frank Adams.
 THE CORSICAN BROTHERS. Illustrated in Colour by A. M. M'Lellan.
 FERNANDE. Illustrated in Colour by Munro Orr.
 THE BLACK TULIP. Illustrated in Colour by A. Orr.
 ACTE. Illustrated in Colour by Gordon Brown.
 GEORGES. Illustrated in Colour by Munro Orr.
 THE CASTLE OF EPFSTEIN. Illustrated in Colour by A. Orr.
 TWENTY YEARS AFTER. Illustrated in Colour by Frank Adams.
 THE SNOWBALL AND SULTANETTA. Illustrated in Colour by Frank Adams.
 THE VICOMTE DE BRAGELONNE. Illustrated in Colour by Frank Adams.
 AMAURY. Illustrated in Colour by Gordon Brown.
 CROP-EARED JACQUOT. Illustrated in Colour by Gordon Brown.

Methuen's Universal Library

EDITED BY SIDNEY LEE. In Sixpenny Volumes.

MESSRS. METHUEN are preparing a new series of reprints containing both books of classical repute, which are accessible in various forms, and also some rarer books, of which no satisfactory edition at a moderate price is in existence. It is their ambition to place the best books of all nations, and particularly of the Anglo-Saxon race, within the reach of every reader. All the great masters of Poetry, Drama, Fiction, History, Biography, and Philosophy will be represented. Mr. Sidney Lee will be the General Editor of the Library, and he will contribute a Note to each book.

The characteristics of METHUEN'S UNIVERSAL LIBRARY are five:—

1. SOUNDNESS OF TEXT. A pure and unabridged text is the primary object of the series, and the books will be carefully reprinted under the direction of competent scholars from the best editions. In a series intended for popular use not less than for students, adherence to the old spelling would in many cases leave the matter unintelligible to ordinary readers, and, as the appeal of a classic is universal, the spelling has in general been modernised.
2. COMPLETENESS. Where it seems advisable, the complete works of such masters as Milton, Bacon, Ben Jonson and Sir Thomas Browne will be given. These will be issued in separate volumes, so that the reader who does not desire all the works of an author will have the opportunity of acquiring a single masterpiece.
3. CHEAPNESS. The books will be well printed on good paper at a price which on the whole is without parallel in the history of publishing. Each volume will contain from 100 to 350 pages, and will be issued in paper covers, Crown 8vo, at Sixpence net.
4. CLEARNESS OF TYPE. The type will be a very legible one.
5. SIMPLICITY. There will be no editorial matter except a short biographical and bibliographical note by Mr. Sidney Lee at the beginning of each volume.

Where it is possible, each separate book will be issued in one volume, but the longer ones must be divided into several volumes. The volumes may also be obtained in cloth at One Shilling net, and where a single book is issued in several Sixpenny volumes it may be obtained in cloth in a double or treble volume. Thus GIL BLAS may be bought in two Sixpenny volumes, or in one cloth volume at 1s. 6d. net, and SHAKESPEARE will be given in ten Sixpenny volumes, or in five cloth volumes at 1s. 6d. each.

The Library will be issued at regular intervals after the publication of the first six books, all of which will be published together. Due notice will be given of succeeding issues. The order of publication will be arranged to give as much variety of subject as possible, and the volumes composing the complete works of an author will be issued at convenient intervals.

The early Books are in the Press.

Novelist, The

MESSRS. METHUEN are issuing under the above general title a Monthly Series of Novels by popular authors at the price of Sixpence. Each number is as long as the average Six Shilling Novel. The first numbers of 'THE NOVELIST' are as follows:—

1. DEAD MEN TELL NO TALES. By E. W. Hornung.
2. JENNIE BAXTER, JOURNALIST. By Robert Barr.
3. THE INCA'S TREASURE. By Ernest Gianville.
4. A SON OF THE STATE. By W. Pett Ridge.
5. FURZE BLOOM. By S. Baring-Gould.
6. BUNTER'S CRUISE. By C. Gleig.
7. THE GAY DECEIVERS. By Arthur Moore.
8. PRISONERS OF WAR. By A. Boyson Weekes.
9. A FLASH OF SUMMER. By Mrs. W. K. Clifford.
10. VELET AND LAAGER; Tales of the Transvaal. By E. S. Valentine.
11. THE NIGGER KNIGHTS. By F. Norreys Connel.
12. A MARRIAGE AT SEA. By W. Clark Russell.
13. THE POMP OF THE LAVIETTES. By Gilbert Parker.
14. A MAN OF MARK. By Anthony Hope.
15. THE CARISSIMA. By Lucas Malet.
16. THE LADY'S WALK. By Mrs. Oliphant.
17. DERRICK VAUGHAN. By Edna Lyall.
18. IN THE MIDST OF ARMS. By Robert Barr.
19. HIS GRACE. By W. E. Norris.
20. DODO. By E. F. Benson.
21. CHEAP JACK ZITA. By S. Baring-Gould.
22. WHEN VALMOND CAME TO PONTIAC. By Gilbert Parker.
23. THE HUMAN BOY. By Eden Philipotts.
24. THE CHRONICLES OF COUNT ANTONIO. By Anthony Hope.
25. BY STROKE OF SWORD. By Andrew Balfour.
26. KITTY ALONE. By S. Baring-Gould.
27. GILES INGILBY. By W. E. Norris.
28. URTH. By S. Baring-Gould.
29. THE TOWN TRAVELLER. By George Gissing.
30. MR. SMITH. By Mrs. Walford.
31. A CHANGE OF AIR. By Anthony Hope.
32. THE KLOOF BRIDE. By Ernest Gianville.
33. ANGEL. By B. M. Croker.
34. A COUNSEL OF IMPROVEMENT. By Lucas Malet.
35. THE BABY'S GRANDMOTHER. By Mrs. Walford.
36. THE COUNTESS TERLA. By Robert Barr.
37. DRIFT. By L. T. Meade.
38. THE MASTER OF BRERWOOD. By Adeline Sergeant.
39. CLEMENTINA. By A. E. W. Mason.
40. THE ALIEN. By F. F. Montresor.
41. THE BROOM SQUIRE. By S. Baring-Gould.
42. HONEY. By Helen Mathers.
43. THE FOOTSTEPS OF A THRONE. By Max Pemberton.
44. ROUND THE RED LAMP. By A. Conan Doyle.
45. LOST PROPERTY. By W. Pett Ridge.
46. THE TWICKENHAM FEBRERAGE. By Richard Marsh.
47. HOLY MATRIMONY. By Dorothea Gerard.
48. THE SIGN OF THE SPIDER. By Bertram Mitford.
49. THE RED HOUSE. By E. Nesbit.
50. THE HOLE IN THE WALL. By A. Morrison.
51. A ROMAN MYSTERY. By Richard Bagot.
52. THE CREDIT OF THE COUNTY. By W. E. Norris.
53. A MOMENT'S ERROR. By A. W. Marchant.
54. PHROSO. By Anthony Hope.
55. I CROWN THEE KING. By Max Pemberton.
56. JOHANNA. By B. M. Croker.
57. BARBARA'S MONEY. By Adeline Sergeant.
58. A NEWSPAPER GIRL. By Mrs. C. N. Williamson.
59. THE GODDESS. By Richard Marsh.
60. MRS. PETER HOWARD. By M. E. Mann.

Sixpenny Library

- THE MATABELE CAMPAIGN. By Major-General Baden-Powell.
- THE DOWNFALL OF PREMPEH. By Major-General Baden-Powell.
- MY DAME'S SWEETHEART. By W. Clark Russell.
- IN THE ROAR OF THE SEA. By S. Baring-Gould.
- PEGGY OF THE BARTONS. By B. M. Croker.
- THE GREEN GRAVES OF BALGOWRIE. By Jane H. Fendler.
- THE STOLEN BACILLUS. By H. G. Wells.
- MATTHEW AUSTIN. By W. E. Norris.
- THE CONQUEST OF LONDON. By Dorothea Gerard.
- A VOYAGE OF CONSOLATION. By Sara J. Duncan.
- THE MUTABLE MANY. By Robert Barr.
- HEN HUR. By General Lew Wallace.
- SIR ROBERT'S FORTUNE. By Mrs. Oliphant.
- THE FAIR GOD. By General Lew Wallace.
- CLARISSA FURIOSA. By W. E. Norris.
- CRANFORD. By Mrs. Gaskell.
- NOEMI. By S. Baring-Gould.
- THE THRONE OF DAVID. By J. H. Ingraham.
- CROSS THE SALT SEAS. By J. Blundelle Burton.
- THE MILL ON THE FLOSS. By George Elliot.
- PETER SIMPLE. By Captain Marryat.
- MARY BARTON. By Mrs. Gaskell.
- PRIDE AND PREJUDICE. By Jane Austen.
- NORTH AND SOUTH. By Mrs. Gaskell.
- JACOB FAITHFUL. By Captain Marryat.
- SHIRLEY. By Charlotte Brontë.
- FAIRY TALES RE-TOLD. By S. Baring-Gould.
- THE TRUE HISTORY OF JOSHUA DAVIDSON. By Mrs. Lynn Linton.
- A STATE SECRET. By B. M. Croker.
- SAM'S SWEETHEART. By Helen Mathers.
- HANDLEY CROSS. By R. S. Surtees.
- ANNE MAULEVERER. By Mrs. Caffyn.
- THE ADVENTURERS. By H. B. Marriott Watson.
- DANTE'S DIVINE COMEDY. Translated by H. F. Cary.
- THE CEDAR STAR. By M. E. Mann.
- MASTER OF MEN. By E. P. Oppenheim.
- THE TRAIL OF THE SWORD. By Gilbert Parker.
- THOSE DELIGHTFUL AMERICANS. By Mrs. Cotes.
- MR. SPONGE'S SPORTING TOUR. By R. S. Surtees.
- ASK MAMMA. By R. S. Surtees.
- GRIMM'S FAIRY STORIES. Illustrated by George Cruikshank.
- GEORGE AND THE GENERAL. By W. Pett Ridge.
- THE JOSS. By Richard Marsh.
- MISER HOADLEY'S SECRET. By A. W. Marchmont.

This book should be returned to the Library on or before the last date stamped below.

THE BORROWER WILL BE CHARGED AN OVERDUE FEE IF THIS BOOK IS NOT RETURNED TO THE LIBRARY ON OR BEFORE THE LAST DATE STAMPED BELOW. NON-RECEIPT OF OVERDUE NOTICES DOES NOT EXEMPT THE BORROWER FROM OVERDUE FEES.

~~CANCELLED~~
FEB 25 1984
FEB 25 1984
109 9802

WIDENER
CANCELLED^R
NOV 11 1987
179210

~~WIDENER
BOOK DUE
NOV 11 1987~~

SEP 10 1993
DUE

CANCELLED^R
DEC 20 1997
177136

